SASQUATCH

Legend Meets Science

JEFF MELDRUM

SASQUATCH

SASQUATCH

LEGEND MEETS SCIENCE

JEFF MELDRUM

A TOM DOHERTY ASSOCIATES BOOK / NEW YORK

SASQUATCH: LEGEND MEETS SCIENCE

Copyright © 2006 by BooBam Ventures, Inc.

Foreword copyright © 2006 by George B. Schaller All rights reserved, including the right to reproduce this book, or portions thereof, in any form.

This book is printed on acid-free paper.

Edited by Moshe Feder

A Forge Book
Published by Tom Doherty Associates, LLC
175 Fifth Avenue
New York, NY 10010

www.tor.com

Forge® is a registered trademark of Tom Doherty Associates, LLC.

Library of Congress Cataloging-in-Publication Data Meldrum, Jeff.

Sasquatch : legend meets science / Jeff Meldrum.—1st ed.
p. cm.
Includes bibliographical references and index.
ISBN-13: 978-0-765-31216-7
ISBN-10: 0-765-31216-6
1. Sasquatch. I. Title.
QL89.2.S2M45 2006
001.944—dc22

2006004267

Printed in the United States of America 0 9 8 7 6 5 4 3 2

Acknowledgments

This project is indebted to Doug Hajicek and all at Whitewolf Entertainment for undertaking the production of a thoughtful documentary that presented the evidence to a discerning audience and to the Discovery Channel for raising the bar in the treatment and consideration of this subject matter; to Michael Hsu for sharing our mutual desire to see a companion volume grow out of that creation and inviting me to author it.

The scope of this book exceeds the experience and expertise of any one person. I am grateful for the objectivity and open-mindedness of the featured scientists and their willingness to follow the data wherever it might lead them along a path that few have deigned to tread: George Schaller, Daris Swindler, Doug Divine, Bob Francis, Bill Taft, Carl Anderson, Reuben Steindorf, Andrew Nelson, John Bindernagel, Lynn Rogers, Loyd Benson, Jimmy Chilcutt, Henner Fahrenbach, and Craig Newton. To this list I would like to add the name of Richard Greenwell, cryptozoologist extraordinaire, who once asked me what I, as a primatologist, thought of sasquatch. Special recognition is afforded the several members of the North American Ape Project, especially Ron Brown, LeRoy Fish, Derek Randies, John Pickering, Rick Noll, Owen Caddy, Brian Smith, John Mionczynski, and Julie Davis.

As one who might be considered a member of the second generation of researchers pursuing this question, I must acknowledge the pioneering efforts of the first watch, who have dedicated so much of themselves toward the resolution of this intriguing natural mystery, and have so generously shared their hard-won experiences with me personally, in particular Grover Krantz, John Green, Bob Titmus, Roger and Patricia Patterson, Bob Gimlin, Wes Sumerlin, Bill Laughery, and Vance Orchard. Many members of the contemporary "Bigfoot community," too numerous to name individually, have contributed immeasurably through their shared experiences, photographs, casts, and samples. Numerous other professional colleagues engaged in scintillating discussions about the subject and kindly permitted the use of a number of the illustrations

that are included herein.

A number of individuals and institutions have funded aspects of my own research directed at this question, both in the laboratory and in the field, including Brant Steigers, Ken and Linda Steigers, Jack Mayfield, Richard and Thomas Stepp, and the Idaho State University Research Committee.

Exceptional thanks are extended to George Schaller for graciously providing the foreword to this book and for lending additional expressions of encouragement. Also, to Jane Goodall for affording the time to read and endorse this book and to hazard an open position of acknowledgment of the value and need for this inquiry. Other valued colleagues who have read and commented upon the manuscript include Russell Mittermeier, Peter Matthiessen, Walter Hartwig, Roderick Sprague, Daris Swindler, Esteban Sarmiento, and John Fleagle. Significant encouragement was received in the early stages of this project from Peter Nevraumont. For their ongoing guidance and assistance, particular recognition goes to members of the editorial team at Forge: Moshe Feder and Denis Wong in editorial, and Barbara Cohen in legal.

Special acknowledgment goes to my wife, Terri, for support and indulgence of my preoccupations and to our six sons, Colin, Sean, Devin, Trevor, Kayd, and Brendon, for keeping me young at heart in spite of the encroaching gray.

Dedicated to the memory of the pioneering research of
Grover S. Krantz (1931-2002)

(Courtesy of Rick Noll)

Contents

Foreword by George B. Schaller

INTRODUCTION

1. THE SCIENCE OF HIDDEN ANIMALS: CRYPTOZOOLOGY

2. WOODEN FEET AND FUR SUITS: RAY WALLACE AT BLUFF CREEK

3. WILDMAN OF THE WOODS: NATIVE AMERICAN TRADITIONAL KNOWLEDGE

4. THE GIANT APE OF THE ORIENT: *GIGANTOPITHECUS*

5. MAKING A BIG IMPRESSION: THE SKOOKUM BODY CAST

6. CAUGHT ON CAMERA: PHOTOGRAPHICS AND FORENSIC MEASUREMENTS

7. THE WRANGLER AND THE WILDWOMAN: BOB GIMLIN'S ENCOUNTER WITH BIGFOOT

8. PICTURE THIS: SCIENTIFIC REACTION TO THE PATTERSON-GIMLIN FILM

9. Ape Antics: Behavioral Parallels

10. Sound Off: Vocalizations

11. Grin and Bear It: Misidentifications

12. By the Numbers: Statistical Analyses

13. Stepping Through Time: The Evidence of Footprints

14. Line Upon Line: Dermatoglyphics

15. Splitting Hairs and Molecules: DNA and Physical Evidence

16. Where We Stand: The Evidence Weighed and Measured

Selected Bibliography

Index

Foreword

Some years ago, a project on mountain gorillas brought me to the attention of those in quest of sasquatch, yeti, and other apelike beings who are said to roam forests and mountains in various countries, from Congo, Indonesia, Russia, and Nepal, to the United States and Canada. I was already aware of the distinctive footprints, supposedly of yeti, photographed by Eric Shipton in Nepal in 1951, and later Edward Cronin and Jeff McNeely showed me casts of similar prints in 1972. Bhutan's Forestry Department has presumed yeti casts in its Thimphu office. Earlier my organization, the Wildlife Conservation Society, had been given yeti hair from Bhutan for DNA analysis (it was human hair). A Chinese team in Lhasa searching for the *yeren* (wild man) showed me photographs of its sleeping beds (they were nests of Asiatic black bear). John Green gave me a cast of a sasquatch footprint, truly a big foot, very different from that of yeti, and I have read his books as well as those of John Napier, Dmitri Bayanov, John Bindernagel, and others. I mention all this because sasquatch and yeti have walked through the forests of my mind for over three decades.

Naturally I am intrigued. I realize that the evidence includes hoaxes, delusions, and mistaken identities, prejudiced conclusions, and cultural legends of dubious value as testimony. It has been claimed that yeti footprints in snow are nothing but the melted tracks of hermits, bears, snow leopards, or whatever roaming the heights. But negative evidence does not disprove the yeti's existence. Still others view the large, hairy beings as mythic monsters gliding through our consciousness, lonely wanderers along the mysterious divide between humans and animals. Naturally we humans are mainly interested in ourselves, in our evolutionary history and our relatives along the road from this ethereal origin.

I look at the evidence with a naturalist's eye. I am neither a believer nor can I reject all the evidence and conclude that a novel apelike being cannot exist. Large unrecognized creatures may still roam remote forests. The saola, a primitive relative of wild cattle weighing 100 kilograms, was only discovered in

the mountains along the Laos-Vietnam border in the early 1990s. The many sasquatch tracks need to be explained. Casts of such tracks, together with the cast of a body imprint with large heels clearly outlined, found in 2000, represent the most compelling evidence to date. The authenticity of films, especially the Patterson-Gimlin footage of 1967, has never been disproved. But there is still no proof. No bones, no skin, no conclusive DNA analysis from hairs. The question of existence remains open. But if even *one* set of yeti or sasquatch tracks were genuine. . . .



Naturalist George Schaller observing wildlife in Tibet in 1985 (Courtesy of George Schaller)

So far searches for these humanlike beings have been based on short expeditions, casual outings, or dependent on lucky encounters. A good field study of a species is based on months and years of work, of living in the wilderness to examine spoor and monitor shadowed forest trails, hoping for contact. At least new kinds of evidence might be obtained by such a much-needed extended effort. I am puzzled, for example, why so few large fecal piles have been reported along sasquatch trails. One would expect many from a bulky vegetarian with only rare access to meat, as shown by gorillas and giant pandas.

Jeff Meldrum is a scientist, an expert in human locomotor adaptations. In *Sasquatch: Legend Meets Science*, he examines all evidence critically, not to force a conclusion, but to establish a baseline of facts upon which further

research can depend. His science is not submerged by opinion and dogmatic assumption. With objectivity and insight he analyzes evidence from tracks, skin ridges on the soles of feet, film footage, and DNA, and he compares it to that on primates and various other species. He disentangles fact from anecdote, supposition, and wishful thinking, and concludes that the search for yeti and sasquatch is a valid scientific endeavor. By offering a critical scrutiny, *Sasquatch* does more for this field of investigation than all the past arguments and polemics of contesting experts.

Humans stand alone, isolated monuments from a distant past. Perhaps we seek an evolutionary bridge to connect ourselves to something closer to us than the known great apes, to reveal more about how we became human. The apes offer only a distant glimpse. Possibly some day the yeti, sasquatch, or some other creature yet unnamed, will help to disclose more about the splendor and wonder of our own creation.

—George B. Schaller

SASQUATCH

INTRODUCTION

Doug Hajicek, nature film producer, took a break from shooting with his cameraman, and wandered near the shoreline of Selwyn Lake, nearly 800 miles north of Winnipeg, on the border of Saskatchewan and Northwest Territories, Canada. In the Arctic to film giant lake trout, they had flown into this remote location in the early 1990s. Along the isolated beach they encountered a crisp 17-inch footprint. The print was exceptionally clear and detailed, and excluding its enormous proportions, clearly humanlike in form, with distinct toes and a broad rounded heel. Some 40 inches farther ahead was another similar footprint, followed by another, and so on trailing alternately into the distance. This resembled no bear track. Besides, a polar bear hind paw measures only between 10 and 14 inches long. The hind paw of an Alaskan brown bear may reach a full 16 inches in length, but their range is generally restricted to the Pacific coastline. Grizzlies do range farther to the east but their foot is only about 10 inches long. Could it be an extraordinarily large and out-of-the-way Alaskan Brown, or an oversized grizzly, fishing for giant salmon? Hajicek weighed that possibility but he was familiar with bear sign from extensive documentary filmmaking with Lynn Rogers, the "man who walks with bears," and he knew that a bear track consists of a distinctive alternating pattern of hind and *forepaw* prints. The narrow interdigital pad of the forepaw is much abbreviated compared to the hind paw, to which is added an extended distinctly tapering heel pad. Whatever animal had left these tracks was walking upright, on hind feet only, and had struck off from the lakeshore in an apparently determined course with an impressive stride. Judging from the freshness of the tracks, it may even have been the film crew's arrival on the lake by floatplane that sent it on its way.

Hajicek's curiosity was piqued, and together with his cameraman, they followed the advancing line of footprints. For over a mile they traced the creature's enormous strides, before deciding that they didn't actually *want* to catch up to whatever behemoth had left the immense tracks clearly and deeply impressed in the frosty tundra soil. The men remained mystified over what could have been responsible for these prodigious footprints. They returned to the lake

thinking that they could readily follow the tracks from the air over the relatively treeless landscape and perhaps overtake the track-maker. But the pilot of the floatplane refused to talk about the tracks and rebuffed their suggestions to pursue them, and so they gave up on the idea.

Hajicek was unfamiliar with sasquatch and therefore had no real concept of a giant upright ape upon which to hang the enigma of the footprints. The obvious and unavoidable fact that *some* unusual animal had made this impressive trackway continued to dog him, and his thoughts frequently returned to the scene of the discovery. The suggestion that someone might have intentionally hoaxed them at that precise spot beside a 70-mile-long lake in the middle of the Canadian wilderness, accessible only by floatplane, seemed absolutely nonsensical. Hajicek thought about it a great deal and eventually, with the proliferation of the Internet, encountered the Web site of the Bigfoot Field Researchers Organization (BFRO), and discovered that he was not alone in his experience. In fact, a surprising number of other people had discovered large inexplicable footprints in the wilds of North America. He also learned that the BFRO was compiling an electronic database of reports of sightings and footprints submitted by witnesses from all walks of life. A network of field investigators responded to and documented these reports, where possible, by interviewing witnesses and collecting corroborative evidence, or determining alternative explanations. Hajicek began to educate himself about the accumulated information concerning the history and nature of this hypothetical and strangely elusive primate. He was surprised and irritated that the public at large, and particularly the media, ignored the extensive evidence for the existence of this otherwise legendary animal. Being a filmmaker by profession, he thought what better project than to produce an informed documentary that dealt objectively with the data and explored the question of sasquatch with an open mind. The folks at the Discovery Channel concurred and so the concept of *Sasquatch: Legend Meets Science* was conceived.

The format of the documentary was a noticeable departure from the established formula for “monster” media. Instead of trotting out a series of sensational eyewitness accounts with interviews and dramatic re-creations, then “balancing” them with retorts by armchair skeptics and willfully ignorant scientific experts, Hajicek opted to let the data stand on their own. He would present the accumulated evidence on its own merits and enlist the expertise of scientists willing to evaluate it objectively and to pursue their analysis wherever it might lead them without prejudice. Several of these recruited scientists were previously unconcerned with the matter of sasquatch, but nevertheless, in the

spirit of exploration, were quite willing to ply their skills to evaluate the evidence laid before them. Others harbored a longstanding interest in the subject, but had rarely spoken openly of it for fear of ridicule and a concern for their reputed credibility. A few of the scientists, like Dr. Bindernagel, Dr. Fahrenbach, and me, had already crossed paths with the evidence and were actively engaged in ongoing research into the matter, in spite of its unpopularity within mainstream science, and even among our own respective institutional colleagues.

The Internet has provided a novel and readily accessible forum for the exchange of ideas and information. Like Hajicek, other witnesses frequently submit reports of their encounters with sasquatch to the many sites on the Internet concerned with the topic. The BFRO was one of an overwhelming number of Web sites that one is confronted with when searching the Internet for information relating to sasquatch or Bigfoot. It was the one that captured Hajicek's attention and would subsequently cooperate during the development of the documentary concept. Many of the pioneering scientists Hajicek would work with were associated at one time or another with the BFRO. For a time the BFRO took the lead among a new generation of amateur and professional investigators. There were a number of organizations of various stripe, but the BFRO boldly touted the distinction of being "the only scientific organization probing the Bigfoot/Sasquatch mystery." A rather grandiose assertion perhaps, but, in so far as efforts were made by its investigators to adhere to the principles and methods of scientific research during the collection, handling, and evaluation of objective evidence, that standard was applied with varying success. Like any community, the BFRO was not without its volatile personalities, egos, strong wills, deep-seated opinions, conflicting agendas, and other controversies. However, in spite of intermittent lapses, there had been a degree of cooperation, collegiality, and professionalism among its collective membership.

Producer Doug Hajicek (center) during the filming of *Sasquatch: Legend Meets Science* (Courtesy of Doug Hajicek/Whitewolf Entertainment, Inc.)

Matthew Moneymaker, the founder and driving force behind the organization, recruited and sometimes rode roughshod over a lineup of amateur curators and investigators with varied skills and backgrounds. Affiliated with their ranks have been a number of credentialed scientists—primatologists, anthropologists, archaeologists, wildlife biologists, geologists, and engineers—who have pursued a professional interest in the matter. Some of the most dedicated field researchers, however, have had little or no formal training in the sciences, but often possess a vast experience in the outdoors and keen powers of observation and discernment.

To their credit, the BFRO investigators have been routinely critical of reports and taken pains to winnow the kernel from the chaff, concerning both potential evidence and would-be debunkers. Indeed, it is the proponent who is frequently responsible for refuting misidentified or misinterpreted evidence or claims. It must be appreciated that many of the individuals involved in the investigation lay claim to firsthand experiences that have effectively laid the question to rest for them personally. They are motivated by a conviction that eventually well-documented evidence will bear out their own experiences or convictions and

resolve for them a vexing and persistent mystery.

As many youngsters then and now, I discovered an enduring fascination with extinct dinosaurs and prehistoric ape-men. I knew the author Jack London, not for his *Call of the Wild*, but for his less well-known novel, *Before Adam*, which explored the main character's dreamlike racial memories that nightly hurled him back to the vicarious experiences of remote forebears who lived in trees at the dawn of humanity. Growing up in the Pacific Northwest I eventually was exposed to the legend of sasquatch. At the age of eleven, I encountered Roger Patterson from a third-row seat in the Spokane Coliseum, where he was showing his captivating documentary film about "America's Abominable Snowman." Its centerpiece was the famous sixty seconds of jumpy footage of what he and partner Bob Gimlin claimed to have witnessed along Bluff Creek in the Siskiyou Mountains of northern California. The larger-than-life image of a Bigfoot deliberately striding across the screen made a lasting impression on a young and adventurous mind and served to reinforce my fascination with the evolution of the primates and primitive humans. Was this creature some "missing link" or some relic from a spent diversity of man-apes? I hadn't yet been indoctrinated concerning what *could* and what *could not* exist. The possibility that a giant humanlike ape, or some remnant apelike human, perhaps a relic of the Pleistocene Ice Ages, could have survived to the present in the remote corners of western North America, or elsewhere in the world, seemed to offer the prospect for a fascinating adventure in exploration. Patterson's dramatic film seemed to draw back the curtain on the legend, revealing what could be one of the most intriguing questions facing zoologists and anthropologists today. Does a giant upright ape inhabit our wilderness today? What, if anything, might it disclose about human history?

The Patterson-Gimlin film did not bring a speedy resolution to the mystery of the sasquatch, as Patterson and others had optimistically anticipated. In fact, it made very little lasting impact on the scientific experts of the day, in the absence of a body or some bones. The years that followed yielded no conclusive physical evidence, no type specimen required by hard science, and sasquatch remained stuck in the company of assorted legendary "monsters" and sundry occult subjects.

Very few physical anthropologists ventured to openly pursue a critical look at the matter. One exception was Dr. Grover Krantz, then a young anthropology professor at Washington State University, and not one inclined to shy away from a controversial idea, whether anthropological or cryptozoological (the search for "hidden" animals). He studied Patterson's film and concluded that it was in all

probability authentic. He examined the tracks and concluded an unknown animal had left them; but more importantly, he persisted in thrusting the broader matter of the evidence for sasquatch under the noses of the "Scientific Establishment" as he came to rather critically refer to it. His colleague at the nearby University of Idaho, Roderick Sprague, editor of the *Northwest Anthropological Research Notes (NARN)*, noted the lack of anthropological literature on sasquatch, and in a 1970 editorial invited responsible articles on the subject at a time when it was downright dangerous to one's career to do so. Over the next decade, a series of submissions was published in *NARN*, and these contributions were eventually assembled by Sprague and Krantz as a collected volume under the title *The Scientist Looks at the Sasquatch*. Without the early attentions of a few intrepid anthropologists, the subject might well have been altogether ignored by science and been relegated wholly to the realm of folklore and fantasy.



Dr. Grover Krantz, for many years the most visible scientist seriously investigating the sasquatch question, stands before a portion of his extensive cast collection of hominid skulls and sasquatch footprints at his home laboratory in Sequim, Washington, shortly after his retirement from Washington State University. (Courtesy of Rick Noll)

Krantz was an accomplished anatomist, and his detailed analysis of the

Patterson-Gimlin film, his published evaluations of the accumulated footprints, and his discovery of dermatoglyphics (skin ridge detail) on the casts of the sasquatch footprints could not be so offhandedly dismissed. However, dealing with "evidence" of such a controversial nature is not without its challenges and pitfalls, and Krantz became the target of criticism springing not only from skeptical professional colleagues but also from the volatile elements of the community of amateur Bigfoot researchers. In the end, Dr. Krantz did not live to see the mystery conclusively resolved, but he and others held the door ajar, creating the opportunity for later investigators to take an objective look at the matter.

My own early interests in apes and prehumans led me eventually into a career in academia, specializing in primate evolutionary biology. I focused on the emergence of human locomotor adaptations, especially our apparently singular trait of walking on two feet—bipedalism. Rather than center my investigations directly on the earliest initiation of hominid bipedalism, I have turned to the more recent pattern of emergence of the distinctive modern form of human walking, characterized by a striding stifflegged gait and endurance walking and running.

Eventually, my path crossed that of Dr. Krantz. In 1996, during a visit with family in Boise, Idaho, I traveled with my brother Michael to Pullman, Washington, and the campus of Washington State University to examine Krantz's assemblage of alleged sasquatch footprint casts for myself. The day was spent pulling specimens from drawers and spreading them out on padded laboratory bench tops. There were casts from the Patterson-Gimlin film site; the enigmatic "cripplefoot" from Bossburg, Washington; a cast made by Sheriff Bill Closner from Skamania County, Washington, the first county with a formal ordinance prohibiting the killing of a sasquatch; casts from the Blue Mountains in southeastern Washington bearing skin ridge detail or dermatoglyphics; and many more. We compared and contrasted characteristics and discussed alternate interpretations of details of anatomy and foot function. We noted the repeated appearance through time of recognizable individuals residing in a given geographical region. Finally, we noted the dubious aspects of the more questionable examples and the evident hoaxes, although these seemed to be decidedly in the minority, contrary to my initial expectations. The singular opportunity for a firsthand examination of Krantz's collected series of footprints was extremely enlightening. The study of photographs can provide only so much, and then the investigator must examine the casts and the footprints themselves to truly appreciate the finer details and signs of animation. In 2001,

Dr. Krantz formally passed the baton, and most of his cast collection was transferred to my laboratory at Idaho State University, where it joined the sample of casts I had also assembled in the meantime, totaling nearly two hundred casts. The Smithsonian Institution accessioned additional selected specimens from Krantz's collection, along with selections from his personal papers, and even his very own skeleton, now an enduring anthropological specimen.

A significant number of the casts in Krantz's collection, which also figure prominently in his notable book, *Big Footprints* (in its current edition known as *Bigfoot Sasquatch Evidence*), were accumulated from the nearby Blue Mountains outside Walla Walla in southeastern Washington. This region took on greater significance when I was asked to review a book, *Bigfoot of the Blues* (in its current edition known as *The Walla Walla Bigfoot*), written by a regional journalist by the name of Vance Orchard. For over a decade, Orchard had chronicled developments in the district in his newspaper column. Upon leaving Krantz's lab, my brother Mike and I paid an unplanned visit to Walla Walla, to call upon Orchard and a few of the people who figured prominently in his narrative: Wes Sumerlin, Bill Laughery, and Paul Freeman. Sumerlin was one of the last of the old-time mountain men, frequently horse-packing in the Blues. Bill Laughery was a former game warden now living in the TriCities area. Paul Freeman had briefly been a patrolman for the U.S. Forest Service assigned to the Mill Creek watershed. It was on one of those patrols that he claimed to have encountered a sasqautch and subsequently found footprints that exhibited dermatoglyphics. Freeman had become something of a controversial figure, particularly among the community of amateur Bigfoot investigators, but I was eager to critically examine the original specimens that I had only seen copies of in Krantz's lab. Our unannounced visit found Freeman at home and he cordially invited us in to visit and to examine his footprint casts. The originals, with a few exceptions, were even more impressive than I had anticipated. I pressed him for more details about his casts, for examples of multiple casts from a single trackway, for circumstances of the finds, all the while attempting to size up the person, his reliability, and motivations. Shortly he turned to me and said, "You're obviously serious about this. Would you like to see some fresh tracks? I just found the first tracks of the spring earlier this morning."



Paul Freeman displays a cast of a sasquatch footprint that he collected in the Blue Mountains outside of Walla Walla, Washington. (Courtesy of Grover Krantz)

I was quite incredulous and silently chuckled to myself. What a coincidence, I thought, to have fresh tracks on hand to show me, just like that. Could he have learned of my last-minute decision to detour to Walla Walla and somehow hastily fabricated some tracks for my visit? It seemed unlikely, but either way, what did I have to lose? The three of us climbed into the truck and headed for the foothills. It seemed Freeman routinely drove the muddy mountain roads as early in the year as conditions permitted, looking for sign below the snowpack. That weekend in February, the meltoff had opened the lower foothill roads. On a restricted-access farm road he had found a long line of tracks in the wet ground. We pulled over, stopped the truck, and stepped out onto the muddy side road. A string of 14-inch tracks was plainly visible. Freeman's own tracks from earlier that day were also evident, but indicated he had merely walked alongside the tracks, pausing occasionally, presumably to inspect individual footprints more closely. Freeman repeatedly downplayed the tracks to me, saying they weren't that good and he wouldn't bother casting them, since he had seen much clearer tracks. However, what he considered shortcomings, to my eye were signs of their spontaneity and animation, although I still found the situation rather suspect due to the sheer coincidence, and I harbored lingering doubts about Freeman's credibility. "How could he have managed this?" I was silently asking myself as I surveyed the scene. Mike and Freeman wandered ahead as I began a closer examination, taking measurements and snapping photographs. The prints were

14 inches long by 5 inches wide. I knelt down close and could make out subtle patches of skin ridge detail, fading rapidly in the light drizzling rain. The tracks, whoever or whatever had made them, were fresh considering the weather conditions of the past several days, probably laid down during the preceding night or wee hours of that very Sunday morning. In some tracks the toes were extended and often the fourth and fifth digits hardly left a discernable imprint. In others the toes clearly curled over protruding stones; in still others the stones were pressed into the ground beneath the weight of the forefoot or heel, while still showing signs that a compliant foot had conformed to them. There were distinct tension cracks about the margins of many of the tracks—signs of dynamic compression rather than a forceful stamped impact. Several showed a speed bump-like ridge a little less than halfway along the length of the foot. This was clearly a pressure ridge marked by expansion cracks, which immediately brought to mind a picture I recalled of a track from the Patterson-Gimlin film site, and the corresponding cast I had just examined in Krantz's collection, which displayed a similar feature and dynamic details.



Examples of 14-inch footprints and casts documented by the author at Five Points, near Walla Walla, Washington, on February 18,1996

Then I came to a peculiar footprint that seemed to altogether lack a heel imprint. The step was on a slight incline and the foot had obviously slipped in the wet loamy mud. Distinct slide-ins were evident ahead of all five toes, which were sharply flexed and deeply impressed to gain purchase. The forefoot had pushed up a ridge of mud behind it, much more pronounced than in the other prints, but there was no heel imprint at all. It was similar to a person walking on the ball of his foot when going up an incline, except in this case the entire forefoot, not merely a ball, remained in contact with the ground. This indicated a greater degree of flexibility of the midfoot than is present in humans. The print

was over two inches deep in the mud so that as the toes had splayed somewhat, the marginal toes had impressed into the sidewall of the track leaving a never-before-seen profile of the first and fifth digits. The three toe segments, corresponding to the three individual bones, the phalanges, of the little toe were discernable, while the big toe possessed only two segments. This is a subtle detail of skeletal anatomy that most people are quite unaware of. As the realization began to sink in that this could well be the track of a flesh-and-blood sasquatch, the hair stood up on the back of my neck.

Freeman rejoined me and described how it seemed that the tracks began about where we had parked the truck, made a hairpin loop in the soft soil of the adjacent plowed field, and ended once again along the side road precisely where the truck was parked. Again I thought to myself, how convenient for a hoaxer—simply don false feet in the back of a truck, jump onto the muddy road, trot out a truncated trackway, jump back into the back of the truck, doff the muddy false feet, and away you go. For the moment I kept these thoughts to myself.

The afternoon was waning and so we returned Freeman to his home and took our leave. I turned to my brother and said, "Even if these footprints are fakes, there is ample anatomy present. We can potentially learn a great deal from the incident, hoaxed or otherwise, by taking a closer look and making some casts." So after a quick trip to a hardware store for some supplies, we were back to the foothills. When we arrived, I said, "If we assume for a moment that these tracks are legitimate, then there has to be more sign up the road beyond the spot where the truck was parked and Freeman believed the tracks started and stopped." There was abundant surface along the road and adjacent fields to take tracks, but a thorough search beyond the truck turned up nothing. The only other option, besides a hoax, was that Freeman had read the sign incorrectly and the sasqautch had come and departed from the opposite direction. We began to flag each footprint methodically and soon recognized the point where the track-maker had made a hairpin turn, not out in the field, but near the truck, toward the road. We backtracked in the opposite direction along a brushlined irrigation ditch and found more tracks beyond any sign of Freeman's footprints. Indeed, it appeared that whatever had made the tracks had come from the direction of the densely wooded Mill Creek that flowed out of the watershed, followed the cover of a brushline ditch through the fields and nearby plum orchards, and was heading for the adjacent ridgeline that leads back to the watershed, when something, probably a passing car late on a Saturday night, prompted it to turn abruptly and retreat across the field toward the cover of the ditch, picking up its pace as it went. I was puzzled by the series of footprints immediately after the abrupt turn

back away from the road. Every second right footprint was toed-out about 45 degrees from the line of travel. It wasn't until some months later, when I was examining my own tracks on an Oregon beach that I realized what had likely occurred. As I walked along the wet sand, I would occasionally glance back over my right shoulder to get a glimpse of the appearance of the tracks I was leaving along the beach. I quickly noticed that every time I looked back, my right foot toed out sharply in a manner very reminiscent of the tracks in Washington. Something caused the track-maker to turn abruptly and, with increasing pace, walk away from the road, glancing back every other step to assess the situation.

The plaster we bought was sufficient for seven casts and I tried to sample the variation evident in footprints depending on the conditions of the soil and the speed of walking or running. Some were shallower with the toes fully extended. Some were very deeply impressed, especially under the forefoot, in the softer soil of the fallow wheat field. I was especially interested in the "half-track" with the toe slippage and included a cast of it, and found another example of such. It was getting late and we both had commitments to fulfill the next day in Boise. I still harbored serious reservations about the whole set of circumstances and could not fully accept the situation on its face, but the more closely I considered the tracks the more intrigued I became. In hindsight, the incident had much more significance than I was prepared to acknowledge at the time. The drive home was punctuated with discussions of the possible meaning and implications of what we had witnessed, from Dr. Krantz's lab and cast collection, to Freeman's tracks in the foothills of the Blues. When we pulled into home, well past midnight, I was not inclined to retire just yet. Instead, I went to the garage sink and carefully unwrapped and washed the dirt from the seven casts we had retrieved. I lined them up and reexamined them, carefully noting the contours of the heel, the consistent protrusion of bony landmarks, the evidence of midfoot flexibility, the signs of articulation and obvious mobility evident in the toe impressions. I placed my little finger alongside the profile of the fifth digit in the peculiar half-track. It failed to cover it fully. The toes were relatively long, even for a 14-inch foot. The evident spontaneity and consistency of the tracks impressed me profoundly. Perhaps there *was* something to these footprints that deserved a much closer look. Who better to evaluate this evidence than someone long preoccupied with primate feet and the evolution of bipedalism? I began contemplating what it would involve to review and extend the line of study that Dr. Krantz had begun.

Some time later, when the opportunity was extended to participate in a sponsored expedition to attempt to collect new data in the field, I was keen to

join. Richard Greenwell of the International Society of Cryptozoology had received funding from a foreign documentary film company to mount a four-week excursion into the Siskiyou wilderness of northern California. Our jumping-off point would be just a few tens of miles from the site at Bluff Creek where Patterson and Gimlin had their alleged encounter, captured on film in 1967. An additional five-man camera crew and four pack llamas accompanied the fourman research team. Our intended llama handler had to withdraw at the last minute and I was given a crash course in llama wrangling, which added a whole new and unanticipated dimension to the experience.

Scenes from the Six Rivers National Forest Expedition of 1997. Equipment was packed into the backcountry on llamas.

Author, Darwin Greenwell, and Richard Greenwell (Courtesy of Richard Greenwell)

We had seismic sensors, night vision and call-broadcasting equipment, and early-model camera traps, at a time when few if any others were utilizing such technologies for this purpose. We discovered that such novel accoutrements presented a set of challenges all their own. On the first day in, we came upon an old set of tracks crossing a pass. They were heavily weathered and unsuitable for casting, but the discernable outlines of broad 13-inch footprints laid down in bipedal sequence were evident. After this tantalizing piece of evidence, little else was found over the next couple of weeks. The infrared triggers for the camera traps were set off by any interruption, animate or otherwise. When the morning fog rolled in off the coast it would set the cameras off in rapid succession, using up a roll of film in short order. We did get some intriguing responses to the calls we broadcast, but they were too brief and faint to record effectively. There was ample sign of bear scat in the areas we explored, but footprints of any kind were scarce, if not altogether absent, given conditions on the ground. Frankly, I was a bit surprised by how little of the ground surface lent itself to taking distinct tracks. The trails were rocky and a deep layer of dry duff often cushioned the forest floor. The creek beds were mostly rocky or densely overgrown with willows and alders. This was something I had not fully anticipated, and it goes largely unappreciated by most who seldom venture off-trail.

The camera crew departed on schedule after five days of shooting. We moved camp farther into the wilderness and hoped that with a fresh location, and fewer people about, we might have a better chance of encountering sign or

detecting something. As the fourth week began, our guide, Mark Slack, and I undertook an excursion about five miles farther along the trail, intending to then cut cross-country a farther couple of miles to reach a cluster of off-trail lakes. We hoped that the shrunken lakes with exposed mud flats would provide more suitable substrate for tracking. The "trail" we followed was barely that since, as the Forest Service personnel had warned us, it had not been maintained for some years. We lost the indistinct trail a number of times as it crossed rocky outcrops, only to pick up portions of it again farther along. In many places it was strewn with numerous deadfalls, rendering it impassable had we brought llamas along. It was clearly a region rarely disturbed by human visitors. As we negotiated an east-west trending ridge the rocky trail was littered with a thin layer of duff still moist with dew. Abruptly, we came upon a series of fresh footprints 16 inches in length. Something had come up the slope, cut along the section of trail for a short distance, and then continued upslope in the direction of a notch through the rocky ridgeline. The outline of the shallow imprints on the hard trail was unambiguous and the moist duff under the forefoot was scuffed back exposing the dry material beneath. The length of the step was over 42 inches on a moderate uphill incline. We scouted about, but what little sign we could distinguish off-trail was eventually lost in the rocky ridge.

About a mile farther on we left the trail, following a small tributary upstream, and made camp near a clear spring just below a ridge separating us from the lakes. The spring was surrounded by exotic-looking pitcher plants, giving the scene a surreal atmosphere. Several bear trails were evident about the margin of the spring; their small quadrupedal tracks were in stark contrast to the footprints we had examined earlier that day. In the morning we climbed the ridge and descended through a vast boulder-strewn slope to the lakes. As we expected, the mud flats preserved many footprints, especially excellent bear tracks, some indicating cubs in tow, but disappointingly no tracks of sasquatch. We returned to the ridge just before sundown and from that vantage point tried to imitate the recorded vocalizations we had broadcast from the base camp on preceding nights. Surprisingly, our voices seemed to carry quite a distance, echoing down the drainage in the still evening air. There was no response—no audible reaction that is.



More scenes from the Six Rivers National Forest Expedition of 1997. The author's step fails to match that of a biped that left 16-inch tracks on the trail.

As we reached camp a cold drizzling mist had engulfed the mountains and we huddled around the fire beneath our ponchos as we sipped miso soup left behind by the Japanese camera crew, and eventually retired to our respective bivy tents. I was awakened several hours later by Mark's urgent voice whispering "Jeff! Jeff, do you hear that?" As I roused from my slumber I could just make out a trailing cry some ways off in the night. I wasn't at all certain what I had heard, but I was certainly wide-awake now. I lay there as the minutes dragged on, straining to listen. Then came the sound of footsteps and popping brush circling our little camp, and a clacking sound, of rocks or perhaps teeth, in rapid succession. The clacking was promptly responded to by a second source of clacking on the opposite side of the camp. There was a pause and silence, and then a clackity-clack of Mark's pack frame bumping against the tree trunk it was leaning against. I struggled to extricate myself from my bag and tent, and heard

Mark doing likewise. We found the pack, which had been wrapped in a poncho, standing uncovered with its flap unclasped and thrown back, its rifled contents hanging out in disarray. The dense mist obscured the moon and stars, and our flashlight beams did not significantly cut through the gloom. Whatever it was had simply slipped away into the fog. We lingered outside our tents for some time before returning to the shelter and warmth of our bedding. No sooner was I settled in than the footfalls returned. Their pace quickened and seemed to approach my tent with a rapid pad-pad-pad. The sound of footsteps passed along the side of my small tent and something bumped one of the poles, jostling it. "Mark?" I queried, wondering if he could be out there investigating something, but he responded from inside his tent in the opposite direction. I again scrambled from my confinement into the wet darkness and shot the beam of my flashlight along the side of my tent. Near the head of my tent was enough grass to momentarily hold a roughly 16-inch oblong impression, the grass just rebounding from the compressing weight of the tread. There were also punch holes in the boggy stretches below the spring where something had apparently stridden rapidly away from the campsite. The punch holes had slumped in with standing water and retained no detail.

The next day and night were uneventful except for incessant rain. We surveyed the immediate area for additional sign but found none, except for old washed-out bear trails. The next morning the rain let up and since our provisions were nearly expended, we broke camp and headed back to rejoin the others. Along the trail I hoped to get another look at what remained of the tracks we had encountered earlier along the ridgeline. They were in thick timber and relatively sheltered from the direct onslaught of the rains. We paused there for a respite and some refreshment. As I slung my pack off, a softball-sized rock sailed onto the trail a mere few feet away. A slight shiver crept up my spine. There was no high point nearby from which a rock might have been dislodged by the rainstorm. Nor did it simply roll onto the trail from uphill. It had been airborne; it had been lobbed. For the first time on this excursion the hair on my neck stood on end; there was that subjective, but inescapable sense of being watched. In spite of the distinct feeling that something wanted us to move along, we determined to tarry and see what would happen. Nothing did and we eventually gathered ourselves up and continued on to the base camp, arriving late that afternoon and related our experiences to our companions.



Bivouac where a nocturnal visitor rifled through Slack's backpack and brushed against the author's tent.

That night I was again awoken by the sound of Mark's backpack clanging against a tree trunk. As I collected my senses, I called to Mark. Immediately there was a pad-pad of heavy footfalls running between our adjacent tents and the sweeping sound of something brushing along the length of my tent's rain fly. I emerged from my tent to see Mark's pack open again, this time the now-empty food bag was out and standing on the ground like an open grocery bag. The hard-packed ground had again taken no readily discernable tracks. In the morning we discovered that our food cache in the meadow had been raided. The twisted double garbage bags were standing open, but there were no claw marks or tooth marks, and no scattered provisions that typically mark bear activity. Curiously, only a large resealable bag of flavored instant oatmeal packets was

missing. The few remaining foodstuffs—instant potatoes, dried fruit, jerky, etc.—were left untouched. Such selectivity was also uncharacteristic of a scavenging bear, but had precedent in other reported sasquatch encounters.

Mark Slack, expedition outfitter (left), and author examine footprint sign.

These experiences in the Siskiyous were perhaps even more compelling than the footprints in the foothills of the Blues. We were in a remote region and had seen only two people besides our party in four weeks—some serious backpackers who had come through from the distant, more popular north end of the wilderness area. I was confident that no human was responsible for the events of those nights. I was equally convinced that we were not dealing with the antics of a marauding bear. The behavior was completely atypical of a bear in camp. There was something that had left l6-inch footprints, apparently walked on two legs, dexterously opened backpacks, rifled its contents without mark of tooth or claw, and accurately lobbed a rock in our direction. Just what that something was, remained hidden from sight throughout our excursion, but little doubt remained that I would have to pursue the question of sasquatch to its resolution, one way or another.

Hajicek's documentary project, *Sasquatch: Legend Meets Science*, set a new benchmark for serious media coverage of this intriguing cryptozoological mystery. It provided an opportunity to further my own research through discussion and collaboration with an assemblage of open-minded and inquisitive

fellow scientists recruited to evaluate evidence in their respective fields of expertise. A colleague of Hajicek, Michael Hsu, suggested that a companion volume should be produced as well, in order to carry the dialogue to another level, and offered to take the lead in coordinating the effort. When Hsu approached me about writing such a book, I was very keen on the idea, having wondered about the possibility of a companion volume myself. While organized after the framework of the documentary, in this companion volume I delve even further into the background and history of scientific reaction to the persistent evidence than was possible within the time constraints of a one-hour television show. I share many of my own experiences, perspectives, and insights gained through nearly a decade of investigation and research. I also take the opportunity to set a baseline of what is known and to explore theoretical questions pointing to new directions of research. The latter may strike some as akin to the medieval debates about how many angels can dance on the head of a pin. But I suggest it begins to establish a framework for what is or is not *plausible* for the anatomy, behavior, and ecology of a reputed large primate. Perhaps it will bring us closer to a rational determination of what lies behind the legend of sasquatch.

Demo version limitation

Demo version limitation

Demo version limitation

THE GIANT APE OF THE ORIENT: *GIGANTOPITHECUS*

"In a clump of bamboo at the edge of a clearing, a troop of giant apes is foraging, snapping huge stalks of bamboo as easily as so many bits of straw. They hear the approach of the men and turn. The two species are eyeball to eyeball for the first time. The apes loom to a height of ten feet—more than twice the height of the men—and weigh well over one thousand pounds . . . one of them lopes forward a few gigantic steps to get a closer look at the group of men. Its head is enormous, with a thickset jaw. The crown of its head looks diminutive atop a huge mandible. Small yellow eyes burn in its skull as it takes in the sight of its furless distant cousin." So Dr. Russell Ciochon, a paleoanthropologist at the University of Iowa, describes a hypothetical encounter between *Homo erectus* and *Gigantopithecus* in the forests of eastern Asia sometime within the last one million years. Fossils of both species, recovered from cave deposits in southern China and Vietnam, attest that they overlapped in temporal and geographical range. The nature of their interaction must remain speculative since so little is known about either the full extent of the geographical range or the skeletal anatomy of *Gigantopithecus*.

Speculative reconstruction of the bust of *Gigantopithec* (Courtesy of George York)

The giant ape was first discovered when, in the 1930s, paleontologist Ralph von Koenigswald began searching the apothecary shops of eastern China for "dragon bones" used as curatives in traditional Chinese medicine. The dragon bones were the fossilized teeth and bones of ancient mammals. In Hong Kong he came upon a single gigantic lower molar tooth of an unknown ape, twice the size of a corresponding gorilla tooth. He named the species *Gigantopithecus blacki*. It was the largest ape that ever lived, estimated to have weighed in excess of 300 kg (660 lbs). By comparison, an adult male gorilla weighs on average 175 kg (380 lbs).



The silhouettes of a 10-foot- and 8.5-foot-tall bipedal *Gigantopithecus* compared to a 6-foot human figure. Note the tremendous bulk of the giant primates by comparison.

The first massive mandible of this ape was recovered in the late 1950s by an expedition from the Academia Sinica. Two more jaws were to follow, along with hundreds of isolated teeth. In the context of earlier evolutionary interpretations, *Gigantopithecus* was considered to be a hominid, i.e., closely aligned with the human lineage, due to the thick enamel on the rounded molar cusps, its nonprojecting canines, its bicuspid premolars, and the marked posterior divergence of its mandible. This interpretation was a matter of serious discussion up through the 1970s. Alternately, it was suggested that the dental characteristics held in common with hominids demonstrated ecological convergence between *Gigantopithecus* and early hominids. It was hypothesized that these characters, especially thick tooth enamel, evolved in parallel to hominids as adaptations to similar diets and foraging habits. With the fossil remains of *Gigantopithecus* restricted to jaws and teeth, there can only be speculation about the locomotor adaptations of this giant ape. But if the foraging strategies that convergently shaped the jaws and teeth of both *Gigantopithecus* and early hominids produced bipedalism in the one lineage, the possibility of the convergent evolution of bipedalism in *Gigantopithecus* under similar environmental conditions should at least be entertained.

Zoologist and “father” of cryptozoology Bernard Heuvelmans first made a potential link between *Gigantopithecus* and the notorious Himalayan yeti. He

suggested, “For giant apes, still agile but no longer able to live in trees, mountains were evidently the most suitable habitat and safest refuge. For the *Gigantopithecus*, which used to live in China, the high Himalayas were the obvious shelter. There, out of reach of their enemies, they could have survived until today, just as their contemporaries have survived in the marshy forests of Borneo and Sumatra. This theory, which is utterly hypothetical, provides the only entirely acceptable explanation of the mystery of the abominable snowman.”

When increasing numbers of western mountaineers encountered large bipedal tracks in the Nepalese mountains, the very real possibility of a relic ape was entertained by a number of respected scientists of the day, including Dr. Carleton Coon, University Museum, Pennsylvania State University; Dr. W.C. Osman Hill, Zoological Society of London; and Dr. Adolph Schultz, Anthropological Institute, Zurich. In his 1973 landmark book, *Bigfoot: The Yeti and Sasquatch in Myth and Reality*, Dr. John Napier, former Director of the Primate Biology Program of the Smithsonian Institution, observed, “It is possible that these creatures, thought by anthropologists to be long extinct, survived in refuge areas such as some of the deep forested river gorges of the Himalayan range until relatively recent times. The absence of a fossil record is not necessarily evidence of extinction.”

An inferred reconstruction of the skull of *Gigantopithecus blacki*, based on its fossil jaws and teeth, by Grover Krantz

As recently as 1998, Dr. Chris Stringer of the British Museum of Natural History acknowledged that the yeti legend might not be so far-fetched as often presumed, and may indeed have been inspired by surviving populations of *Gigantopithecus*. He allows that the giant ape may survive today in the dense forests of Southeast Asia, if not in the less likely environs of the Himalayas. Stringer recognized that it would be wrong to assume that yetilike creatures could not survive to the present day without being discovered. "It could have survived until the appearance of modern humans 50,000 years ago, and it is at least possible that it is still living as a very rare creature in remote forest areas," Stringer contemplated. On this matter, Dr. David Begun, paleoprimatologist at the University of Toronto, noted in 2003 that, "There is no reason that such a beast could not persist today. After all, we know from the subfossil record that gorillasize lemurs lived on the island of Madagascar until they were driven to extinction by humans only 1,000 years ago."

Ciochon has posed a curious paradox. He noted that *Gigantopithecus* is presumably the only great ape to have gone extinct during the Pleistocene. The extant great apes have a greatly reduced range as compared to their former distribution, but they have largely managed to weather the transition to the Holocene. What was it that presumably drove the giant ape to extinction? To account for this apparent inconsistency, Ciochon pointed to the possibility that *Gigantopithecus* had a narrowly specialized diet of bamboo. He then compared the demise of Gigantopithecus to that of the giant panda. Thus, dwindling resources, competition, and encroachment by early humans presumably combined to extirpate the giant ape. However, recent analysis of tooth wear seems to have nullified this hypothesis of dietary specialization. The pattern of microscopic pits and scratches on the giant ape's teeth suggests instead that *Gigantopithecus* was a generalized omnivore, removing dwindling resources and competition from pandas as arguable causes of its extinction. The remaining leg of the extinction argument is human encroachment. Other large apes have survived the pressures of human encroachment until now, if only marginally. Why not *Gigantopithecus?*

Gigantopithecus is likely not the only potential ancestral candidate for a relic ape species, however. An extensive radiation of apes is found in the fossil record of the Miocene epoch, beginning about 23 million years ago and ending about 5 million years ago. The Miocene deposits of Africa and Eurasia have yielded an extraordinary diversity of fossil ape species with nearly one hundred extinct

species described, and additional species of fossil large-bodied hominoids continue to come to light. For a time the Earth truly was a “planet of the apes.” Monkeys had just come onto the scene and begun to diversify as shifting climates created new ecological opportunities for them. Not only were the extinct Miocene apes taxonomically diverse, but also they were quite varied in their adaptations for movement, posture, diet, and distribution. Some were terrestrial quadrupeds, with most of their activity occurring on the ground like modern baboons. Some inhabited temperate woodlands with more seasonal resources and evolved thick tooth enamel to handle a diet of harder coarser foods. A few known species eventually attained great size; a trend realized by several species of primate, including a five-foot tall Ice Age ally of the spider monkey found in Brazilian cave deposits, and a gorillasized lemur in Madagascar.



The mandible of *Gigantopithecus blacki* compared to that of a modern human

An earlier smaller species of the genus *Gigantopithecus, G giganteus*, is known from the fossil record of Indopakistan dating from 9-6 million years ago. Although the fossil record is patchy, it is believed that *Gigantopithecus blacki*, from the Pleistocene, less than 1.6 million years ago, evolved from its smaller predecessor *G. giganteus*, as the lineage continued to increase in size through the Pliocene. Many species of warmblooded mammals employed the strategy of gigantothermy to better endure the colder climates of the Pleistocene and to extend their ranges and exploit more temperate habitats.

Of course the prospect of Ice Age relics in the remote corners of Asia is one

thing, but what is the likelihood of a giant ape taking refuge in the rugged mountains of North America? A trend for increased body size, thick tooth enamel, and exploitation of terrestrial habitats would conceivably have permitted *Gigantopithecus* to extend its range into more northerly latitudes and better cope with cooler temperatures and more seasonal forest forage spanning across the periodic land bridge between Asia and North America, while its smaller, more arboreal, ape cohorts were restricted to tropical forests.

This trend for increased body size in more northerly-distributed species remains evident even today when comparing related species distributed along a north-south latitudinal cline. Take for example a series of bear species. The spectacled bear *(Tremarctos ornatus)* of tropical South America is the smallest in the series, weighing in at between 60 to 140 kg. Moving northward, we encounter the American black bear *(Ursus americanus)* with weight ranges from 90 to 270 kg. Next comes the grizzly bear (*Ursus arctos*), found throughout the northern Rockies and Canada, weighing between 150 and 380 kg. The Alaskan brown bear (*Ursus middendorffi*), found along the southern coast of Alaska and nearby islands, weighs as much as 675 kg. Finally the polar bear (*Ursus maritimus*) along the northern coastline of Alaska, Canada, and Greenland, can reach weights of 800 kg.

This tendency for increased size in more northerly habitats is referred to as Bergman's rule. It reflects a straightforward strategy for coping with the challenge of retaining body heat in colder environments. Increased body size decreases the ratio of surface area to body mass. The surface area of geometrically similar bodies of different size is the square of a linear dimension, and the volume is the cube of the linear dimension. Take a simple example of a cube with 1-inch sides. Each side has a surface area of 1 square inch (in^2). There are six sides to a cube, so the combined surface area is 6 in^2. The volume is the height × width × depth of the cube, or 1 cubic inch (in^3). Now let's double the linear dimensions of the cube making each side 2 inches square, or having a surface area of 4 in^2. This six-sided cube has a combined surface area of 24 in^2—a fourfold increase over the 1-inch cube. The volume of the 2-inch cube increases to 8 in^3—an *eightfold* increase. Considering the 1-inch cube, the ratio of surface to volume is 6:1. By comparison, the 2-inch cube has a ratio of 24:8 or 3:1. For larger animals with relatively less skin surface exposed to the environment, less body heat escapes allowing them to tolerate colder climates. Increased body size would be a reasonable adaptation for sasquatch inhabiting northern latitudes, by contrast to its extant tropical cousins.



An illustration of Bergman's rule. Reported height and foot lengths plotted against latitude. (Courtesy of George Gill)

Bergman's rule also influences body size distribution *within* a single species that has a wide geographic distribution. In 1978, Professor George Gill, a physical anthropologist at the University of Wyoming, presented an analysis of the geographical distribution of footprint lengths and estimated stature of sasquatch. He determined that north-south clines were indeed evident in the data. He concluded, "The present analysis of reports of alleged eyewitness sightings and tracks of the sasquatch was undertaken as the result of the increasing seriousness of this anthropological mystery. The preliminary results of our study support the hypothesis that the sasquatch actually exists, in that population clines in reported body size and track lengths not only seem to exist, but conform to ecogeographical rules."

An added benefit of heat conservation afforded by larger body size is reduced metabolic rate. Less metabolic energy per unit of body mass is required to maintain core temperature. Larger animals also have more space to accommodate a more capacious gut needed to process less easily digested foods. Therefore, larger animals can often subsist on coarser or more seasonal diets of relatively less nutritious foods, as is frequently the condition in temperate forests.

John Green was the first to suggest a link between *Gigantopithecus* and the North American sasquatch. The inferred size and upright posture of *Gigantopithecus* provides ". . . a pretty good thumbnail description of what people have been seeing in North America all along. How it got here is no problem," he said. "Man and a lot of types of animals are believed to have reached North America via a land bridge from Siberia. *Gigantopithecus* . . . could easily have tagged along."

Distinguished scientists such as Geoffrey Bourne, former Director of the Yerkes Primate Research Center, acknowledged the possibility of a large primate immigrating to North America. He suggested, ". . . there is no reason why *Gigantopithecus* could not have earlier come up the mountain causeway and crossed the Bering Strait . . . into the montane forests of America . . . So perhaps the *Gigantopithecus* is the Bigfoot of the American continent. . . Only the discovery of an actual animal and its thorough scientific examination can provide the answer."

Shortly after viewing the controversial Patterson-Gimlin film footage, Dr. Joseph Wraight, chief geographer of the U.S. Coast and Geodetic Survey, shared his reaction to the film with Ivan Sanderson. Wraight echoed Bourne's acknowledgment and countered a frequent misconception about the possible origins of sasquatch: "The presence of large, hairy humanlike creatures in North and Central America, often referred to as sasquatch, appears very logical when the physiographic history of the northern part of this continent is considered. The statement often made that monkey-like creatures never developed in North America may easily be discounted, for these creatures are more humanlike than apelike and they apparently migrated here, rather than representing the product of indigenous evolution. The recent physiographic history of the polar edges of North America reveals that the land migration of these creatures from Asia to America is a distinct and logical possibility. The compelling reason for this distinct possibility is that the land bridge between Asia and North America is known to have existed several times within the last million years, at various intervals during the Pleistocene or Ice Age. It appears then that these hairy,

humanlike creatures, sometimes called sasquatch, could easily have migrated to North America at several times during the Ice Age. This is particularly plausible when it is considered that conditions were mild in that area when the land bridges existed. These creatures could have then found conditions along the way similar to their Asian mountain habitat and could naturally have migrated across the land bridge."

Indeed, the temporal and geographical distribution of this giant ape suggests the possibility that it may have spread to North America during times when a land bridge connected Asia and North America. The Bering land bridge is often envisioned as a frozen arctic wasteland or bleak windswept tundra—a seemingly unlikely habitat for an ape. However, the fossil record of past vegetation in the region indicates that during the early to middle Miocene a continuous temperate corridor of deciduous broadleaf and coniferous forest extended from northeast Asia, across the land connection in the region of the present Bering Strait, down across western North America into the Pacific Northwest. Global cooling, beginning about 2.6 mya, first eliminated the broadleaf trees, and then intermittently reduced the coniferous forests, more particularly in the interior regions, while sparing the coastal forests to a greater degree. Of course much of these coastal regions are now under water due to elevated sea levels. Any fossil-bearing sediments from those periods are inundated by hundreds of feet of seawater.

Ongoing discoveries continue to demonstrate the incompleteness of our understanding of movements of species between Asia and North America. A new fossil jaw of a brown bear recovered in southern Canada, dated to 26,000 years ago, has doubled the temporal depth of the fossil record of that species, raising renewed questions about the timing of transcontinental migrations. The discovery in Tennessee of a single molar of the red panda, today found in the Himalayas, with a highly specialized diet of bamboo has obvious geographical, if not ecological implications for discussions of a sasquatch/*Gigantopithecus* connection. This recent find is the second discovery of the red panda molar in North America and dates to between 4.5–7 mya. The earlier find was made in Washington State and dates from 3–4 mya. In a similar vein a new species of grylloblattid, a primitive form of cricket, was discovered in Ape Cave near Mt. St. Helens in the Washington Cascades. The Family Grylloblattidae has the least number of included species and also boasts the most restricted geographical range, including Eastern Asia and northwestern North America. Certainly it would be a worthwhile exercise to compile a list of species of fauna and flora common to these two regions to illustrate the remnant of a contiguous habitat

that once spanned these adjacent continents and the extent of their shared communities of plants and animals.

Nearly as controversial as sasquatch itself is the interpretation that a fragment of a fossilized human brow ridge found at Mexico's Lake Chapala may be from the skull of a relic *Homo erectus*. The attribution is a matter of considerable debate, but the close resemblance of the fragment to the cranial anatomy of *Homo erectus* is inescapable. This Asian hominid is thought to have gone extinct within the last 100,000 years, possibly persisting until quite late, until less than 30,000 years ago on isolated Indonesian islands. That the notion of *Homo erectus* in North America is even entertained by serious researchers has implications for the potential range of *Gigantopithecus*. If red pandas, and perhaps *Homo erectus*, both sympatric contemporaries of *Gigantopithecus* in Asia, successfully migrated to North America, what would prevent a similar distribution of *Gigantopithecus?*



Renowned naturalist George Schaller gives serious consideration to the evidence for sasquatch. (Courtesy of Doug Hajicek / Whitewolf Entertainment, Inc.)



Journalist and author John Green is considered the patriarch of proletarian sasquatch investigators. (Courtesy of Doug Hajicek / Whitewolf Entertainment, Inc.)



Native *buk'wus* dancer sculpted by Jack Gibson (Courtesy of Jack Gibson, www.jackgibsongallery.com)

Dsonoqua and her daughter on a totem pole at the Thunderbird Park on the grounds of the British Columbia Provincial Museum, Victoria, British Columbia, Canada (Courtesy of John Bindernagel)

Yokuts rock art depicting the Hairy Man (Courtesy of Kathy Moskowitz)

The mandible of a *Gigantopithecus blacki* alongside Bill Munn's artistic reconstruction of a *Gigantopithecus* bust (Courtesy of Doug Hajicek / Whitewolf Entertainment, Inc.)



World map depicting the possible expansion of *Gigantopithecus's* range from Asia to North America during periods when those continents were joined by a land bridge

Rick Noll, longtime field investigator and one of the discoverers of the Skookum imprint (Courtesy of Rick Noll)

Map indicating the location of the Skookum site in the Southern Washington Cascade Range (Courtesy of Rick Noll)



The Skookum imprint (Courtesy of Rick Noll)

The author, Esteban Sarmiento, and Daris Swindler examine details of a mold taken from the Skookum cast. (Courtesy of Doug Hajicek /Whitewolf Entertainment, Inc.)



Three-dimensional scan of the Skookum cast highlighting topographic features of the anatomy and their interpretation (Courtesy of Rick Noll)



Sequence of stills from the Freeman video made near Deduct Springs in the Blue Mountains of southeastern Washington (Courtesy of Paul Freeman)

Stills from the Memorial Day video taken by the Pates in northern Washington. Note the increase in height of the subject in the lower still. Inset compares the subject in question (above) to a human model (below) at the same scale. (Courtesy of Doug Hajicek/Whitewolf Entertainment, Inc.)

Forensic team members Doug Divine and Bob Francis prepare to map the Memorial Day video site. (Courtesy of Doug Hajicek/Whitewolf Entertainment, Inc.)



World-class sprinter Derek Prior dons a GPS back pack to track his reenactment of the Memorial Day sighting. (Courtesy of Doug Hajicek/Whitewolf Entertainment, Inc.)

Tracking sequence of Prior following the path of the video subject (Courtesy of Doug Hajicek/Whitewolf Entertainment, Inc.)

Frame 352 of the Patterson-Gimlin film (Courtesy of Martin and Erik Dahinden)



Frame from near the beginning of the film footage showing the back of the subject and the sole of the foot (Courtesy of Martin and Erik Dahinden)

Close-up of the sole of the foot alongside a cast of a footprint from the film site made by Bob Titmus (Note the sole of the foot is viewed at a slight angle.) (Courtesy of Martin and Erik Dahinden)

The author correlates dynamic features of a footprint cast from the Patterson-Gimlin film site in order to estimate the skeletal proportions of the sasquatch foot. (Courtesy of Doug Hajicek/Whitewolf Entertainment, Inc.)

Skeletal overlay tracking the Patterson-Gimlin film subject (Courtesy of Doug Hajicek/Whitewolf Entertainment, Inc. and Martin and Erik Dahinden)

Modeling the foot skeleton based on the author's reconstruction of the film subject's skeletal proportions and landmarks (Courtesy of Doug Hajicek / Whitewolf Entertainment, Inc.)

Completed animation of the skeletal kinematics of the film subject constructed by Reuben Steindorf (Courtesy of Doug Hajicek / Whitewolf Entertainment, Inc.)



Before and after shots of the apparent quadriceps herniation on the right thigh of the film subject. Inset depicts a close-up of the herniation. (Courtesy of Martin and Erik Dahinden)

The author in his laboratory at Idaho State University discussing the distinctive points of anatomy of sasquatch footprints (Courtesy of Doug Hajicek /Whitewolf Entertainment, Inc.)

The complete set of ten casts made by Bob Titmus at the Patterson-Gimlin film site at Bluff Creek in northern California, nine days after the filming



Author’s reconstruction of the skeletal basis for the midfoot flexibility that produces the distinctive midfoot pressure ridge in some sasquatch footprints

Some examples of typical sasquatch footprints and casts



Latent-fingerprint examiner Jimmy Chilcutt is satisfied that an unknown primate is responsible for the ridge detail on some sasquatch casts. (Courtesy of Doug Hajicek / Whitewolf Entertainment, Inc.)

Close-up of ridge detail on the Blue Creek Mountain, California, cast

Close-up of the ridge detail and healed scar found on the footprint cast from Walla Walla, Washington

Hair displaying primate characteristics recovered from the Skookum cast (Courtesy of Doug Hajicek / Whitewolf Entertainment, Inc.)



Comparative series of examples of hair from bear, chimp, human, and presumed sasquatch (all to same scale) (Courtesy of Henner Fahrenbach)

The term “migration” sometimes has a misleading connotation in this context. The hypothetical movement of *Gigantopithecus* from Asia to North America should not be considered an intentional trek through unfamiliar and inhospitable territory to invade a new frontier on the American continent. Instead

it is more accurately seen as a gradual expansion of a species' range as its habitat expands with changing climate and geography. This expansion may take millennia to culminate, or it may happen more rapidly in species that are naturally more opportunistic and far-ranging. Species that are generalists and more readily exploit diverse resources are also more likely to successfully adapt to varied environments encountered as their range expands. Large body size would further enable them to consume and process a broader repertoire of foods than smaller-bodied apes.

Dr. Tom Agar, a research geologist with the USGS, and expert on the conditions of Beringia, recently speculated, "As for the feasibility of a large primate traveling across northeast Asia, the land bridge, and down into western North America during the Miocene (or later), yes that is possible. And the habitat, climate, edible plants, and coastal marine resources would not have changed all that much along the route during the early to middle Miocene. After that it would have been much continuous coniferous forests along the North Pacific rim, affording somewhat less diverse food resources perhaps . . . Today, the coastal rain forests of southeastern Alaska, British Columbia and parts of the Pacific Northwest are pretty dense, and it might be possible for a critter to avoid detection for a long time."

Chinese snub-nosed langur (*Pygathrix roxellana*), which inhabits elevations up to 10,000 feet (Courtesy of George Schaller)

While most extant primates are generally tropical, this is not an exclusive characteristic of the order. Some living primates, such as the Japanese macaques, *Macaca fuscata*, and the Chinese snub-nosed langurs (golden monki), *Pygathrix (= Rhinopithecus) roxellana*, live today in temperate conditions, and endure very cold, snowy winters. The range of the Japanese macaque is the northernmost known for a nonhuman primate, at 41 30′ N., the same latitude, incidentally, as the supposed northern California habitat of the sasquatch. Furthermore, the Chinese snub-nosed langur, one of the largest monkeys in the world, has adapted to montane mixed bamboo, coniferous, and deciduous forests, up to 3,150 m (10,335 ft) in elevation. They endure the longest and coldest winters of any other primate except humans. The record low temperature in their range is −30°C (−22°F). In the winter their diet consists largely of lichens, a plentiful carbohydrate source, and the inner bark of some trees. A bit to the east, a related species, the black or Yunnan snub-nosed monkey *(Pygathrix bieti)* ranges up to 4,500 m (14,765 ft). Half of its diet consists of lichen from the genus *Usnea*, which hangs from evergreen trees, also found throughout much of the Pacific Northwest.

Apes have a somewhat different physiology and life history than monkeys. In an anonymous peer-review, a member of the scientific board of the California Academy of Sciences argued that the larger brains of apes required a constant and rich food supply during their development—a requirement that could not be met by the resources of the temperate forests of North America. This conclusion ignores the presence of fatty acids critical to brain development in a diet including meat. These fatty acids are especially concentrated in fish, in particular salmon and cold-water species in mountain streams found in the Pacific Northwest and northeast Asia. Furthermore, the reviewer's opinion conveys an oversimplification of great ape evolutionary history, diets, and habitat diversity. For many populations of extant apes living in the tropics, the availability of preferred food resources exhibits marked seasonality. One population of chimpanzees studied, occupied a range of nearly 200 square miles with a mere 3 percent forest cover. Bonobos exhibit a peak in births just after the dry season, presumably to maximize the length of the beneficial rainy season for both lactating mother and infant before the next dry season. Mountain gorillas live in a very cool and wet climate, considering they are found in the tropics, often experiencing subfreezing temperatures at night. The gorillas typically range between the 2,743 m (9,000 ft) and 3,352 m (11,000 ft) elevations, but have been

tracked as high as 4,114 m (13,500 ft), the lowest elevation at which snow falls on the Virunga Mountains. They have evolved much thicker coverings of hair than their lowland counterparts. The ability of apes to adopt seasonal life histories may have significance for the potential for sasquatch to adapt to temperate climates.

Furthermore, the remnant species of modern great apes do not fully represent the versatility exhibited by some of their fossil relatives. For example, the ancestral apes became a diverse and successful radiation in Eurasia, where they clearly exploited more seasonal woodland environments. Indeed, much of early ape evolution likely occurred in temperate to subtropical forests in northerly latitudes and possibly higher elevations of Europe and Asia, prior to their expansion into Africa.

Finally, this reviewer's generalization about temperate forests seems to reveal a lack of familiarity with the richness of wild food resources in the rain forests of the west coastal U.S. and Canada available to a large generalized omnivore. In the subalpine habitats of the temperate "rain forests" of the Pacific Northwest and Rocky Mountains, there is an impressive abundance of plant and small mammal resources as I have come to understand through ongoing fieldwork with wildlife biologists and botanists. These potential habitats seem to lie at the core of reported sasquatch activity.

Are there any clues or inferences that address the posture and locomotion of *Gigantopithecus?* Is it reasonable to speculate that bipedalism may have emerged convergently in both early hominids and *Gigantopithecus?* Ciochon continues the search for fossils of *Gigantopithecus*. In his book, *Other Origins: The Search for the Giant Ape in Human Prehistory*, he described the concerted but as yet unsuccessful attempts to locate a skeleton. Without the skeleton of the torso and limbs, the postcranial skeleton, or the base of the skull, which reveals how the skull was poised on the spine, researchers are very limited in what can be inferred about how *Gigantopithecus* stood or walked. The known extant apes are to some extent arboreal and employ powerful arms to suspend themselves below branches where they find the fruit that constitutes a significant fraction of their diet. A common legacy of life in the canopy may have implications for *Gigantopithecus*'s limb proportions. Arboreal apes like the orangutan have proportionately longer upper extremities than do terrestrial quadrupeds such as baboons. Chimps and gorillas spend a great deal of time on the ground, but their apish limb proportions and specialized hip structure constrain them to use a modified form of quadrupedalism called knuckle-walking, although they are capable of walking on only their hindlimbs, when carrying food, nesting

material, *etc.* Jane Goodall observed a chimp in the Gombe, who was stricken with polio leaving its arms paralyzed, which walked exclusively bipedally. The bonobos are even more adept at ambulating bipedally.

Given *Gigantopithecus*'s large size, activity in the treetops was virtually prohibited, and tropical fruits out of reach. It was most likely ground-dwelling, or terrestrial. Once restricted to the ground by its bulk, there would be only two locomotor options—either quadrupedalism (including a possible form of knuckle-walking or perhaps fist-walking) or bipedalism. Dr. Grover Krantz, physical anthropologist at Washington State University, proposed that the configuration of the jaw of *Gigantopithecus* and its relationship to the position of the neck indicate upright posture and bipedalism in this species. Krantz observed, ". . . these [the bodies of the mandible] diverge toward the rear in a remarkable manner. This divergence is so extreme that it would make sense only if the base of the neck was positioned so far forward as to require this spread in order for it to fit between the jaw's rear extensions. Such a neck orientation would have to be vertical, and thus indicates a fully upright posture . . . With the teeth being of a clear hominoid [ape] design, it follows that *Gigantopithecus* was also a brachiator, like all other hominoids. These animals were much too large for arboreal locomotion, but they still would have had the broad shoulders of that adaptation."



The shape of the thorax and the placement of the shoulder blade in an ape (gorilla) and a monkey (macaque) (Reproduced from a drawing by Jack J. Kunz)

The climbing and arm-hanging behaviors of apes are correlated with a distinctive shape of the chest and shoulder. Apes have a broader flattened rib cage with the shoulder blades positioned on the back of the chest and the shoulder joint directed to the side and slightly upward, whereas quadrupedal monkeys tend to have deep narrow chests, with the shoulder blades positioned on the sides of the rib cage and the shoulder joint pointed downward. The square shoulders of a hominoid are the consequence of a stout clavicle, or collar bone, which provides a bony anchor between the shoulder and the torso, critical in arm-hanging. It also acts as a strut holding the shoulders squarely out from the rib cage. This is very different than the sloping shoulders of an upright bear, for example, with reduced clavicles. These modifications of the ape shoulder render it less adapted for quadrupedal locomotion, since the joint is subjected to shearing forces that would tend to push the arm past the shoulder blade, rather than having the arm and shoulder blade lined up in compression. This would be an even more critical factor in a very large-bodied ape like *Gigantopithecus*. We might expect there to be strong selection to avoid bearing weight on the

forelimbs, while favoring bipedalism. Therefore, while Krantz's hypothesis has met with some criticism, it would seem to have a sound basis and hold a better than fifty-fifty chance of being correct—either terrestrial quadruped or terrestrial biped. It certainly deserves consideration pending the discovery of skeletal evidence to refute it.

Living in a mountainous habitat may have also influenced the evolution of bipedalism in *Gigantopithecus*. The mountain gorilla exhibits a trend that may have been paralleled alleled and extended in the sasquatch. Mountain gorillas live on the slopes of the Virunga volcano chain in East Africa. Adults spend over 95 percent of their time on the ground, venturing only occasionally into the trees to feed, and then staying very close to the central trunk of the tree. They do not use their feet in a quadrumanus manner when feeding, as do chimpanzees. Their feeding is usually manual and oral. The foot of the mountain gorilla displays several trends that are associated with its more terrestrial lifestyle. Dr. William Straus describes the distinctions thus: "The foot of the highland gorilla seems to be relatively broader than that of the lowland form; the heel is broader and better developed [longer]; the great toe is relatively longer, and the free digital length much less." By extending these distinctive trends a bit further, one arrives at a basic description of the distinctions of the enigmatic sasquatch footprints. The much greater body size of *Gigantopithecus* and the possibly longer terrestrial tenure in a steep mountainous forest habitat may have shaped its lower extremity gorilla into what we now observe as the sasquatch foot.

Cast of the foot of a mountain gorilla

In the past anthropologists had suggested that *Gigantopithecus blacki* was a strict herbivore with a highly specialized diet of bamboo, much like the giant panda. There is evidence of tiny silicate phytoliths embedded in some teeth of *Gigantopithecus*, indicating grasses (bamboo is a grass) in the giant ape's diet, but other evidence from the wear pattern on its teeth indicates a more generalized dietary adaptation. Examination of the pattern of microwear features —pits and scratches—on the surface of the molar teeth shows the greatest similarity between the patterns on the teeth of *Gigantopithecus* and the omnivorous common chimpanzee. So it appears *Gigantopithecus* 's diet included not only grasses, but also fruit and seeds of woody plants, insects, and a host of other items. As more is learned about the feeding ecology of the great apes the list of plants eaten continues to grow, in some instances numbering into the hundreds of species. It is also possible that *Gigantopithecus* supplemented their diets with significant amounts of meat, as is the case with chimpanzees. Hence it appears they were generalized omnivores, rather than specialized grazers of bamboo. This could have permitted them to exploit a much broader range of habitats.

Even granting the possibility that the sasquatch may have originated from Asia and may have been in North America for a mere few hundred thousand years, the vexing fact remains that no fossils of such an ape have ever been found on this continent. This time period during which the sasquatch may have inhabited North America is quite brief, geologically speaking. In terms of the fossil record, it is a veritable "blink of the eye," and uncovering fossils from such a particularly short time span would be rather exceptional, especially if the primary habitat were coastal rain forests that are now underwater. Fossilization is actually a rare process, requiring a very specific set of conditions. Most bones are promptly recycled—consumed by scavengers, or carried off by rodents or porcupines—as calcium is a rare commodity in the environment. What bones remain exposed to the elements are rapidly weathered and deteriorated. Should the necessary conditions for fossilization be met, the eventual exposure and discovery of fossils are even further rare and exceptional events.

The recent discovery of a fossil brown bear in Alberta, Canada, illustrates the significant implications of the serendipity of paleontology. Fossil bears were not known from below the extent of the ice sheets prior to 13,000 years ago and all bears south of the glaciers were genetically distinct from those north in Beringia. Where did they come from? The newly discovered fossil turned out to be over 26,000 years old—twice as old as previous southern fossil bears—yet genetically similar to them. "It's always been a mystery why brown bears didn't

migrate farther south if they were in Beringia as early as 100,000 years ago, and the passage wasn't blocked until about 23,000 years ago," wondered Paul Matheus, paleontologist at the Alaska Quaternary Center. Although there was an implicit expectation that a population of bears with this distinct genetic identity had extended their range southward much earlier than could be demonstrated in the fossil record at present, there was a complete lack of *any* fossil specimens for a period spanning possibly as much as 80,000 years.

Indeed, the fossil record for most animals is unavoidably spotty. Bob Martin, a paleoprimatologist, estimated there was at the time a total of over 235 known species of living primates, and that 474 extinct species of primate had been described in the scientific literature. Assuming an average species duration of approximately 2.5 million years, based on the number of fossil species known in each stratigraphic interval contrasted with the number known today, Martin estimated that as many as 8,000-9,000 extinct primate species have yet to be discovered in the fossil record. "Our calculations," concluded Martin, "indicate that we have fossil evidence for only about 5 percent of all extinct primates, so it's as if paleontologists have been trying to reconstruct a thousand-piece jigsaw puzzle using just fifty pieces."

In light of such figures, how damning is the lack of fossils for sasquatch? There is an adage among those who search for and study vertebrate fossils—the absence of evidence alone is not the evidence of absence. In other words, just because there is no fossil evidence of sasquatch in North America, does not of itself constitute *conclusive* evidence that an ape species didn't or doesn't exist there. Were it not for a couple of jaw fragments and a number of isolated teeth, there would be no fossil evidence of the past existence of *Gigantopithecus* in eastern Asia. A case in point was the recent discovery of a new species of extinct fossil ape in Thailand. Dubbed *Lufengpithecus chiangmuanensis*, this novel ape, believed to be an ancestor of the orangutan is estimated to have weighed about 70 kg (154 lbs) and to have lived between 10 and 13.5 million years ago. Prior to this initial fossil discovery, the existence of this ape species, its role in its environment, and its possible phyletic relationships would have remained unrecognized. Its recovery and description simply affirm that many more significant fossil discoveries remain to be made.

Considering these factors of fossilization and the incremental pace of new discoveries, the lack of sasquatch fossils in North America is not such a surprising circumstance at all, even allowing that the initial range of sasquatch may have extended beyond the coastal forests that were eventually inundated by rising sea levels. Added to this situation are the especially poor fossilization

conditions prevailing in the Pacific Northwest with its moist coniferous forests and predominantly volcanic soils. The acidity of forest soils is not conducive to the preservation of bone.

Articulated skeleton of a giant black bear discovered in a sealed cave on Vancouver Island, British Columbia. Age 10,000 years. (Courtesy of Martin Davis)

On the other hand, the acidic groundwater does create caves in limestone sedimentary rocks. The limestone buffers the acidity, allowing exceptional preservation of bone in cave deposits. Where these caves occur they are generally of two types—lateral passages used as denning sites by bear, otter, bats, and small rodents, and vertical sinkholes, some with small openings near the surface. At the bottom of these vertical shafts a cone of detritus accumulates. The in-falling coarse material, wood, and moisture are themselves not conducive to bone preservation. Unless the animals inhabit the caves or are carried there by predators, their remains are not well represented. Sitka black tail deer are common in these regions and yet even their remains are rarely recovered. This biased sampling of the paleofauna is being explored and studied by Dr. Timothy Heaton, of the University of South Dakota, and his colleagues, as they excavate the sedimentary deposits in remote caves of southeastern Alaska. The scarcity of the remains of quite common animals is significant; the lack of remains of a much rarer species is therefore not at all surprising, particularly given the infrequent mention of signs of cave habitation present in accumulated sasquatch reports. If the prospect of finding fossil remains of sasquatch in North America is ever realized, they will most likely be fortuitously preserved and discovered in

such cave deposits.

Curiously, a scant or altogether absent fossil record for the living great apes has not raised undue concern among paleoprimatologists. Until just recently, there have been virtually no generally accepted fossil ancestors in Africa of chimpanzees or gorillas, despite their presumed presence in Africa for over seven million years. In 2005, Nina Jablonski and Sally McBrearty announced the discovery of a single molar and a pair of incisors identified as the first ever chimpanzee fossils. The three teeth likely came from a single individual that lived about 545,000 years ago. Commenting on this dearth of fossil evidence for living hominoids, Peter Andrews of the British Museum of Natural History said, "The apes seem to have sprung out of nowhere." Obviously this is not literally the case, nor did Andrews intend it to be taken literally as such. Either fossil remains of gorillas and chimps, however rare they may be, have yet to be found in African sediments, or they evolved elsewhere and are geologically recent interlopers on the African landscape. In fact, putative fossil ancestors of the African ape/hominid clade *have* been recovered in adjacent Eurasia that presumably migrated into Africa along with other elements of the current African fauna, such as that African symbol, the giraffe. Likewise, only recently has a new species of fossil Asian hominoid been proposed as the most likely ancestor of the orangutan. It bears striking dental similarities to the orang and originates from the geographic area of Pleistocene orangs. Also of interest, the plants associated with this orang ancestor exhibit a strong and surprising affinity to African flora and indicate a possible, and previously unrecognized, dispersal corridor between Africa and Asia.

Field primatologist Julian Kerbis Peterhans (right) and assistant searching among the litter of the dense

Kibale forest for chimp remains (Courtesy of Richard Wrangham and Julian Kerbis Peterhans)



The remains of a chimpanzee skeleton partially buried on the floor of the dense forest (Courtesy of Richard Wrangham and Julian Kerbis Peterhans)

Dr. Julian Kerbis Peterhans, of the Field Museum of Natural History, and colleagues have discussed the factors involved in the taphonomy, or the fate of the remains of dead chimpanzees at their site at Kibale, and at other study sites in Africa. In their initial survey they recovered, over a period of nine months, the remains of seven chimps, two that had died quite recently, four that were only represented by cranial remains. Over the next forty-three months only a single chimp was recovered, suggesting that the initial rate of recovery was biased by an accumulation of remains over an extended period prior to collection. At Kibale the pH of the soil is neutral, which contributes to the persistence of the skeletal remains in contrast to the more rapid demise of bone at sites with more acidic soils. Still the significance of finding only a single set of remains in forty-three months at a site of concentrated chimp activity, where multiple researchers are specifically being watchful for such remains, should not be underestimated. Dense forest cover plays a significant role even where conditions are conducive for bone persistence. In nearly 2.3 million km^2 of forest in Zaire only six archaeozoological sites have been described and all lie at the periphery of the forest with none having produced chimp fossil remains. The paucity of *Gigantopithecus* fossils is better appreciated when considered with such figures in mind. Likewise, the absence of sasquatch fossils should be no more inexplicable.

At the very least *Gigantopithecus* dramatically illustrates the point that one or more species of ape did attain dimensions on the order of those attributed to sasquatch. It is recognized to have lived until quite recently in a region where reports of giant apelike figures that leave oversized footprints are documented today and from whence, in both a biogeographical and paleoecological sense, it could have conceivably extended its range into North American habitats. Although it is certainly tempting to connect the dots, this can only be suggested in a qualified manner, based upon the incomplete evidence at hand—of sasquatch, of the natural history of *Gigantopithecus*, and of the overall biogeographical history of hominoid evolution and dispersal. Nevertheless, the *possibility* is certainly sound and the *plausibility* is quite reasoned and tenable.

MAKING A BIG IMPRESSION: THE SKOOKUM BODY CAST

The fossil record for many species is meager at best, or altogether nonexistent. In some instances only the trace of the organism is preserved—the mold of a shell, the infilled burrow, or the petrified footprints left behind in silt or volcanic ash. Many animals today are reclusive and effectively avoid human contact. Their presence is only betrayed by the subtle tracks and traces they leave behind, commonly during nocturnal activities.



Knuckle prints cast by Paul Freeman, associated with 14-inch tracks, compared to a similar imprint of the author's knuckles made in firm clay. Notice the contrasting orientation of the thumb and the apparent indication of a thumbnail.

Although infrequently seen for more than a fleeting glimpse, enormous

footprints have repeatedly provided mute but intriguing indication of sasquatch's suspected passage. Occasionally impressions of other than oversized humanlike feet are found in the forest—those of hands, knuckles, and buttocks. In one instance, the unmistakable imprint of knuckles was found associated with a short line of 14-inch footprints in the Blue Mountains of southeastern Washington. Had a sasquatch momentarily supported its weight on the backs of its fingers in a decidedly apelike fashion? The cast visibly preserves the impress of the backs of the middle phalanges, or the middle segment of the four fingers, the same parts of the fingers that a gorilla, chimp, or less frequently an orangutan or even gibbon, would rest upon when knuckle-walking, but the sasquatch imprint displays none of the broad thickened pads of the specialized knuckle-walking fingers of the African apes. The sasquatch knuckles combined measure over 5 inches across, comparable in size to the disproportionately large hand of a male mountain gorilla. What is so impressive about the anatomy of this cast is the subtle, yet readily discerned by the trained eye, trochlear or "spool" shape of the distal ends of proximal phalanges. This shape is especially prominent on the third or middle finger of the cast, it being the largest. On the other digits it is best discerned by lightly running a fingertip over the surface contour of the cast. Despite their imposing breadth, the segments are not exceptionally long and indicate unhumanly short stout fingers. It recalls a muddy 11-inch handprint that was left on the side of a white house near Fort Bragg, California, in 1962. A college art professor, Chuck Edmonds, of Southern Oregon State, traced the handprint. It showed a long palm and proportionately short thick digits, more subequal in length than a human hand. The thumb was relatively long and more in line with the remaining fingers. The muddy print was sufficiently clear that Edmonds could make out details of fingerprints, and observed that no whorls were present.

Outline of the muddy handprint left on the side of a house in Fort Bragg, California, compared to that of a human hand (Courtesy of Chuck Edmonds)

Returning to the knuckle prints, the end of a very thickly padded thumb juts off from the knuckle imprints, set at what seems to be an odd angle when compared to a human thumb in a hand of similar posture. It would require the thumb to be rotated outward from the remaining fingers, with its pad facing out in nearly the same direction as those of the other fingers, rather than turned toward them, not to mention shorter bones of the palm, the metacarpals. The placement of a distinct impression of the edge of the thumbnail seems to confirm this inferred position. It is this inward rotated set of the human thumb that permits opposition of the thumb to the fingers, critical to the precision grip. The precision grip appears to have been refined relatively late in human evolution and is correlated with the progressive sophistication of tool manufacture.

Interestingly, other handprints, as well as careful eyewitness observations corroborate the apparent lack of opposition in the thumb. When noticed carrying objects or hefting rocks, the sasquatch thumb has been described as lying parallel to the other fingers rather than opposing them. Grover Krantz drew attention to this feature when he reported on two handprints in the *Northwest Anthropological Research Notes* in 1971. The few casts of handprints attributed to sasquatch uniformly exhibit a lack of exceptional enlargement of the thenar muscles, the swelling of muscles at the base of the thumb that lend its drumstick appearance. In humans these muscles are responsible for the distinctive

movement of the thumb in opposition, which involves abducting, rotating, and flexing the thumb across the palm. In fact, when these muscles in the human hand become paralyzed and atrophy due to nerve damage, their wasted appearance is referred to as “ape hand.” The lack of specialization of the thumb accords with the universal lack of observations of tool use by sasquatch, beyond that exhibited by other great apes, such as brandishing sticks, or lobbing stones.



Comparison of the hands of a human, chimpanzee, and gorilla

A handprint found on the bank of a pond and cast by Bob Titmus (Courtesy of Willow Creek-China Flats Museum)

In the 1980s, Bob Titmus had returned to California to continue his search for Bigfoot. He located a line of tracks in a gravel bar that led to a water hole. These were photographed and cast, although the gravelly substrate precluded much detail beyond the contours of the deep impressions. The sasquatch had apparently climbed into the water hole and then climbed back up the steep muddy slope on all fours, leaving a series of slip marks, including one rather clear handprint. The fingers appear elongated due to the slippage, but the most striking feature is the orientation of the thumb imprint. The broad pad of the thumb lies close to the remaining fingers, and its pad is facing in the same direction, rather than rotated toward the palm. Once again, this distinctive anatomy of the nonopposed thumb is evident.

In 1986, Paul Freeman discovered a handprint in rather wet mud. The imprint appears somewhat distorted, presumably as a result of the motion of the hand and the slackness of the mud consistency. The handprint is quite large, over 8 inches across the palm, and correlates with the large 17-inch tracks reportedly associated with it. The hand exhibits the more apelike characteristics of relatively flat palm and nonopposable thumb. It also displays the thick and nearly subequal fingers with extensive webbing between the digits. The flexion creases on the palm and digits are faint, as is to be expected when the hand is bearing weight, but discernable, permitting inferences to be drawn about the placement of joints in the fingers. There is some variability to the arrangement in primary and subsidiary creases, which in humans has given rise to repeated interest throughout history in chiromancy or palmistry. From a strictly functional perspective the primary creases are of two fundamental orientations: running across the palm (transverse) or running the length of the palm (longitudinal). The transverse creases result from the flexion of the knuckles or metacarpophalangeal joints. The transverse creases in Freeman's cast indicate that the palm extends farther past the base of the fingers in a more apelike fashion. Although the fingers appear disproportionately short, this impression is the result of more extensive webbing between the fingers. In humans, the distal transverse crease (the "heart line") typically runs between the second and third digits, while in apes it usually runs completely across the palm to the gap between the thumb and index finger. This distinction of the human crease is thought to indicate the greater independence of movement of the index finger, while in apes it moves more in concert with the remaining fingers. In this respect the sasquatch handprint more resembles the human configuration. The

longitudinal creases result from actions of the thumb. The opposability of the human thumb results in two or more distinct longitudinal creases that extend to the wrist, dividing the "ball" from the "heel" of the palm. These mark the movement of the thumb as it crosses the palm in opposition to the remaining digits. In the sasquatch handprint, these creases are noticeably absent or short, in agreement with the configuration of the nonopposable thumb.



Handprint cast by Paul Freeman and skeletal reconstruction by author based on position of flex ion creases

A partial fist imprint cast by Paul Freeman, who at the time mistook it for "toes," compared to the author's hand

Paul Freeman found another example of a handprint, although he was unable to interpret it. It was found in 1992, north of the Mill Creek watershed associated with a partial footprint of a smaller individual whose tracks had been found repeatedly in the area (discussed later). Freeman had characterized the imprint as "toe marks," but it appears to be the partial imprint of a fist. The outer edge of the palm and the knuckles (metacarpophalangeal joints) of the four fingers are impressed at an angle. What is noteworthy is the relatively subequal size of the

knuckles. This detail is consistent with the proportions of the digits evident in other handprints. The impression of the fifth is slightly distorted, but only slightly less prominent than the others. Nor does it appear to be flexed at the carpometacarpal joint, as would be the case in a clenched human fist. Instead the knuckles are more aligned relative to one another. The third knuckle is the most prominent and skin detail in the form of flexion creases are preserved on the third and fourth knuckles.

In May of 1993, east of Walla Walla, Washington, Paul Freeman discovered tracks that led to a sandy bank along Dry Creek. The sasquatch apparently sat down on the edge of an elevated bank and left a distinct imprint of its derriere, which Freeman cast. It measured 14.5 inches across at its widest point. When I first saw the cast, I could not restrain a chuckle (a response I have found the cast evokes from most observers on first exposure to it). Then as I considered it more closely, the appropriate anatomical landmarks became readily apparent. The coccyx or tailbone was evident at the commencement of the deep natal cleft. The cheeks of the buttocks were prominent and apparently well muscled. The depth of the imprint and the clarity and width of the natal cleft indicated a well-developed musculature, with little indication of compressive expansion of excess fat. The delineations of the gluteal folds were evident, separating the upper thighs from the buttocks. The striations of hair could be seen streaming downward and inward across the cheeks toward the natal cleft, but leaving a midline margin of relatively hairless skin; the indications of hair on the backs of the thighs were streaming downward. Below the tailbone was the suggestion of a sphincter and there was no indication of a scrotum, but the possible hint of labia. In spite of my initial involuntary chuckle, this cast was quite “anatomically correct” and yet distinctly nonhuman in dimension and proportion. Its consistency with eyewitness observations of prominent buttocks on sasquatch is noteworthy. The gluteus maximus is a powerful retractor of the hip, important in climbing steep mountainsides, as well as holding the torso erect over the lower limbs. Its apparent development in a giant bipedal ape is appropriate to its posture and habitat.



Buttocks imprint found associated with sasquatch tracks and cast by Paul Freeman

The singular discovery in September 2000, of a partial body imprint of what appears to be a large hairy animal was something of a sensation. The Bigfoot Field Researchers Organization (BFRO) had mounted a ten-man expedition to the Cascade Mountains of southern Washington. They established camp near a site called Skookum Meadows, an appropriate name, as events would have it. *Skookum* is a Chinook jargon word for "strong" or "powerful," and was often used to refer to evil deities. When used in connection with localities, the word *skookum* generally indicates a place inhabited by a *skookum*, or evil god of the woods. Native Americans avoided *skookum* places considering them to be haunted. In contradistinction to a *skookum*, a *hehe* was a good spirit and a hehe chuck was a fine place for games, races, and other sports and festivities. The geographical distribution of modern equivalents of place names bearing elements of skookum, demon, devil, diablo, or spirit is remarkably coincident with the distribution of contemporary reports of sasquatch encounters or footprint discoveries.

The BFRO expedition's objectives were to detect and document evidence in the field of a large primate, including tracks, hair, scat, signs of foraging, vocalizations, and, if fortunate, a sighting. To this end they set about to experiment with various instruments and attractants. Large broadcasting speakers were set up to test for responses to recordings of not only purported

sasquatch calls, but other recordings that might pique a primate's curiosity, such as the sounds of human children playing and infants crying. Thermal imaging and starlight night vision-equipped cameras were on hand. Food baits and pheromone chips were deployed in efforts to lure the quarry to suitable tracking surfaces or, if opportune, into sight. On two separate occasions unidentifiable vocal responses to the broadcasted calls were heard in the distance, once faintly captured on tape. One response call was made from much closer proximity and will be described in chapter 10. Several sets of large, but indistinct, tracks were located and documented. On the morning of Friday, September 22, LeRoy Fish, a professional wildlife ecologist; Derek Randies, a landscape architect and avid outdoorsman; and Richard Noll, an aerospace metrologist, together left camp early to check on the bait that had been laid out during the previous night. At a muddy turnout along a Forest Service road in the general direction from which the previous night's vocalizations had originated, they noticed that a pheromone attractant that had been wired to a nearby tree was missing and several pieces of fruit deposited near a large puddle were gone. Some fruit fragments, bearing what appeared to be broad shovel-shaped tooth marks, were scattered about an unusual depression in the adjacent moist clay soil. The depression appeared to be the imprint of a large hairy animal, as patterns of hair striations covered the various portions of the puzzling configuration. The three investigators considered what sort of animal could possibly be responsible for the impression. One by one, they eliminated the most likely potential candidates—deer, elk, bear, and coyote—and eventually came to the realization that the only other large hairy animal remaining, with the bulk and requisite anatomy, was sasquatch.

The impressions appeared to include that of a left forearm, buttocks, thigh, and heels. But where were the familiar sasquatch footprints? The puddle of water was surrounded by a halo of moist loamy soil. Beyond that perimeter the soil was relatively hard, dry, and choppy from previous traffic—vehicular, pedestrian, and animal. The surface conditions there would not be expected to take the track of a padded foot lacking sharp-edged hooves and claws. Apparently the sasquatch had approached the puddle, lain down across the halo of moist soil on the periphery of the puddle without stepping there, then leaned onto its left elbow and forearm to reach in with its right arm toward the puddle for a sampling of the fruit, while pushing against the mud with its heel. Unfortunately initial references to the site conjured images of a mud wallow, and questions about why a sasquatch would flop into a gooey morass to retrieve some bait. The "mud" was moist soft loamy soil of a consistency ideal for taking

up the detailed impression of hair and skin texture without adhering to the body.

Was the sasquatch deliberately trying to avoid leaving tracks in the soft soil? Indications of such behavior have been noted previously in descriptions of sasquatch encounters and are perhaps suggested by the limited tracks left behind. On such occasions the lay of tracks suggested an intentional effort to avoid patches of snow or soft soil that might betray its passing. Would the intentional avoidance of leaving sign be uncharacteristic behavior of an ape, or even beyond its mental capabilities? Recently, Dr. Sue Savage-Rumbaugh, a primatologist from Georgia State University, and colleagues suggested that chimpanzees intentionally break vegetation as a form of trail marker for the benefit of stragglers when the group is spread out during foraging forays. It could be a series of stomped down plants, a broken leafy twig dropped in the trail, or even a twig stuck perpendicularly into the ground. These twigs were pushed at least 8 cm into the ground, clearly as a deliberate act. The "trail signs" were so distinct that if the field researcher arrived at a sleeping tree after the group had already departed, she could readily follow the markers and catch up to the chimps. When traveling a muddy path, however, where their footprints are clearly discernable, the chimps expended no effort to leave trail sign in the thick vegetation, suggesting an awareness of their own footprints as indicators of their passage.

Interpretation of the reclining pose of the sasquatch at Skookum Meadows, based on the imprint (Courtesy of Pete Travers)

I have personally had experience with captive chimps recruited for footprint studies that seemed to indirectly corroborate this awareness of their own

footprints that is suggested by Savage-Rumbaugh's observations. The study chimp displayed awareness that he was responsible for the footprints left in a sand track box, and recognition of my interest in examining them. He even took to wiping them away in order to avoid going back into a holding cage while I examined and documented his tracks between bouts. Could the sasquatch be aware that their footprints betray their presence in an area? Anecdotal accounts of the behavior of predators such as bears and big cats would seem to indicate an awareness of their own tracks. It hardly seems unreasonable to infer that a hominoid with a higher level of intelligence would exhibit at least as much, if not more cognition.

There is also the matter of the posture inferred from the configuration of the impression. Is it reasonable to imagine a sasquatch simply taking a timely pause on its nocturnal foraging circuit to recline and munch on a few opportune apples? Given their tendency to hold the trunk more upright (orthogrady) as compared to typical quadrupeds, great apes do tend to squat or sit while they are feeding. This can readily be observed at feeding time at any zoological gardens with an ape exhibit. While filming gorillas at the Seattle Zoo, Rick Noll recorded just such an instance. It was quite intriguing to watch the video of a reclining gorilla resting on its forearm, digging in its heel to adjust its position and reach for apples, taking bites and letting pieces drop to the ground in a manner very reminiscent of the scenes envisioned for the Skookum impression.



Inferred relationship of the reclining sasquatch to the pond and fruit at the imprint site (Courtesy of Pete Travers)

Fish, Randies, and Noll, experienced with animal sign, were confident that it was a living animal that made the imprint, but without a clear sasquatch track leading to or from the impression, could they be certain what sort of animal? None of the obvious tracks of hoofed deer and elk, or clawed coyote, present at the scene could be directly associated in a meaningful context with the impression. These tracks simply crossed the imprint, or skirted around it. Of these candidates, the only possible animal with sufficient bulk to create an impression of such dimensions might have been an elk. This would become the focus of our comparisons.

In order to cast the imprint, all the plaster on hand was amassed—over two hundred pounds of it (not such an extraordinary amount when you consider any sasquatch investigator worth his salt has a fifty-pound bag of hydrocal in his trunk). Aluminum tent poles were donated to reinforce the large slab of plaster. The skillfully executed cast, measuring 3½ × 5 feet, was gingerly loaded into a cushioned truck bed and transported back to Derek Randles's workshop. From there, additional scientists were contacted and arrangements were made to clean and examine the cast.

I first learned of the incident just after the cast arrived in Randles's workshop

at his home outside of Seattle. I quickly made arrangements to fly there that weekend. I was joined by an initial gathering of scientists that included Fish, who participated in the discovery and casting of the impression; Dr. John Bindernagel, wildlife biologist; Dr. Grover Krantz, physical anthropologist; and Dr. Ron Brown, M.D., an African game guide. Once more, comparisons with impressions of local animals such as elk, deer, bear, and coyote were discussed at length. Could any of these animals be responsible for the shape, dimensions, depth, and attributes of this imprint? The conclusion seemed inescapable—the appearance of the imprint suggested a large hominoid. Preliminary measurements indicated the inferred body dimensions to be 40-50 percent greater than my six-foot frame. The unanimous consensus was that this could very well be a body imprint of a sasquatch.

The author beside the cast of the Skookum imprint, pointing to the most distinctive heel impression (Courtesy of Ron Brown)



Close-up of the heel and Achilles tendon impression on the Skookum cast compared to a cast of a human heel. Note the coyote print in the sasquatch heel impression. (Courtesy of Rick Noll)

Of particular interest to me was what could only be interpreted as a distinct heel impression. As I meticulously removed the encrusting soil, it appeared that the heel bore skin ridge detail. Once the heel was thoroughly cleaned, a thin latex peel was made of the skin detail. Consultations over the apparent dermatoglyphics, or skin ridges, were had with latent fingerprint examiner, Officer Jimmy Chilcutt. He found them to be consistent in texture and appearance with other specimens of purported sasquatch tracks exhibiting such skin ridge detail (more will be said on this matter in chapter 14).

The impress of the back of the leg above the heel showed a pronounced Achilles tendon, a distinct feature of a bipedal primate. The Achilles tendon appeared relatively broad in concert with the wide heel imprint, and anterior to it was a noticeable hollow that would lie behind the tibia, or shinbone. This pronounced hollow is the consequence of the lengthened heel segment of the foot, an adaptation for increased leverage in response to the massive weight of the sasquatch (discussed further in chapter 13). The imprint of moderate length hair could be seen streaming down across the tendon, giving way to hairless skin just above the margin of the sole, which in turn gave way to the texture of ridged friction skin. From here, the remaining contact surface was painstakingly cleaned of the encasing dirt using dental picks, soft brushes, and magnifying lenses. Hairs and fibers were collected in small paper envelopes as they were encountered.

Detail of the surface of the heel impression taken from a thin latex peel of the cast, demonstrating the hair striations coursing across the Achilles tendon, and skin detail over the heel giving way to coarse dermatoglyphics

The coincidence of a commercial film crew on hand at the discovery site and the proximity of an adjacent Forest Service road raised some concerns about the credibility of the incident. Could the Skookum cast have been a hoax committed by one or more of the expedition members themselves or perhaps perpetrated upon them by someone else aware of their location and activities? In such a case, the imprint would have to have been laid down at the site sometime between 3:00 A.M. and 6:00 A.M., the interval between the deposition of the fruit and the return of the investigators to the site the following morning. Recall that bites of the fruit were scattered *upon* the imprint (as well as superimposed animal tracks). The hoaxer(s)would have left no sign of their activities while fabricating the detailed impressions of hairy body parts. They would have had to deeply impress, rather than excavate, a coherent shape, as indicated by the flow and extrusion of the loamy soil from beneath a heavy body. They would have had to uniformly apply a rather long hair pattern that was distinct from common animals, such as elk, but suggested similarities to hominoid patterns of hair distribution and flow. This would have been accomplished in an apparently seamless fashion without interruption or over striking of the hair impressions. They would have had to work out the proportions and points of contact of a hominoid body that was about half again as large as a six-foot man. An intentional hoax seemed unlikely, but a case of misidentification remained a possibility in need of further consideration.

Skookum cast with indication of hair flow pattern superimposed and isolated (Courtesy of Owen Caddy)



Typical posture of a bedding bull elk, with the resulting pattern of impressions. The darkest regions indicate the position of the hooves

Eventually, careful comparisons to elk imprints were made at multiple game ranches and zoological parks. These comparisons, combined with consultation by professional gamekeepers, ruled out elk as a possible candidate for the imprint. The obvious heel imprints and forearm imprint simply could not be accounted for by the anatomy of an elk. Skeptics opined that the heel imprint was simply the mark of a kneeling elk, without ever examining the cast itself. A wrist of a 650-pound bull elk was obtained by Rick Noll, impressed in soft soil, and cast. Not only did it fail to measure up to the dimensions of the Skookum heel imprint, it was clearly distinct in shape and pattern of hair. The overall orientations of the hair patterns on the Skookum cast were likewise incongruent

with those of an elk. This was made quite evident by comparisons to taxidermy museum mounts. And finally, and perhaps most telling, when an elk rises from a repose it must place its hooves directly under its weight in order to stand, leaving tracks in the centerline of its imprint. Yet there are no elk tracks located in the *center* of the Skookum imprint, only deep and clear elk imprints *skirting* the imprint.

A press release announcing the discovery and plans for a coordinated study of the imprint was issued through Idaho State University's office of university relations:

Written by: Glenn Alford, October 23, 2000

ISU Researcher Coordinates Analysis of Body Imprint That May Belong to Sasquatch

Pocatello. Dr. Jeff Meldrum, associate professor of anatomy and anthropology at Idaho State University, is a member of the scientific team examining a plaster cast of what may be the first documented body imprint of a Sasquatch. The imprint of what appears to be a large animal's left forearm, hip, thigh, and heel was discovered Sept. 22 in a muddy wallow near Mt. Adams in southern Washington state by a Bigfoot Field Researchers Organization expedition in the Gifford-Pinchot National Forest. The investigating team, including Meldrum; Dr. Grover Krantz, retired physical anthropologist from Washington State University; Dr. John Bindernagel, Canadian wildlife biologist; John Green, retired Canadian journalist and author; and Dr. Ron Brown, exotic animal handler and health care administrator, all examined the cast and agreed that it cannot be attributed to any commonly known Northwest animal and may represent an unknown primate. Meldrum, whose research includes comparative primate anatomy and the emergence of human walking supervised the careful cleaning of the cast, and will coordinate its analysis by a scientific team. He first became actively interested in the question of the existence of a North American ape after examining fresh Sasquatch (popularly called Bigfoot) tracks in 1996.

"While not definitively proving the existence of a species of North American ape, the cast constitutes significant and compelling new evidence that will hopefully stimulate further serious research and investigation into the presence of these primates in the Northwest mountains and elsewhere," Meldrum said. Dr. LeRoy Fish, a retired wildlife ecologist from Triangles Lake, Ore., with a doctorate in zoology from Washington State University;

Derek Randies, a landscape architect from Belfair, Wash.; and Richard Noll, a tooling metrologist from Edmonds, Wash., discovered and cast the partial body imprint. More than 200 pounds of plaster were needed to produce the 3-½ × 5-foot cast of the entire impression, which was reinforced with researchers' aluminum tent poles. Other Sasquatch evidence documented by the party includes voice recordings and indistinct 17-inch footprints. Trace evidence attributed to Sasquatch is usually footprints, but impressions of other body parts, including hands, knuckles, and buttocks, have occasionally been found. This unique instance of a partial body impression provides further insights about this elusive ape species' anatomy. Preliminary measurements indicate its body dimensions are 40 to 50 percent greater than those of a six-foot tall human.

After the cast was cleaned, extensive impressions of hair on the buttock and thigh surfaces and a fringe of longer hair along the forearm were evident. Meldrum identified what appear to be skin ridge patterns on the heel, comparable to fingerprints that are characteristic of primates.

The ridge characteristics are consistent with other examples from Sasquatch footprints Meldrum has studied in collaboration with Officer Jimmy Chilcutt, a latent fingerprint examiner with the Conroe, Texas, Police Department. The anatomy of the heel, ankle, and Achilles tendon are also distinct and consistent with models of the Sasquatch foot derived by Meldrum after examining hundreds of alleged Sasquatch footprints. Hair samples collected at the scene and from the cast itself and examined by Dr. Henner Fahrenbach, a biomedical research scientist from Beaverton, Ore., were primarily of deer, elk, coyote, and bear, as was expected since tracks in the wallow were mostly of those animals. However, based on characteristics matching those of otherwise indeterminate primate hairs collected in association with other Sasquatch sightings, he identified a single distinctly primate hair as "Sasquatch."

Sasquatch is a species of North American ape suspected to inhabit the mountainous forests of the Northwest. Its existence remains controversial despite numerous eyewitness sightings and the discovery of enormous footprints.

The official press release by an accredited academic institution precipitated a great deal of attention and interest in the find, both in the United States and abroad. *New Scientist*, Britain's leading popular science periodical, carried a

news feature that portrayed the Skookum impression as the strongest hint yet that Bigfoot or sasquatch may indeed exist. The article also made note of the challenge to get mainstream science to even consider the possibility and examine the evidence. Dr. LeRoy Fish was quoted, "If we can just get other scientists to look at this with an objective view, I think they'll say there must be something out there." Few scientists were willing to take up the challenge. *Field & Stream* magazine ran a news item featuring the cast that precipitated additional responses from a number of outdoorsmen who had encountered inexplicable tracks that resembled those attributed to sasquatch.

Eventually the cast was examined jointly by other expert scientists, including Dr. Daris Swindler, a primate anatomist from the University of Washington and author of *An Atlas of Primate Gross Anatomy*, and Dr. Esteban Sarmiento, a research associate of the American Museum of Natural History with extensive experience studying gorillas in the field. As a fellow anatomist, Dr. Swindler was likewise especially impressed by the appearance of the Achilles tendon. In fact, after a number of past public statements of skepticism concerning the sasquatch phenomenon, the anatomy of the Skookum cast ultimately convinced him of the probable existence of a bipedal North American ape. Dr. Swindler's incisive comments on this feature fully corroborated my preliminary observations: "There is a combination of two muscles, the gastrocnemius and the soleus. In humans about a third of the way down the leg they fuse together to form the tendon of Achilles that then continues on down and attaches to the back end of the heel or calcaneus. *This* (referring to the cast) is a well pronounced, well-developed tendon of Achilles." In nature there is definite correlation between form and function. A well-developed Achilles tendon in a heel impression made by a large ape could be reasonably interpreted only one way. "This was a bipedal animal," concluded Swindler. "In my opinion, the Skookum body cast is that of an upright descendent of *Gigantopithecus."*



Dr. Daris Swindler, professor emeritus of anatomy, commenting on the implications of the Skookum heel impression (Courtesy of Doug Hajicek /Whitewolf Entertainment, Inc.)

Dr. Esteban Sarmiento, primatologist and research associate of the American Museum of Natural History, was consulted on the analysis of the Skookum cast. (Courtesy of Doug Hajicek / Whitewolf Entertainment, Inc.)

The cast reveals another hallmark of bipedalism—a pronounced buttocks, produced by a short flaring hipbone and well-developed gluteal muscles. The gluteus maximus in particular is a powerful retractor of the hip, a particularly important function when walking up steep inclines, characteristic of mountainous terrain. It also aids in keeping the torso upright over the supporting legs when in an erect posture. The presence of the pronounced buttocks in the Skookum cast is correlated with the Achilles tendon, combined indicating an adaptation to bipedalism in this hominoid.

Dr. Sarmiento, with extensive field experience observing primates, was particularly interested in the hair strands, a few which could still be seen trapped in the plaster of the cast. These had been systematically collected during the cleaning of the contact surfaces of the cast, sorted, and identified. As was to be expected, many of the hairs were from such animals as the deer, elk, and coyote, whose tracks were present in the vicinity of the impression. However, a number of the hairs could not be readily identified, although they closely resemble primate hair in many characteristics. These hairs are very similar to an assemblage of independently collected hair samples curated by Dr. Henner Fahrenbach that are suspected of belonging to sasquatch (see chapter 15). Dr. LeRoy Fish independently confirmed that a selection of hairs taken from the cast indeed exhibited primate characteristics.

Dr. George Schaller, renowned naturalist, conservationist, and director of science for the Wildlife Conservation Society in New York City, was afforded an early opportunity to examine the cast. His attention immediately gravitated to the distinct forearm impression and the broad heel imprint. Having studied ungulates, i.e., hoofed mammals, on several continents, Schaller was familiar not only with their anatomy, but also with their behavior. He did not see how the imprint could be attributed to elk bedding. On the other hand, his pioneering field studies of the mountain gorillas made him particularly qualified to draw comparisons to the anatomy of that African hominoid. Although he had frequently witnessed gorillas in the wild reclining during their foraging sessions, he had never taken notice of the impressions they may have left, as the ground was typically heavily vegetated. He summarized his impressions by noting that the Skookum cast, combined with the numerous examples of footprint casts he was familiar with, constituted far more compelling evidence for the existence of the sasquatch than could be mustered for any other prospective unknown hominoid from around the world. He felt a concerted effort to study the matter was certainly warranted.

The Skookum cast has evoked tremendous interest largely due to its novelty

—i.e., it's not just another set of footprints. However, it is likely to remain largely a moot point, because its significance is only readily apparent to the highly specialized trained observer. To most onlookers it more resembles a piece of modern art that one might see hanging on the wall of a doctor's waiting room. But for a few careful observers, such as Dr. Swindler, it was the singular piece of evidence that decidedly tipped the scale of his considered opinion.

CAUGHT ON CAMERA: PHOTOGRAPHICS AND FORENSIC MEASUREMENTS

It has been said that a picture speaks a thousand words. It stands to reason that a clear definitive photograph of a sasquatch would go a long way to resolve the question of their existence. In its absence, skeptics point instead to the lack of clear undisputed photography as "evidence" that sasquatch does not exist. Why are there so few unambiguous pictures purporting to show a sasquatch? Of the few claimants, are any credible and compelling? How might the genuine article be differentiated from a clever hoax?

In the age of abundant point-and-shoot cameras and minicamcorders in the hands of a growing number of outdoor recreationists, one might expect an occasional picture, or video recording of sasquatch to materialize. The abundance of quality wildlife documentaries regularly appearing on television has led to the common belief that any animal can be readily located, followed, and filmed in the wild by experienced naturalists and professional cameramen who set out to get the desired footage. I once attended a museum seminar about the conservation of small, less popularized carnivores of the Intermountain West, such as martens, fishers, bobcats, and wolverines. I was particularly keen to learn more about the notorious wolverine, because of its solitary and far-ranging behavior. This predator is largely unfamiliar and poorly understood. The last time I made mention of the wolverine, the only recognition I got from a young listener was a reference to the *X-Men* character. The wolverine is the largest of the weasel family, but more resembles a small bear. A full-grown male may be 4 feet long including tail, stand 17 inches at the shoulder, and weigh 60 pounds. The wolverine is a rare and remarkably elusive, solitary predator that has a very large home range of over 240 square miles. One individual that was radio-

collared with a GPS transmitter wandered nearly 550 miles over a six-week period. In one nineteen-day span it traversed a 250-mile stretch from Grand Teton National Park to a ridge just east of my hometown of Pocatello and back again. This individual, at least during his wandering phase, had an estimated home range of 23,000 square miles. The wolverine's preferred habitat range largely corresponds to areas of regional sasquatch reports. The seminar presentation was well illustrated, and I was curious about the protocols used to get such stunning photographs of such a secretive animal as the wolverine. The presenter's response was, "Do you remember that one particular slide with a distant tiny brown dot on a white field of snow? That was the only photo in this presentation of a wolverine taken in the wild. All the rest were simply staged in a pen on a game ranch."

Few people realize that a large portion of the sharp vivid nature photography that adorns calendars and enlivens television features has been staged under controlled conditions. Obtaining truly natural wildlife photographs is a challenging undertaking. With over two years experience in the field with wild chimpanzees, park ranger Owen Caddy related an occasion when a professional wildlife film crew attempted for two months to get film footage of the apes left skittish in the aftermath of a lingering civil war. These expert photographers failed to get any film of the chimps at all, in spite of their concerted efforts to do so.

As surprising as it may sound, no television wildlife production company or wildlife magazine has ever put a professional wildlife photographer in the field for more than a few days in an attempt to obtain photographs, film, or video footage of sasquatch. Production companies that do create programs dealing with sasquatch typically focus their attention on the researchers and theorists (not to mention the skeptics) rather than trying to get original footage. And even if they did make the attempt, the reported behavior of the sasquatch—solitary, nocturnal, furtive, and far-ranging—distinguish it as one of those animals that all wildlife photographers acknowledge as notoriously challenging to even locate and observe, let alone successfully photograph.

Oregon wildlife photographer Michael Durham has captured some of the most stunning images ever of wildlife in their natural setting. He laments the profusion of staged wildlife shots that flood the commercial markets. To his distinction, Durham has developed an innovative system, which he combines with his inherent knack for getting into his subject's head, so to speak, when setting up a location. It takes a great deal of work and he will frequently spend an entire day setting up a single camera trap. He notes that most people have no

idea how much work is involved, but that is what it takes to get the quality shot, even of familiar wildlife generally thought to be relatively common in the outdoors.

Others are perhaps less concerned with the aesthetic quality of the shot as they are of capturing an image of some elusive and secretive species of interest. Camera traps are the tool of choice for researcher Jim Sanderson, a research associate with Conservation International's Center for Applied Biodiversity Science. Cameras deployed by Sanderson and other field biologists around the world have documented such rare animals as Abbott's duiker, the Siamese crocodile, and the Andean mountain cat. He remains skeptical of accounts of elusive apes such as the orang pendek. After 250,000 camera trap photos spanning twelve years from one end of Sumatra to the other, not a single photo of orang pendek was taken. While Sanderson doesn't consider North America the primate capital of the present world, he was impressed by photos of footprints emerging from our study areas and what they implied and acknowledged: "A single convincing camera trap photo will blow the lid off it. Go for it."

The typical sighting of a sasquatch is described as quite fleeting, not to mention unexpected. On those infrequent occasions, there is generally only a moment to compose oneself sufficiently and direct the camera at the usually retreating subject. In spite of the odds, a few evocative video clips purporting to show a sasquatch do exist. Analysis of video presents its own set of technical challenges. The image quality of consumer-grade video cameras used by most amateur videographers does not hold up well under stop-action and enlargement. The image quality is susceptible to low-light conditions often encountered in forests, especially at night, and the resulting video usually contains a considerable amount of noise.

An example of a “hit” on a camera trap—this time a black bear (Courtesy of Brian Smith)



A left footprint from a track at the site of the Freeman video. Notice the long second and third toes. (Courtesy of Paul Freeman)



A human foot exhibiting a variant of Morton's foot

Paul Freeman, a former Forest Service watershed patrolman in southeastern Washington State, shot a video of a sasquatch in 1994. Even though this particular video was taken in broad daylight from a reasonable distance, it has been afforded very little serious consideration and remains controversial. The footage starts with Freeman shooting a line of fresh footprints that he was informed were found near a spring in the Blue Mountains. The footprints are clearly visible along a dusty trail adjacent to a pond fed by the spring. My interest in the video was initially piqued because of the appearance of these footprints, which measured about 14 inches in length and bore a striking resemblance to footprints I had witnessed myself in the region in 1996. The relative lengths of the toes displayed distinctive proportions. The digital formula was 2=3>1>>4>5, that is, the second and third toes were longer than the great toe, and the last two toes were considerably shorter. This may be considered a variant of what is called the Greek foot, or Morton's foot, in human populations, a condition in which the second toe is longer than the first. It occurs on average less than 10 percent of the time. Having the third toe also longer than the first is an even less frequent variant of the condition. When the first three toes are all of about the same length and the foot is rather broad and squarish, it is referred to as a Peasant foot. The distinction between variants of these respective foot types

may be subtle and less than clear-cut. Nevertheless, the fact that the footprints evident on the video exhibited the same distinctive and uncommon toe pattern as was also present in the very compelling and animate footprints I had examined in the same region just two years later, prompted me to take a more concerted look at the subject of this video.

Two examples of footprint casts that exhibit toe lengths that resemble the footprint associated with the Freeman video. On the left is a cast from the region made in 1994, and on the right is a cast made by the author in 1997.

At the sound of popping brush, the camera rises up from the footprints, and a dark hair-covered figure emerges from the tress and crosses into view. Freeman exclaims “Oh! There he is!” and the subject proceeds deliberately from right to left through the underbrush, passing behind a snag and in front of a small fir, turning its head to glance toward Freeman once before stopping within the partial cover of the brush. From its obscured vantage point it stands motionless and stares back momentarily as if to assess the situation. The camera frame lurches as Freeman attempts to reposition himself for a better perspective, and then again frames the subject as it continues to the left and into the tree line. At no point does the subject appear to be alarmed or threatened by Freeman’s presence, merely surprised perhaps that the spring was currently “occupied.”

Videographic specialist David Bittner, of Pixel Workshop, examined the footage looking for signs of a hoax. Bittner recounts, “The footage was provided to me on a VHS dub, which I understand was already at least one generation removed from the camera original tape. Unfortunately, the original tape was not available for me to analyze. VHS is a relatively low-resolution format, to say the

least, and suffers from a significant reduction in detail with each generation of dubbing. The footage was shot with a consumer grade analog camcorder, which was another limiting factor in the quality of the footage.



David Bittner, professional videographer, at work evaluating the Freeman video (Courtesy of Scott Suchman)

"We digitized the footage into our video compositing workstation and went to work trying to extract as much usable detail out of the footage as possible. We slowed the footage down, digitally zoomed in, and used a variety of filtering techniques in various combinations. A combination of enlargement, slow motion, and edge enhancement yielded the best results. What remains is, in my opinion, a reasonably compelling video. There is nothing about it technically that points to a hoax, certainly no evidence of editing or digital compositing. There's no sign of a 'zipper on the monkey suit' or anything else that blatantly indicates a hoax, and the gait and apparent mass of the creature fit in with the accepted descriptions of these creatures. Overall, the scene plays out like countless other encounter reports—someone stumbles across a sasquatch; the creature calmly walks away. Freeman's excitement and heightened emotional

state are clearly evident in his verbal reactions to what he is witnessing.

”Over the past few years I have viewed numerous photos and videotapes of alleged Bigfoot creatures. I have an interest in the subject, and I never turn down anyone who would like to get my opinion on a video or photo. Some are more interesting than others, of course, and the quality varies tremendously, but typically people tend to overestimate the usefulness of the footage or photos they have collected. A dark blurry image moving through the trees isn’t going to capture the interest of any mainstream scientists or legitimate Bigfoot researcher.”

Bill Laughery, a retired game warden, and Wes Sumerlin, an outfitter and guide, were familiar with the location of Freeman’s video encounter and measured the snag that the subject walked immediately behind. Based on the height of the snag at 11 feet, the subject stood between 7 and 8 feet in height. This agrees with Freeman’s statement that the small fir tree situated just behind the subject measured about 16 feet in height. Unfortunately, the Forest Service constructed a campground and other improvements at the spring site, obliterating critical landmarks that were visible in the video. This alteration of the site hindered any subsequent confirmation of scale on which estimates of the video subject’s height relied.

From left to right: Bill Laughery, Ron Brown, “Pee Wee” Sumerlin, and Wes Sumerlin

During editing of the video footage, producer Doug Hajicek came upon an

interesting detail that had apparently otherwise escaped notice, and had never been mentioned by Freeman. In the parting shot, as the subject is seen at some distance from behind retreating into the forest, it appears to bend forward slightly to scoop up something. What seem to be small legs are barely discernable, momentarily dangling before swinging in toward the subject (perhaps securing a hold?). Might this be an infant?

Lori and Owen Pate shot another fascinating piece of video, on Memorial Day in 1996, near Chopaka Lake in northern Washington. The video depicts a dark figure with sure-footed stride, apparent breasts, and possibly an infant on its back, running for cover across a mountainside clearing. One of a number of eyewitnesses present at the time, Tom Lines, viewed it closely, although briefly, through binoculars and noted its covering of hair, which hung long off the arms. He was quite confident it was not a human.

As the location of the Memorial Day video was relatively unaltered since the incident, an elaborate forensic reconstruction was undertaken. Five expert forensic scientists, including Doug Divine of Pacific Survey Supply, and Bill Taft, of Taft & Associates, recreated the incident with the assistance of Derek Prior, three-time ail-American sprinter from Washington State University. They set out to determine the size and speed of the figure, and whether a mere human could replicate its performance.

(Left) Owen and Lori Pate reenact their taping of the Memorial Day footage shot in 1996, near Chopaka Lake in northern Washington. (Right) Witness Tom Lines indicates the long hair he observed on the figure he watched through binoculars. (Courtesy of Doug Hajicek /Whitewolf Entertainment, Inc.)

This was perhaps the most high-tech analysis of any film purporting to depict a sasquatch. They effectively mapped the entire hillside recreating the path of the subject and precisely determining the distances it traversed.

After extensive data collection and analysis, the team concluded that the figure was a mere 5′ 3″ in height, which meant that it was not exceptionally

large, and could conceivably have been a human in a costume. But then, should sasquatch exist, they wouldn't spring into being as full grown adults, nor are all adults of the same dimensions. Also, the taller champion sprinter soundly outpaced the figure, although on the first attempt Prior took a potentially nasty spill on the uneven terrain. The team did confirm a curious observation that in the closing sequence the figure gained approximately eight inches in height before passing into the tree line.

Carl Anderson, a forensic measuring expert, directed the analysis conducted at the Memorial Day footage site. (Courtesy of Doug Hajicek/Whitewolf Entertainment, Inc.)

As the team was preoccupied with the scale and speed of the figure, less commentary was offered about the specifics of the anatomy and behavior that could be observed from the video image itself. The subject reportedly hesitated at the tree line for a considerable time and was seen occasionally peering from behind some cover. When it finally broke from cover and was captured on videotape, it made its descent down the hillside, apparently with something of a slightly lighter hue on its back. That something then appeared to slip lower on the figure's back and an appendage of sorts, flailed behind. At that point the running figure, with arms pumping, reached back with its right arm to clasp the

object to itself, without breaking stride. Also discernable were unmistakable breasts that gyrated with each running step. There are no indications of clothing, no bulging, bunching, or borders. There is nothing to contradict Lines's testimony that he saw a hair-covered figure through the binoculars. The figure passed behind an intervening rise in topography and when it emerged beyond, its right arm was poised upward, toward or above its head, as if steadying something. The arm dropped and the figure noticeably increased in height, before entering the timber. Could this be a female sasquatch, perhaps a young female, with a youngster on board? The smaller size and apparent breasts suggest this might be the case. Was the infant nearly dislodged from its piggyback position as its mother made a dash for cover behind the intervening high ground? Did it receive a boost into a position behind the female's neck and peer over the top of her head? This is a posture for infant transport that is typically practiced by apes, and humans for that matter. Infants ride atop the adult's back or shoulders and peer over the adult's head. This sometimes continues until the infant is quite large, if the adult is indulgent.

Infant apes frequently ride atop their mother's shoulders, which may account for the increase in height of the Memorial Day video subject.

Dr. Esteban Sarmiento's impression of the Memorial Day footage was that

the behavior of the subject was quite natural—running for cover. But the shortcomings of the medium and the distance from the subject come to the forefront again. “If I had to reach a conclusion, I would have to sit on the fence given the resolution. It’s very difficult to prove with certainty that the creature is real or a man in a monkey suit. The detail just isn’t there,” concluded Sarmiento.

By far the most intriguing and most discussed, albeit controversial, piece of photographic evidence is a 16mm film taken in northern California in 1967, by Yakima, Washington, rodeo rider Roger Patterson and horse rancher Bob Gimlin. Patterson had become interested in the subject after reading an article by zoologist Ivan Sanderson on the subject of “California’s abominable snowman.” He had made a trip to the region to see the enigmatic footprints for himself, and made a cast of a 17-inch track in 1964 on Bluff Creek above Notice Creek. In 1967, word of fresh footprints reached Patterson by way of Al Hodgson, a local proprietor in Willow Creek. Patterson was producing a documentary in hopes of financing a full-time search for the animal. He wished to get footage of clear footprints to include in the production. He enlisted the help of Bob Gimlin, who had accompanied him on earlier trips to Mt. St. Helens, Washington, and the two began patrolling the area surrounding Bluff Creek. For nearly two weeks they found no sign. Then on October 20 they rounded a bend in the creek, their approach and view obscured until the last moment by a large root wad. Suddenly the horses became spooked by a large hair-covered figure about sixty feet to their left, which turned and with a determined, but unhurried gait began to retreat upstream across a wide elevated sandbar. Roger grabbed the camera from his saddlebag, a maneuver he had actually practiced extensively in anticipation of just such an incident, and ran across the creek in pursuit. At the high sandbar he stumbled and dropped to his knees. The subject pivoted at the waist, swinging its arms widely, as it seemed to glare back at the intruders. Roger stayed down momentarily and steadied the camera. What he saw through the viewfinder, Gimlin saw even more clearly from atop his horse—an upright figure covered with short, dark hair that was slightly longer on its head. Its body was thick and heavily muscled.

(Left) Frame 352 of the Patterson-Gimlin film taken in October 1967 in northern California. (Right) Close-up of the film subject. (Courtesy of Martin and Erik Dahinden)

Said Bittner, "Consider this—the Patterson footage is by far the *gold standard* for Bigfoot footage. It was shot during the day, in full sunlight, out in the open on 16mm film. Independent researchers examined the location immediately after the encounter, and footprint casts and countless measurements and photos were taken. Hard to imagine better circumstances, and yet this film remains controversial, written off as an *obvious hoax* by many. So that's what you're up against. In order for a photo or video to make a significant impact, it needs to be at least as good as the Patterson film, if not better." Indeed, this film remains among the most compelling evidence for the existence of sasquatch, detractors and skeptics notwithstanding. Innovative modern techniques of image analysis have revealed new details lending further corroboration to the film.

THE WRANGLER AND THE WILDWOMAN: BOB GIMLIN'S ENCOUNTER WITH BIGFOOT

Bob Gimlin is a horse rancher and builder in Yakima, Washington. The first time he had heard of sasquatch was during a trip through British Columbia, Canada, when he and his wife saw a sign for "sasquatch country" depicting a hair-covered figure. His wife suggested that it must be some kind of Indian tribe, to which Gimlin responded, "They are not very good-looking Indians." He maintains that he was agnostic on the subject of sasquatch's existence, holding a noncommittal "show-me" attitude. A friend by the name of Roger Patterson, a fellow rodeo rider, became enthusiastic over the prospect of finding Bigfoot after reading an article written by Ivan Sanderson in 1959, about America's "abominable snowman" in the mountains of northern California. Several years later, Patterson learned from tribal elders on the Yakama Indian Reservation that these huge creatures once lived throughout the Northwest and some believed they still roamed the more remote mountainous areas. In 1964, Patterson made a business excursion to Los Angeles, and stopped in northern California along the way to see what was behind Sanderson's article. He made several acquaintances, including Al Hodgson, proprietor of the general store in Willow Creek, taped interviews and made some plaster casts of footprints himself, and showed these to Gimlin. Gimlin remarked, "I was not convinced that they really existed. You know, I figured Roger must have had a reason. He showed me plaster casts and I heard different stories from people who had seen them, so I thought well maybe there is something to this, but I just didn't believe in them basically. . . didn't believe it was possible they could exist."

However, Gimlin remained open-minded. Hearing the eyewitness accounts and examining the casts, he thought there must be *something* there that he didn't

understand. His interest was piqued and he accompanied Patterson to investigate reports in the Yakima region, and the two rode on horseback many times in the forests around Mt. St. Helens. Returning from one such trip they found a message waiting for them from Al Hodgson in Willow Creek, California. Hodgson had learned from John Green about fresh tracks found along the Blue Creek Mountain road discovered after the Labor Day weekend. He waited until Green and Rene Dahinden had examined the tracks and left the scene and then gave Patterson a call to let him know new tracks had recently been discovered. Patterson was hopeful of getting footage of fresh tracks to include in a documentary film he had been putting together over the previous eight months, featuring interviews of eyewitnesses and shots of the locations where they had reported seeing a sasquatch. His intent was to be able to finance a full-time search for sasquatch from the proceeds of the documentary. Gimlin was between construction jobs and so he agreed to go to California with Patterson once he was able to get his affairs in order at his ranch. They took two saddle horses and a packhorse, Gimlin's one-ton truck and horse van, and supplies to keep them for two weeks or more. In fact, it was Gimlin's equipment that made the trip possible. Patterson was out of work at the time and was receiving some financial backing from his brother-in-law, Al DeAtley.

By the time they arrived, rains had effectively eradicated whatever tracks remained on Blue Creek Mountain. Although traces remained, Bob admitted he could not make much out of them. They set up a base camp down across Bluff Creek and began patrolling the dirt roads. The routine was to wait until the heavy construction and logging rigs were off the roads and then ride them on horseback, looking for tracks or whatever might turn up, returning to camp at night. By night they would slowly drive the roads in the truck looking for tracks that might have been left across them. They also rode out singly in order to cover more ground, searching for sign along the creek beds and up the mountainsides throughout the region. This went on for a couple of weeks Gimlln recalled the morning of October 20, 1967. "The day we got the film footage, I left early in the morning and Roger slept in. I just rode out and around, I always got up early and so I rode on out. My horse loosened a shoe and I came back in to tack the shoe on tighter. About ten, midmorning or so, I sat around there for a little while, because Roger was gone when I got back. Supposedly he had gone down the creek there—ah, Bluff Creek there—and after awhile he came back and asked what area I had covered that morning. I told him and he says, why don't we ride up into this area we had ridden into before, a desolate type area down a couple of canyons, there's a creek running through it. So we went ahead and fixed lunch

and he said let's get our gear together so when we ride out we can stay if we have to and stay a little bit later into the night if we need to. We packed up the packhorse and it was about midday."

Stills from what has become known as the "cowboy footage" of Bob Gimlin leading the packhorse along Bluff Creek in northern California (Courtesy of Martin and Erik Dahinden)

They were riding upstream on the right-hand side of Bluff Creek. Roger was in the lead, followed a horse-length or two behind by Gimlin with the packhorse in tow. Several miles upstream, they skirted a large downfall tree with a large root wad that had diverted the flow of the creek. As they rounded the obstruction, there was a logjam—a "crow's nest"—left over from the flood of '64 that had scoured the narrow valley and piled up the logs. Suddenly there was the creature standing by the edge of the creek a mere 60-80 feet to their left. In Gimlin's words, "When I first saw it, it was standing, looking straight at us. That's when everything started happening. The horses started jumping around, raising the devil and spooking from this creature. Roger, well his horse was rearing up and jumping around."

Patterson's horse, younger and less experienced, tried to spin around and

come back. Gimlin's was a more seasoned roping horse but was still spooked by the encounter with the figure. Patterson was trying to control his horse with one hand while reaching back into the saddlebag for his camera with the other. He was quite agile and athletic, since he did rodeo riding and gymnastics. This was a maneuver he had practiced. "He always kept that saddlebag ready. The saddlebag had two straps on it to keep it buckled down. He kept one buckled and one of them unbuckled so he could get his camera in the event he needed it in a hurry and this was the case at that particular time . . . that was his theory that if he ever had to get it, he kept the one buckle on there so it would not bounce out while he was riding and the other one loose so he could get it out in a hurry," said Gimlin.

Patterson slid off the horse with his camera in hand and the horse ran off, prompting the packhorse to jerk free from Gimlin and follow. Patterson called out "Cover me!" as he ran across the creek toward the sandbar, which had a slight elevation of about 30 inches, the camera to his eye. With his vision restricted by the viewfinder, he ran into the sandbar and fell to his knees. Gimlin could see this within his field of vision, while keeping his eye on the creature, which had immediately turned and begun retreating up the sandbar and parallel to the creek bed. Gimlin rode across the creek, dismounted, and pulled his 30.06 rifle from its scabbard. He figured if it became necessary, he could get off a surer shot on foot than in the saddle on a jittery horse. He recalled that at the time he was young, was still hunting and was an excellent shot. They always carried rifles when they rode in the mountains, but not with the intent to shoot a sasquatch. "We had talked about it, but decided unless it was necessary, we would never shoot. In other words, unless it was violent or attempted to attack us . . . I just stood there with my rifle. I never raised the rifle like I would shoot or anything like that, just held it in my hand and with the other hand held my horse to keep him from getting away from me."

Early frames from the Patterson-Gimlin film clip, when the subject was about sixty to eighty feet distant (Courtesy of Martin and Erik Dahinden)

The creature reacted twice to their approach, glancing back once when Gimlin crossed the creek on horseback. At that moment Gimlin was at his closest to the creature, perhaps less than sixty feet. The second glance, which has become the most publicized frame from the film (frame 352), occurred either when Patterson repositioned himself to a better vantage point and/or when Gimlin dismounted behind him. It was all happening so fast; he was uncertain precisely where the creature's attention was focused.

Fatigued from weeks of hard riding and searching the countryside day and night, the gravity of the moment did not immediately weigh upon Gimlin. Then the reality of what they were witnessing suddenly struck him. "When I saw this thing—it's almost unexplainable how I felt—I thought, is this really true? Is this really happening? Here I am, I've been here, I'm tired, but this thing is real. It's real. It's humanlike. It's walking upright and it doesn't seem to be walking fast, but it's covering the ground quickly.

"Its walk was extremely graceful, especially for a huge creature like that. I did notice that it brought its knees up fairly high, but I took into consideration that it was a pretty heavy animal—or pretty heavy creature. I'm not going to call it an animal because I don't believe it is."

Gimlin described his initial impressions of the creature's size and weight—"I

thought it was about six and a half feet tall and I would have guessed its weight at 250 to 300 pounds. It did have tremendous muscle bulk. It was massive. This was an estimated guess at the time of course. I'm not used to seeing things like that. I was just guessing weight compared to the amount of muscle quarter horses have. It wasn't as big as a quarter horse naturally. And the height, because we were up on our horses at the time we first saw the creature, it probably didn't look as tall as it really was. Now the horse I was riding was a sixteen-hand horse. One hand is four inches on a horse. My horse was sixteen hands tall plus my saddle. That would make him approximately sixteen and a half hands high. Now of course, with me sitting up there, you can figure my eye level was about nine feet high. So anything actually less than nine feet you would be looking down at it."

These were Gimlin's initial impressions, but after examining the footprints deeply impressed in the firm sand compared with the shallow hoof prints left by the horses, he reconsidered. "We knew it had to be heavier than it appeared to be when we first saw it. The horse that I was riding was around 1,200 to 1,300 pounds. I rode him alongside the tracks. With new film in the camera, Roger took pictures of how deep the horse's prints were in the soil compared to the creature's tracks. Of course, we thought the horse's weight was distributed on four feet and I'm not good with the mathematics of such things, but if you figure a 1,400-pound horse distributed on four feet would be about 350 to 400 pounds, we figured it must have weighed much more than we originally figured. Then I got up on a stump, which was approximately three to four feet. We didn't measure it, probably should have. Anyway I jumped off with a high heel boot as close to the track as we could. Then we took pictures of that to illustrate the depth that my footprint went into the same dirt with a high heel cowboy boot and at that time I weighed 165 pounds . . . Course Roger did some research by going over to the zoo in Seattle; watched the gorillas there and asked how much they weighed and so forth. They had one over there named Bobo and I don't remember his weight exactly, but I do remember he weighed more than it looked like he weighed . . . In the end it probably weighed approximately 500 pounds to make tracks that deep in the dirt.

Gimlin reported that the subject looked back when Gimlin rode across the creek, drew his rifle from its scabbard, and dismounted. (Courtesy of Martin and Erik Dahinden)

”It wasn’t looking directly at me, but I could see the face real good and I could see the eyes,” Gimlin recalled, describing their initial encounter with the creature. As for the details of its face—”The face would have a flat type nose; the lips, I can’t really remember what the lips looked like except it did have lips and we could see its teeth. The eyes were large eyes but not big round eyes like a horse or a cow but there were large eyes. The hair on its face was short. There wasn’t a whole lot of hair around its cheeks and down alongside the face. The best I can remember is the face didn’t have a whole lot of hair on it.”

The creature walked away with an easy motion, swinging its arms like a human. Gimlin, familiar with livestock was especially impressed by the evident and dynamic musculature. “Yes, I could see the muscles clearly and that was one of the deciding factors in my opinion that this was no ‘man in a suit.’ The thighs, the buttocks, the arms and shoulders, you could see it move clearly underneath the hair.”

Regarding the creature’s gender he continued, “Well, it appeared to be a female, but You know l had never seen one. I had never even seen a track until that day so I couldn’t even make a statement whether it was male or female. But the film indicates that it had mammary glands, so we assumed it was a female.”

Since the tracks found earlier on Blue Creek Mountain were of three

different sizes, Patterson and Gimlin had assumed there were a male, a female, and a younger one in the area (in retrospect the three were probably a female and two offspring, perhaps even the female they encountered). The prospect of possibly two more enormous creatures being in the vicinity, perhaps an even larger male, was a bit disconcerting. Gimlin was careful to ensure his horse didn't bolt from the scene. He continued, "It was moving away from me. That was about all that was in my mind at that time. That this creature was of no threat to us and oh yeah, I was trying to keep my horse under control cause you know I never had any idea what might happen and I sure didn't want to be on foot! So I knew I could get back on my horse if I had to. If I had to shoot it and it didn't go down, I could get on my horse and I could get out of there . . . and Roger would have to fend for himself. I'm not a coward, but I'll be darned if I was going to stick around if this creature got violent, you know? So I was concentrating on keeping my rifle in my hand and my horse under control."

Roger Patterson pouring a cast at the film site and displaying the cast upon their return to Yakima, Washington (Courtesy of Martin and Erik Dahinden)

The creature continued its course of retreat upstream disappearing around a knoll that dropped down from the canyon wall, but Patterson, still on foot and without his rifle was nonetheless uneasy about the situation. Said Gimlin, "Then

when the creature did disappear up a little draw, why I wanted to follow it. Of course Roger didn't want to follow it because he was on foot and he didn't want to be left there. We thought there was the possibility there were the two others around . . . we didn't know at the time whether that was one of the ones that had made the tracks up above the scene or not. Roger was a little bit upset about that so he wanted to catch his horse and get some more film in the camera. It took quite a while to catch the horse and to catch the packhorse as well and tie them up. Then we rode on in pursuit of the creature."

The 14.5-inch right and left footprints left in firm, moist sand, cast by Roger Patterson on the Bluff Creek film site in October 1967

Patterson quickly changed out the film under a poncho. Gimlin optimistically thought they might catch another glimpse of the creature. They followed its tracks for about a quarter mile. Beyond the sandbar they became little more than scuffs in the gravel. The stride increased to 68-72 inches, suggesting it had possibly broken into a run when it was out of sight. "Then we tracked on up the creek bed quite a ways. We saw one wet half of a footprint on a rock where it crossed the creek and it went up into the mountains and that was as far as we went with it." Gimlin was ready to continue the pursuit, even if they would have to proceed on foot up the steep mountainside. Patterson thought not. The days were short that time of year and the prospect of being out on foot in the dark dissuaded them from going farther. "He wanted to get back and take plaster casts of the tracks and then go on into town to see if we had anything on film. We

weren't sure from Roger stumbling and falling down on the sandbar and getting up and running. We didn't even have an idea that we had anything on film at that time. In fact, it was doubtful that we did have anything." That was the object in getting the film back to DeAtley as quickly as possible for development and then getting back to the site with more film and calling in the tracking dogs to pick u the trail where it went up the mountain, to see if more footage could be obtained. Gimlin recalled Patterson lamenting, "I don't know, Bob . . . I'm not sure that I got any film footage at all—I fell down, got relocated, then got relocated again, and then I ran out of film!"

Still image of a footprint on the Bluff Creek sandbar from the second roll offilm(Courtesy of Martin and Erik Dahinden)

They returned to the truck back at camp and retrieved some plaster. They poured casts of two clear footprints—a right and a left. Casting and filming the tracks occupied what remained of the afternoon. It was nearly dark by the time they arrived at camp and got the horses tied and fed. They got in the truck and drove through Weitchpec and over the Bald Hills road to the coast at Orick, then down to Eureka where Roger shipped the film to DeAtley for developing.

They returned through Willow Creek and stopped to see Al Hodgson, proprietor of the local general store, who held a personal interest in the topic, phoning him after hours from in front of the store. Hodgson said he took the call and heard Patterson say, "I got a picture of the son-of-a-buck!" Hodgson had

taken Patterson as always a calm speaking sort of man, but on this evening Patterson was quite excited. Hodgson observed, "Honestly, he was three feet off the ground. He was very, very excited. Afterward I turned to my wife, Frances, and asked her what she thought. She said either he saw it or he's on LSD." Hodgson called Syl McCoy from the Forest Service and they talked for several hours. Afterward Hodgson recalled, "I'm not an expert in interrogation, but as far as we could tell, he [Patterson] was telling the truth." Patterson and Gimlin went to buy some groceries and before leaving, Patterson asked Hodgson to contact Green and Dahinden, two Canadian investigators from British Columbia, about arranging for tracking dogs.

They arrived back in camp late that night and sat up for several more hours discussing what they had seen, especially what Gimlin had noticed, as he had the better view, while Patterson was looking with one eye through the camera's viewfinder. Sleep that night was brief, interrupted when Gimlin awoke to the pitter-patter of rain, which quickly increased in intensity. "Around 5:30 A.M. or so it started raining, and it was just a pouring-down rain. I told Roger we better get up and do something about the tracks or they'd wash **out**, and he said no, it would stop raining after a while. I went ahead and got up, put the saddle on my horse, and decided I would ride up there while it was raining really hard. I had gotten a couple of cardboard boxes from Mr. Hodgson's to cover these tracks the night before. So when I went outside to get a couple of these boxes that were folded up out there, they were just soggy old pieces of cardboard. I disregarded taking those back up there. So I rode back up to the scene, pulled some bark off some dead trees, and covered up the tracks as best I could, the best ones that I could identify. In the rain like that it had already done some damage to them. Then I went back to camp. By then we decided it wasn't going to quit raining. The little creek that was six or seven feet across was now ten or twelve feet across and four feet deep! We were on the side of the creek, which had to be crossed with the truck to get out to the main road. I said, 'Well I'm going to go ahead and cross the creek with the truck and get started out.' And of course Roger thought it would stop raining and he suggested I leave him there and come back and pick him up." Gimlin's truck was a two-wheel-drive one-ton and he felt they needed to get moving. The rain virtually eliminated any prospects of using the tracking dogs, even if they could get to the site and pick up the trail into the mountains. Now Gimlin's concern was getting his rig out of the mountains. The rain didn't let up and the low road was blocked by a flowing mudslide several feet deep. Trees were sliding down off Onion Mountain. They nearly backed their vehicle into the creek trying to turn around. The windshield

wipers couldn't keep ahead of the torrent and visibility was poor. It took nearly all day to get back to the main highway. They drove all night to get back to Yakima.

Eventually, Gimlin relived the experience by viewing the developed film footage. Of this he said, "I was kinda disappointed with the original film, because I thought it should have gotten a lot more than that, but with Roger running part of the time and trying to relocate part of the time and these things happened so rapidly—it was just happening in heartbeats . . . I was relieved to see that he got that much. At least there was something there; that you could see the movement and you could see the muscles." Gimlin added a remark that also sheds light on the question of the film frame speed controversy that arose later. Patterson, who usually kept the frame speed set at 24 frames per second (fps), discovered the snap dial positioned at a slower setting, 16 fps. This had fundamentally significant implications for the estimation of the height of the subject and the characterization of its walk, but Patterson confessed that he simply had no idea when the dial had been reset. Quite pertinent to this matter is Gimlin's observation, "What didn't please me was that I'd see other people run the film footage [on TV] maybe at different speeds or what [typically 24 fps], but it didn't look the same, it didn't even walk the same. I was terribly disappointed with that."

Some twenty-five years later, Gimlin reflected, "My impression is that there is a creature, and I don't feel it was a man in a suit. If it had been a man in a suit, I don't know how they would have gotten him back into that particular area. I have heard this story and thought about it many times. God! At one point with the film circulating all around and people criticizing, I was almost to the point of not being even sure myself. But I thought about it all these years and I'm quite sure it wasn't a man in a suit. I saw the face. I saw the expression on its face. With all the muscles in the arms and legs, I don't know how it could be a man in a suit! Plus I never had anything to do with a man in a suit and *if* Roger did, how would he know I wouldn't shoot it? In my opinion, that creature was not a man in a suit." Although the two had previously agreed not to shoot a Bigfoot unless their lives were at risk, who's to say precisely what circumstances might constitute a risk in any one person's estimation placed in such an unpredictable situation. Gimlin couldn't imagine Patterson putting him in that position.

At the Willow Creek Bigfoot Symposium, held in 2003, Gimlin was asked if he ever regrets his involvement in the incident. He replied that he had no regrets then and he had none now after meeting so many nice people at the conference. There had been times, however, when he did wish he had never been involved.

He could handle the criticism, but his wife had also endured a lot of ridicule. At times it was a strain on their relationship. In his words, she is not as thick-skinned as he, and so was more sensitive about the ridicule and harassment they experienced. In spite of the incredulous reaction to the film by many, Bob Gimlin reiterates that there is no doubt at all in his mind that he had seen a real animal. Once again he calmly and confidently reiterated, “They are real; I saw one.”

On the occasion of the Willow Creek Conference held in 2003, Bob Gimlin returned to the film site for the first time. Pictured from left to right are: author, Bob Gimlin, John Bindernagel, Daniel Perez, John Green, and Dmitri Bayanov. (Courtesy of Daniel Perez)

How good is the Patterson-Gimlin film? If authentic, this is one of the most startling natural history films in existence. It has received the most extensive forensic analysis by anthropologists, zoologists, and film experts of any of the purported films or videos of sasquatch. What do the analyses of the experts say about the dimensions, anatomy, and gait of the creature captured in this footage?

PICTURE THIS: SCIENTIFIC REACTION TO THE PATTERSON-GIMLIN FILM

Patterson was eager to rush off to show the film to experts in Los Angeles and New York; however, Green and others argued that he would lose credibility away from his own setting. At length he was persuaded to first show the film at the University of British Columbia, Canada, where a few of the resident authorities had already been exposed to some of the evidence of sasquatch. As might be expected, reactions by the scientists were at best guarded and essentially noncommittal.

Dr. Ian McTaggert-Cowan, a leading zoologist, summarized the ingrained bias directed at the question of sasquatch, saying, "The more a thing deviates from the known, the better the proof of its existence must be." This declaration has often been rehearsed by those who are prompt to dismiss *any* evidence of sasquatch. Justified or not, this approach seems to apply a double standard to evidence of sasquatch. It would seem that an equally rigorous standard of evaluation should be applied to all evidence laid out for scientific consideration, regardless of preconceptions, since history has attested that perceptions based on yesterday's understanding are often of necessity revised in the light of today's revelations.

Don Abbott, curator of anthropology at the Royal British Columbia Museum, who had just weeks before examined firsthand the extensive trackways of three individual sasquatch in the region of Bluff Creek represented the feeling of a number of scientists who were duly impressed by the film but found it a challenge to abandon their preconceptions. He said, "It is about as hard to believe that the film is faked as it is to admit that such a creature really lives. If there's a chance to follow up scientifically, my curiosity is built to the point

where I'd want to go along with it. Like most scientists however, I am not ready to put my reputation on the line until something concrete shows up)—something like bones or a skull."



Don Abbott examining footprints on the Blue Creek Mountain Road in northern California (Courtesy of John Green)

Dr. G.C. Carl, the provincial museum director, was sufficiently impressed to make a promise to scientifically investigate any fresh tracks that turned up in British Columbia.

Dr. WJ. Houck, of Humboldt State College in Arcata, California, attended the viewing in B.C. as a complete skeptic, but left undecided. "I'm not going to call it a hoax," he told the Province newspaper, "yet the alternative is still too fantastic to accept. Where does that leave me? Darned if I know."

After a day or two of notoriety in the regional press it became apparent that nothing further could be accomplished locally. Inertia had prevailed. However, *Life* magazine expressed interest in the story and therefore arranged for another showing to scientists, this time at the American Museum of Natural History in New York City. In attendance were Dr. Richard Van Gelder, head of the Department of Mammalogy and Dr. Harry Shapiro, from the Department of Anthropology, along with members of the press. During a brief showing of the film, Patterson and DeAtley were left waiting outside the conference room. The

expert consensus was, “It is not kosher because it is impossible.” In other words, it was considered impossible that a giant primate could exist in North America yet unknown to science; therefore, the only explanation for the film was that it was a hoax. As a result of this negative assessment *Life* washed its hands of the matter and suddenly dropped out of negotiations.

Argosy magazine promptly took on the story and arranged a second U.S. showing, this time at the Smithsonian, in Washington, D.C., which was attended by Dr. John Napier, who was director of the Primate Biology Program at the time, Dr. Joseph Wraight, Chief Geographer, U.S. Coast Guard and Geodetic Survey (a human ecologist), Dr. Vladimir Markotic, associate professor of archeology at the University of Calgary (a physical anthropologist), and Dr. Alan Bryan, professor of anthropology at the University of Alberta. Sanderson wrote the article for *Argosy* and quoted favorable comments by Napier and Wraight. Markotic and Bryan were not quoted, but Markotic considered the film genuine and was involved in further investigations until his death.

It was not only a men’s magazine that publicized the story. The *National Wildlife* magazine, the outlet for the National Wildlife Federation, promptly picked up the story as well. An article penned by executive editor and experienced outdoorsman Dick Kirkpatrick, presented a balanced matter-of-fact treatment of the story to wildlife enthusiasts and conservationists. He concluded with his reflections on just what the film depicted. “I don’t know. After several weeks of research and interviews, I’m as confused as I was in the beginning,” he said. “It could be a big, hairy anthropoid creature, rare enough and shy enough that it simply hasn’t been captured yet. Where there is that much smoke, there just may be some real fire.” Shortly thereafter, the January 1969 issue *of Reader’s Digest* carried a story by James B. Shuman, “Is There an American Abominable Snowman?”, condensed from *West* magazine, a publication of the *Los Angeles Times*, which reached an even wider readership.

Some years later, Dr. Richard Thorington, Jr., who succeeded Napier as director of the Primate Biology Program at the Smithsonian, commented on *his* rather contrasting assessment of the reaction to that historic viewing of the PattersonGimlin film: “. . . To them it appeared all too obvious that the pictures were made of a person dressed up in an ape costume, trying to run in an unnatural way. The one person who did not at the time consider this to be the case was Dr. John Napier . . . let me point out that there are two ways to look at the ‘Bigfoot phenomenon.’ One is the approach that Dr. Napier espoused that we should keep an open mind and review all evidence to decide whether this is a hoax or a legitimate area of study. “Dr. Napier is thus incorrectly singled out as

the only expert at the viewing who lent any credence to the film, let alone a willingness to give the evidence a reasonable hearing. Thorington went on to suggest that the only tenable position—one that he felt "forced to espouse"—is ". . . that one should demand a clear demonstration that there is such a thing as Bigfoot *before* spending any time on the subject. There are many, many valid areas of research for which the subject matter is known to exist, so one should busy oneself with these rather than with will-o'-the-wisps." If such an attitude prevailed without exception throughout science, it would be a wonder that any breakthrough discoveries were ever realized.

Dr. William Montagna, former director of the Oregon Regional Primate Research Center, was among those viewing the film and reflected on his experience in *Primate News*, September 1976: "Along with some colleagues, I had the dubious distinction of being among the first to view this few-second-long bit of foolishness. As I sat watching the hazy outlines of a big, black, hairy man-ape taking long, deliberate human strides, I blushed for those scientists who spent unconscionable amounts of time analyzing the dynamics, and angulation of the gait and the shape of the animal, only to conclude (cautiously, mind you) that they could not decide what it was. For weal or woe, I am neither modest about my scientific adroitness nor cautious about my convictions. Stated simply, Patterson and friends perpetrated a hoax. As the gait, erect body and swing of the arms attest, their Sasquatch was a large man in a poorly made monkey suit. Even a schoolchild would not be taken in. The crowning irony was Patterson's touch of glamour: making his monster into a female with large pendulous breasts. If Patterson had done his homework, he would have known that regardless of how hirsute an animal is its mammary glands are always covered with such short hairs as to appear naked.

"To believers who claim that we scientists are too opinionated to look at the evidence, I reply: Is a scientist to listen to every zealot who regales him with tales of a putrid stench, who shows him fake footprints, or makes films of a man wearing a badly tailored monkey suit? The scientist who is reviled because he won't listen to fantasy goes securely on his way, knowing that life is so full of real wonderment and mystery that he does not have to fantasize. But perhaps I ought to add that man's need to fantasize is a vestigial remnant of his past. It created mythological characters, good and evil; visions and miraculous events, heaven, purgatory and hell. It created the oracles, the art of palmistry, phrenology, astrology, and all sorts of other occult sciences. And finally it peopled man's world with monsters."

The smug confidence in Montagna's assessment of the situation, even some

years later, lends little to his credit. His often-repeated statement about the contradiction of hair-covered breasts is one that has always puzzled me. First, the degree of hairiness of the breasts of the film subject is open to interpretation because the exposed areas of skin are nearly the same color as the hair, excepting the appearance of the soles of the feet, and the palms of the hands, a matter addressed a bit later on. The resolution of the film makes it difficult to be certain how densely covered with hair are the presumed breasts. On the other hand, anyone has but to peruse the many published photographs of apes to discover that the ape's chest *is* covered in hair, no matter how fine. In a study by Wettstein, a sample taken from the middle of the chest of a series of apes yielded the following average hair densities per square centimeter: Gibbon 600, Orangutan 100, Chimpanzee 70, Gorilla 5, and *Homo* 1. Human female breasts are indeed covered with hair follicles and associated erector pilli muscles that cause goose bumps, although the hair is extremely short and fine. This hair is sensitive to masculinizing androgens, circulating sex hormones that cause the hair to become heavier and darker in typical areas, including the chest. With this in mind, and given the evident variation among the closely related hominoids, where is Montagna's justification in drawing such a dogmatic conclusion about the appropriateness or otherwise of the apparent hairiness of sasquatch breasts?

One of the first persons to take the initiative to investigate the alleged film site and the apparent circumstances of the encounter was Bob Titmus. In a letter to John Green, Titmus explained his reaction and his impressions of the incident:

> By the end of the day it had become apparent that a few of the viewers felt there was the possibility the whole thing was a very elaborate and expensive hoax. I felt that this possibility was so extremely remote as to be almost nonexistent. (None of these individuals witnessed more than one showing, I believe.) However, I did have to take into consideration the fact that I believe that I viewed the film through somewhat different eyes than most of the persons present.
>
> First, I think that a taxidermist will see and retain far more detail, while watching an animal, and is probably far more qualified to recognize anything unnatural, than the average person.
>
> Secondly, evidence that I witnessed in the mountains of Northern California about ten years ago changed me from a nonbeliever to a believer and since that time I have spent a major portion of those years, as you know, interviewing witnesses, investigating reports, collecting evidence, casting many, many different tracks, setting up camera and live traps, tracking the creatures dozens of times, etc., all of this was in an effort to capture one of

creatures dozens of times, etc., all of this was in an effort to capture one of the creatures. All of this only strengthened the case of the existence of the creature Bigfoot/Sasquatch.

Thirdly, many years ago I saw one of these creatures at fairly close range and watched it for about ninety seconds before it walked off into the timber.

Since I know more about tracks than film and generally feel that they will tell me a more accurate story than film, I had a very strong urge to see the tracks that were being made during the time that Roger was shooting his film. I felt that the tracks could very well prove or disprove the authenticity of the pictures. No one else present seemed inclined or able so the following day I went on to California to have a look at the tracks.

My first full day up near the end of Bluff Creek, I missed the tracks completely. I walked some fourteen to sixteen miles on Bluff Creek and the many feeder creeks coming into it and found nothing of any particular interest other than the fact that Roger and Bob's horse tracks were everywhere I went. I found the place where the picture had been taken and the tracks of Bigfoot the following morning. The tracks traversed a little more than three hundred feet of a rather high sand, silt, and gravel bar, which had a light scattering of trees growing on it, no underbrush whatsoever, but a considerable amount of drift debris here and there. The tracks then crossed Bluff Creek and an old logging road and continued up a steep mountainside.

This is heavily timbered with some underbrush and a deep carpet of ferns. About eighty or ninety feet above the creek and logging road there was very plain evidence where Bigfoot had sat down for some time among the ferns. He was apparently watching the two men below and across the creek from him. The distance would have been approximately 125-150 yards. His position was shadowed and well screened from observation from below. His tracks continued on up the mountain, but I did not follow them far. I also spent little time in trying to backtrack Bigfoot from where his tracks appeared on the sandbar since it was soon obvious that he did not come up the creek but most probably came down the mountain, up the hard road a ways and then crossed the creek onto the sandbar. It was not difficult to find the exact spot where Roger was standing when he was taking his pictures and he was in an excellent position.

I spent hours that day examining the tracks, which, for the most part, were still in very good condition considering that they were nine or ten days old. Roger and Bob had covered a few of them with slabs of bark etc., and these were in excellent condition. The tracks appeared perfectly natural and

normal. The same as the many others that we have tracked and become so familiar with over the years, but of a slightly different size. Most of the tracks showed a great deal of foot movement, some showed a little, and a few indicated almost no movement whatever. I took plaster casts of ten consecutive imprints and the casts show a vast difference in each imprint, such as toe placement, toe gripping force, pressure ridges and breaks, weight shifts, weight distribution, depth, *etc.* Nothing whatever here indicated that these tracks could have been faked in some manner. In fact, all of the evidence pointed in the opposite direction.



Bob Titmus seated in front of his cast collection, including ten successive footprint casts made at the PattersonGimlin film site, which are now held at the Willow Creek-China Flats Museum (Courtesy of John Green)

And no amount of thinking and imaging on my part could conceive of a method by which these tracks could have been made fictitiously.

His sister Allene and brother-in-law Harry Halbritter joined Titmus at the site. “Harry has hunted big game all of his life. He has been all over Africa, Alaska, Yukon Territory, Canada, Mexico, and the United States and stated that this impressed him more than anything he had ever seen in the bush in all of his travels. Harry made several tests and observations, one of which was to walk

briskly beside the tracks to try to match their depth of up to an inch and a quarter in places. Harry is a two hundred-pounder and the best he could do was an imprint of about a quarter of an inch on the rear portion of his shoe heel, and one eighth of an inch and less on the rest of his shoe imprint. We both agreed considering the depth of the two imprints and the difference in the amount of the bearing surface that the creature that made these tracks would have to weigh at least six hundred to seven hundred pounds."

The next summer John Green visited the site and conducted a simple and straightforward size comparison of the PattersonGimlin film subject. The remains of the trackway were still evident as a series of rough depressions stretching across the sandbar. Equipped with slides from the movie he was able to relocate Patterson's and the film subject's approximate positions, by lining up objects through the viewfinder of a similar camera. Although inexact, this method could at least offer an indication of the estimated size of the subject. Green filmed 6′ 5-5″ Jim McClarin, a student at nearby Humboldt State University, as he retraced the path followed by the alleged sasquatch.



John Green filmed 6′ 5.5″ Jim McClarin retracing the path walked by the film subject. Precise superimposition of the frames yields this revealing split-screen image. (Courtesy of John Green and Martin and Erik Dahinden)

The footprints were still evident as vague depressions, the trackway punctuated at points where the effects of time had erased them altogether. McClarin had been on the scene with Richard Henry shortly after the original events on November 5, 1967, when the trackway was still very clear and he had become quite familiar with the specific course taken by the subject across the sandbar. In an interview with Daniel Perez, an amateur investigator (and author of the definitive publication about the provenience of the film), Henry noted an interesting detail of the dynamic nature of the tracks. He described the high bank

on the far side of the creek, marking the edge of the elevated sandbar traversed by the film subject. The bank was 28-30 inches high. The film subject took the bank in one step, cresting the bank with only the ball of the foot and the toes, which slid down digging into the edge of the bar. Both were impresssed with the natural appearance of the trackway.

When the corresponding frames of Green's film of McClarin were placed over the PattersonGimlin film, the alignment of features in the foreground and background was quite correct, as well as the resulting superimposition of the steps of the two individuals filmed. If there was any apparent discrepancy, it was that John held the camera slightly lower on occasion. In those instances, the camera angle would make McClarin look slightly taller in relation to the subject. But at the distances involved, this discrepancy would be negligible. From this demonstration it was evident that the creature stood taller than the 6′ 5.5″ McClarin. Even more distinctly evidenced in the comparison was the subject's massive build, which dwarfed McClarin, who at the time weighed 180 pounds. The breadth and depth of its torso, shoulders, and arm span were considerably greater than McClarin's.

In 1969 John Green met with Ken Peterson, a senior executive at Disney Studios, who told him that their technicians had examined and studied the film. They concluded that in order to create something like it they would have to resort to animation. None of their animitronics was sophisticated enough to move freely. According to them, if it was hoaxed, it had to be a man in a suit. One of the top men in the costume field at that time was Janos Prohaska, a Hungarian-born stuntman and costume designer in Hollywood since 1939. Prohaska's ape characters made costumed appearances during the late 1960s in such television series as *Gilligan's Island, Perry Mason, Land of the Giants, Here's Lucy*, and *Red Skelton*, to name a few. One of his most memorable appearances was as the white unicorned gorillalike *mugato* that bit Captain Kirk on the *Star Trek* episode, "A Private Little War" (1968). After studying the film, Prohaska was convinced that it depicted a living creature rather than a man in a suit. He noted, "You could see all the muscles on the body . . . It didn't move like a costume at all." He felt that instead of a suit it would have to have been a minimum ten-hour makeup job in which the hair was glued directly to the actor's skin. He concluded, "It looked to me very *very* real. If that was a costume that was *the* best I have ever seen." Isn't it curious that such a hypothetically skilled costume designer had never been employed in the Hollywood film industry then or since?

No American or Canadian scientists were inclined to undertake a systematic

analysis of the film, so Rene Dahinden, a long-time investigator, took the film across the Atlantic to have it studied. He succeeded in recruiting the expertise of Dr. Don Grieve, a professor of biomechanics at London's Royal Free Hospital of Medicine, and Dr. Dmitri Donskoy, chief of the chair of biomechanics at the USSR Central Institute of Physical Culture in Moscow. The complete reports of each of these analysts have been published elsewhere, but they deserve further comments here. A number of Grieve's metrics must be qualified due to a handicap. He was not provided with the length of the footprints or the measured step. These he derived from the film itself and came to the conclusion that the foot was 13.3 inches long, instead of nearly 15 inches. In spite of this he summed up his overall impressions by saying, "My subjective impressions have oscillated between total acceptance of the sasquatch on the grounds that it would be difficult to fake, to one of irrational rejection based on the emotional response to the possibility that the sasquatch actually exists. This seems worth stating because others have reacted similarly to the film."

The ultimate conclusions of Grieve's analysis hinged upon the frame speed. He observed that if it was shot at 24 frames per second (fps) the quantitative details of the gait were reasonably similar to a human. However, if the film were shot at 16 or 18 fps the possibility of a human mimicking the distinctions of gait were virtually eliminated. Grieve said, "The possibility of fakery is ruled out if the speed of the film was 16 or 18 fps. In these conditions a normal human being could not duplicate the observed pattern, which would suggest that the sasquatch must possess a very different locomotor system to that of man."

Patterson stated that he normally set the camera at 24 fps, but that after the film had been taken he found the camera set at 18 fps. He could not say when the setting might have been altered. Up to his death he maintained that he simply did not know what frame speed the camera had been set at during the filming. The camera's lowest settings are only marked at 16 and 24 fps. There actually is no marked setting for 18 fps, and it was assumed that Patterson simply misspoke or was unfamiliar with the rented camera's settings when he stated that he found the dial set to 18 fps. The confusion led to analyses being conducted at all three frame speeds. Dr. Grover Krantz's analysis indicated that 18 fps was the probable speed although the camera dial is a snap dial, precluding intermediate settings between 16 and 24 fps. However, the instructions for this camera model (Cine-Kodak K-100 16 mm, hand wound) note that the actual speed of individual cameras will vary within 10 percent of the indicated speed setting. Krantz related that a BBC cameraman obtained an example of the camera model Patterson used and timed the frame rate electronically when set at 16 fps and

discovered that it was actually filming at 19 fps, nearly a 19 percent deviation. Therefore the potential accuracy of Krantz's conclusion of 18 fps, and its implications, are quite justified.



Calculations by Don Grieve indicate it was very unlikely that the gait pattern of the film subject was executed by a human. (Courtesy of Don Grieve)

Several lines of evidence conclusively point to the slower frame speed. First, and perhaps most fundamentally, the degree of motion blurring evident in the film footage points to a slower frame speed. At 24 fps motion blur would be all but eliminated. Second, one of the Russian observers, Igor Bourtsev, noted that the vertical vacillations of the film frame most likely corresponded to the running or walking of the cameraman, presumably Patterson. Bourtsev observed intervals of 4 and 7 frames. He also noted that world-class sprinters manage 5 steps per second. If the film speed were 24 fps, then Patterson would have to had managed 6 steps per second to produce the vertical oscillations at 4-frame intervals, which is simply impossible. At 18 or 16 fps he was taking 4.5 or 4 steps per second, either of which are possible considering Patterson's short stature.

Krantz had employed an elegantly straightforward approach to determining the frame speed. He noted, as had Grieve, that the leg-to-stature ratio of the film subject was comparable to an average human. Since the limbs swing essentially like modified pendulums, then the period of the swing is proportional to the square root of their lengths. Therefore, the frame speed, not to mention the height of the film subject, can be determined by comparing its rate of step with a human of known height. Krantz, at 6′ 5″ tall, used himself as the comparative biped and found that a two-step stride required an average of 1.15 seconds if he was walking very briskly, and 1.3 seconds if he walked more slowly. If the

frame speed was 24 fps, the subject's walking speed was less than one second per stride, which would be a very fast unnatural movement for someone of comparable height and would produce a jerky halting gait. At 18 fps the film subject was moving at 1.25 frames per stride, intermediate between Krantz's walking speeds, indicating that the slower film speed was the correct one. Finally, Patterson had shot film footage just prior to the encounter, showing one of them riding and leading the packhorse up the creek bottom. When played back at 24 fps the gait of the horse is very jerky and unnatural, while at 18 fps the movements appear quite appropriate, further indicating that the camera was set at the slower frame speed.

I recently presented this new information about frame speed to Dr. Grieve and asked what implications this might have for his conclusions about the film. He reiterated his position that the possibility of fakery was *ruled out* at the slower frame speed. He qualified that statement by acknowledging that it might be conceivable for a practiced actor or a dancer to execute such an extravagantly atypical pattern of gait at 16 or 18 fps, but took it as highly improbable.

Primatologist John Napier examines a castof a sasquatch footprint. (Courtesy of Martion and Erik Dahinden)

Dr. Dmitri Donskoy worked out training methods for Soviet athletes preparing for international competition, including the Olympics. His assessment

of the film subject is a qualitative appraisal of the synergy of the whole organism. He concluded by noting an expressiveness of movement, indicating a motor system well adapted to the task it is called upon to perform. “In other words, the neat perfection is typical of those movements which through regular use have become habitual and automatic . . . At the same time, with all the diversity of human gaits, such a walk as demonstrated by the creature in the film is absolutely nontypical of man.” This is admittedly a subjective assessment that may be trivialized by some, but one that is based upon an intimate and extensive familiarity with human athletic movements and the underlying functional anatomy.

In 1972, Dr. Napier, one of the few U.S. scientists of very applicable expertise who maintained an open mind toward the subject, published a book titled, *Bigfoot: the Yeti and Sasquatch in Myth and Reality*, containing his evaluation of the Patterson film, including his initial impressions upon viewing it at the Smithsonian in 1967 and after dozens of viewings both frame-by-frame and from printed stills. His assessment is remarkably at odds with those by others who have studied the film, such as the preceding statements by Dr. Donskoy. Napier concludes, “There is little doubt that the scientific evidence taken collectively points to a hoax of some kind. The creature shown in the film does not stand up well to functional analysis. There are too many inconsistencies; yet no scientist to whom I have spoken and who has seen the film has any direct evidence to prove that the episode was anything other than what it purported to be. My own comment quoted in an article in *Argosy* magazine (February 1968) was that there was nothing in the film, which would prove conclusively that this was a hoax. In effect, what I meant was that I could not see the zipper; and I still can’t. There I think we must leave the matter.”

Rather than leave it there, a closer examination of Napier’s observations indicates that his conclusion has little foundation. He cited several impressions made at the 1967 showing at Washington, D.C., that remained unchanged by further examination of the film. His impression was that the gait was consistent with a human, specifically a male human. However, a relatively small-brained ape would not have the obstetric constraints of a human female pelvis, and therefore would not be expected to exhibit a dramatic gender difference in style of gait. He added that the walk was “self-conscious” which he went on to attribute to a conscious effort to exaggerate the stride on false feet. This inference appears at odds with his earlier observation that, “The physical and psychological attitudes of the creature appear totally relaxed almost to the degree of nonchalance.” He speculated that the center of gravity appeared to be

positioned comparably to a human male's, although the upper body bulk seemed to dictate a higher position of the center of gravity. Since the film subject's upper body bulk appears proportionately matched by that of the lower body, I can see no inconsistency on this point. Also, there was Napier's discomfort with the combination of apelike and humanlike attributes. Again, our present knowledge of the course of hominid evolution renders this concern obsolete; early hominids display a mosaic of apelike and humanlike traits. Finally, Napier suggested that the feet were too large for the estimated stature and the reported step length too short. This conclusion was arrived at using standardized human coefficients (without allowance for expected deviations) applied to a purportedly unknown hominoid ape, surely the application of a standard of debatable relevance. As will be discussed in chapter 13, the proportions of the foot segments are not typical of human feet, but yet are quite reasonable given the inferred mechanics of the sasquatch foot and size of the subject.

Composite illustration of several frames ot the PattersonGimlin film superimposed with a six-foot tall subject (Courtesy of Martin and Erik Dahin den and NASI)

After unsuccessful attempts to recruit disinterested technical analysis of the film, Dr. Grover Krantz undertook an analysis of his own, published in his book titled, *Bigfoot Sasquatch Evidence*. Not only did he have access to additional information regarding the provenience of the film, but he also came to

personally know both Roger Patterson and Bob Gimlin very well. The technical aspects of the film subject, combined with the circumstantial evidence of the encounter, led him to conclude with a high degree of certitude that the film was genuine.

In another study conducted at the film site, Peter Byrne photographed a model holding a graduated staff exactly where the film was shot. The model, Michael Hodgson, was 6′ and 150 pounds. Jeff Glickman, a certified forensic examiner, superimposed the photograph over frames from the PattersonGimlin film and aligned visible landmarks. He concluded that the film subject was 7′ 3-5″ tall (± 1 inch). Glickman summarized his findings in a report prepared by the North American Science Institute (NASI). He went on to note a number of anatomical details that appeared similar to those of a mountain gorilla. The congruence of the appearance of the film subject's foot and the footprints cast at the film site was demonstrated. This was noteworthy since some had contested that the footprints were hoaxed separately, after the filming. He also drew attention to an interesting detail of the visible presence and action of the kneecap. The range of motion of the knee joint was demonstrated to be distinct from typical human gait patterns. Glickman pointed out clear surface plasticity in the side of the torso as the subject turns to look back at the witnesses. The digitized film was subjected to an edge detection algorithm but no seams or borders were found. In conclusion he stated, "Despite three years of rigorous examination by the author [Glickman], the PattersonGimlin film cannot be demonstrated to be a forgery at this time."

Dr. David Daegling, a physical anthropologist at the University of Florida specializing in the primate chewing apparatus, and Dr. Daniel Schmitt at Duke University, a specialist in primate locomotion, undertook a recent analysis of the film, addressing two fundamental issues: Are the film subject's body dimensions outside the range of human variation? Can a human duplicate the gait of the film subject? The results of their investigation were published in the Skeptical Inquirer (May/June 1999) and reiterated in a book by Daegling, *Bigfoot Exposed*. After pointing out the potential sources for measurement error plaguing the efforts to estimate the precise dimensions in the film, they flatly state that the *exact* dimensions are unknowable. On this point I must concur. However, they acknowledge that the scale of the footprints, which are correlated with the sole of the foot quite visible in the film, is known. This potential scalar is one-fifth to one-sixth of the subject's height and while not ideal, provides a reasonable reference for approximate height estimation, even as we acknowledge the potential for measurement error. The inherent scale of the foot was the

primary basis for one of Dr. Krantz's estimates of stature and dimensions. Daegling and Schmitt report, "Krantz's estimate of the film subject's stature is 6′ 6″ (198 cm), well within human limits, but he argues that the chest width of the subject is incompatible with the human form: 'I can confidently state that no man of that stature is built that broadly.' Assuming that these parameters are measured without error, this assertion may be refuted by a quick consultation of the *Anthropometric Source Book* (1978). Chest width is measured by Krantz in the same fashion as a distance known as *interscye* in the anthropometric literature. In a sample of 1,004 men of the German Air Force, interscye of the ninety-fifth percentile is 49.6 cm, a good 3 cm larger than Bigfoot's impossibly wide thorax. The ninety-fifth percentile stature is 187.1 cm in this group, less than 4 inches shorter than the film subject. Unless Krantz would argue that taller Air Force personnel necessarily have narrower chests, his confident statement is admirable for its faith but not its veracity."

It seems their consultation of this reference was too *"quick,"* as Daegling and Schmitt have unfortunately misstated their case. By referring to the *Anthropometric Source Book*, one discovers that the "interscye" measure (#506) is "a *taped* measure across the back between the posterior axillary folds at the lower level of the armpit." A taped measure is distinguished as an arc or a circumference measured on the surface of the body, rather than a straight projected length, as would be estimated from a film image. In this case interscye is an arc following the contour of the back from one armpit to the other. If the radius of curvature of this arc is large, then the difference between the length of the arc and its cord length, or linear distance between its end points, is minor, and perhaps justifiably negligible. If there is considerable depth to the torso, the radius of curvature will be considerably smaller and the disparity between arc length and cord length can be significant. The correct measure found in the *Anthropometric Source Book* for comparison to Krantz's chest breadth is, not surprisingly, "chest breadth" (metric #223), defined as "the breadth of the torso measured at the nipple line" (without pressure). This is a straight-line measure of the greatest breadth of the torso taken at the level of the male nipple. Whether projected from the ventral or dorsal surface is irrelevant. In this dimension the ninety-fifth percentile of the same sample of German aviators measures a mere 35.4 cm, much less than the 49.6 cm value for the interscye, and also much less than the 46.5 cm chest breadth estimated by Krantz for the film subject. Indeed, the ninety-ninth percentile of the German sample still only reaches 37.4 cm, still over 9 cm shy of the film subject's estimated chest breadth. The largest reported value actually comes from a sizeable sample of 2,984 U.S. law enforcement

officers, with a ninety-ninth percentile value of 41.7 cm for chest breadth and 192.6 cm for stature.

Broad-shouldered men often have a decidedly V-shaped torso; that is, their hips are not nearly as wide as their chest and shoulders. The torso of the film subject appears as wide through the hips as it does through the chest, roughly 50 cm according to Krantz's estimate of stature. Turning again to the *Anthropometric Source Book* we find that for standing hip breadth, the sample of German aviators referred to previously yields a representative ninety-fifth percentile value of 38.3 cm, once again considerably less robust than the film subject. Krantz estimated the film subject's shoulder breadth at 71.6 cm, compared to the German aviators ninety-ninth percentile value of 51.8 cm. So much for the claim of refuting Bigfoot's "impossible" dimensions. It appears that the plausibility of Dr. Krantz's estimates remain intact.

Turning to the second issue, Daegling and Schmitt take exception to Krantz's opinion that based on the manner of walking there is "no possibility" that the subject is a man in a fur suit. They acknowledge that the apparent gait is atypical of normal human walking, but point out that humans can adopt a compliant gait that approximates the deeper flexion of knees and hips exhibited by the film subject and that it also results in a longer stride and faster walk. This simplified generalization is correct, and a refined examination will certainly shed light on the distinctions between a typical human gait, a human compliant gait, and the compliant atypical gait exhibited by the film subject. However, this generalization also glosses over several aspects of lower limb movement that appear distinctive about the film subject's walk, such as the noticeably abducted foot during the swing phase. Furthermore, they note that statements by Dahinden and Perez, "that, on one of his numerous visits to the film site, he and others present were incapable of walking the distance traveled by the film subject in the time that it did so (assuming a film speed of 24 fps)" seem to attribute superhuman capabilities to the film subject. Actually the observation was intended to point out what had been determined independently—that the film could only have been shot at a slower frame speed. They did not intend to suggest that the subject was walking at extraordinary speeds. Indeed, Daegling and Schmitt present data indicating that human subjects of appropriate stature, when using a forced high-speed compliant gait, can match the film subject's walking speed, assuming 24 fps. However, this assertion trivializes the naturalness of gait exhibited by the subject when viewed at the correct film speed (18 fps) that is not matched by the exaggerated, "forced, high-speed" human compliant gait referred to by Daegling and Schmitt. This point of film

speed was rather significant to Don Grieve, who concluded that, based on the pattern and speed of the subject's gait, the possibility of fakery was virtually ruled out if the film was shot at 16 or 18 fps, rather than 24 fps. The question remains whether a human subject using a forced high-speed compliant gait would exhibit a fluid pattern of joint excursions comparable to those of the film subject. That remains to be demonstrated.

In sum, there has been considerable discussion of various individual aspects of the anatomy, locomotion, and general behavior of the PattersonGimlin film subject, with opinions and interpretations sometimes inexplicably varying widely between the experts. Many of these discrepancies are simply repeated without discussion or qualification. For example, Napier expressed disapproval of what he saw as incongruence between the film subject's height and the length of its feet. He determined on the basis of a simple formula (stature = foot length × 6.6) that a foot of between 14 and 15 inches in length indicates a stature of between 7′ 8″ and 8′ 3″, a range considerably higher than most estimates. This simplified formula does not account for expected variation present within a human population and it further assumes that a similar relationship holds true for a different and markedly larger species. Curiously, Geoffrey Bourne of Yerkes Primate Center drew a very different conclusion. He said, "It appears to be about seven feet in height, but it left footprints that were rather small for such a big animal—only fourteen and a half inches long." My own study of sasquatch footprints in general, and specifically the film site footprints, suggests a disproportionate length of the toes and heel by comparison to the human foot. Assuming these add approximately 10 percent to the relative length of the foot, an adjusted height estimate according to Napier's *human* formula falls closer to seven feet. Making further allowances for differences in the height of the cranium, the estimate is even more congruent with other height estimates.



The male gorilla skull on the left displays a prominent bony ridge, the sagittal crest, which provides expanded attachment for the chewing muscles.

This raises the issue of the hominoid crest. Exception has been taken to the combination of an apparent sagittal crest with the presence of what seem to be female breasts. The sagittal crest is a bony ridge that runs along the midline of the skull. It is often characterized as a male feature, but is really a function of the ratio of body mass to cranial volume and the robustness of the jaws. The muscles necessary to operate the jaws and chew a coarse diet require sufficient surface area on the cranium for attachment. If sufficient area is not provided by the rounded contour of the cranium then a projecting flange of bone creates additional surface. In relatively smaller species of primate, such a situation usually only occurs in more robust males who sport larger jaws and more pronounced canines. However, in larger species where the disproportionate increase in muscle mass, i.e., volume, outstrips the increase of bony surface area, larger females may also exhibit sagittal cresting, as is the case with some female gorillas. These are not as pronounced in their development as are the male's crest, but to suggest this is unprecedented reveals a lack of understanding of the biomechanics underlying this trait and an ignorance of the anatomy observable in available museum specimens. In addition, the gorilla's head is capped by a pad of fibrous connective tissue that further adds to the peaked appearance of the head. Given the estimated mass of the film subject, the presence of a crest, even on a female, should come as no surprise. However, it is not at all certain that a

bony crest is solely responsible for the subject's peaked head. In an interview with Ivan Sanderson, Patterson noted, "She seemed to have a sort of peak on the back of her head, but whether this was longer hair or not I don't know." Careful observation suggests that a degree of the peaking may be due to a shock of hair that seems to bounce in step on occasion. Therefore, determination of the extent of development of a sagittal crest on the film subject is uncertain.

Colin Groves, a primatologist at the Australian National University, has noted with regard to the film subject that, "There is a big sagittal crest, implying heavy jaws and temporal musculature, yet the jaws are in fact not large or protrusive." Russian investigator Igor Bourtsev drew attention to film frame 344, which depicts a clear lateral view of the facial profile, just before the film subject turns to look at Patterson. Although the pertinent landmarks cannot be precisely discerned, it appears that the head is tipped forward slightly relative to the Frankfurt horizontal, a line tangential to the inferior margin of the orbit and the top of the ear canal. The line is typically horizontal when the head is held at rest, but may be inclined when the head is leaning into a brisk stride. By orienting skulls to this horizontal plane, consistent comparisons can be made. The jaws of the film subject do project beyond the rather flattened nose, but are certainly nowhere near as projecting (prognathic) as a chimp or gorilla. However, flattening of the face is an adaptation exhibited in a number of primates whose diet is coarse, including *Gigantopithecus*. This rearrangement shifts the loading of the bite to the enlarged premolars and molars. The lower face appears quite deep vertically and the lower jaw becomes deeper posteriorly with evidence of flaring of the angle of the mandible. This flaring provides greater surface area and leverage for the enlarged masseter, the principal chewing muscle in front of the ear. This muscle is quite evident in the film subject. Its relative thickness is seen in the pronounced vertical ridge indicating its anterior margin.

That the face and jaws are massive is attested to also by the correlated presence of prominent muscles in the back of the neck and shoulders that attach to the posterior base of the skull and balance it over the spine. These attach relatively higher on the skull than is the case in humans, which accords with the slightly stooped and forward carriage of the head, relatively small braincase, and large jaws. However, the attachment point, is neither as high nor as prominent as that in quadrupedal apes.

Frank Beebe, of the British Columbia Provincial Museum, questioned why a creature with a tall bony crest on its skull has a nonprotuberant abdomen. This objection assumes that a large ape would have a protruding stomach to accommodate the capacious gut required to process a coarse herbaceous diet.

Four factors are overlooked in this assessment. First, an assertion of a "tall" sagittal crest is equivocal, as has been discussed.

Second, the reputed diet of the species represented by the film subject is omnivorous rather than strictly herbivorous. The menu of food items reported by eyewitnesses ranges from berries to elk. It is unjustified to assume a diet for sasquatch requiring extensive fermentation of bulk vegetative foods. Kenneth Wylie, a Ph.D. in African Studies, notes that a "flat stomach in an omnivorous or carnivorous terrestrial primate of such bulk would be unprecedented." I must assume that he implies that the existence of an omnivorous or carnivorous terrestrial primate of such bulk would be unprecedented. In fact, we have seen that *Gigantopithecus* has already set that precedent, since microwear analysis of its teeth indicate an omnivorous diet similar to that of a chimpanzee.

Third, if it is implied that sasquatch exhibits an *unreasonably* flat stomach, then an understanding of comparative abdominal anatomy is lacking. A specialized shortening of the lower back and a broad forward-facing pelvic architecture accentuate the protruding gut of the African apes, especially the larger gorilla, whose diet includes more foliage. The film subject has a lower back and pelvic structure more similar to a human, in accordance with its bipedal posture and locomotion. It does not appear to have a shortened lower back and its pelvis appears more basin-shaped than an ape's. Hence, a relatively capacious abdomen would not appear so prominent in a sasquatch torso.

However, in the fourth factor it differs from human torso morphology considerably. In addition to a very wide torso, the film subject has a noticeably barrel-shaped torso, being nearly as deep from front to back as it is wide. Therefore, the volume of the torso is in fact relatively large for its size compared to humans. In all, the generalized anatomy seems consistent with a moderate-length gut combined with a generalized omnivorous diet.



The torso skeletons of a macaque monkey, a gibbon, a human, and a gorilla (Reproduced from A. H. Schultz, 1950, “The Specializations of Man and His Place Among the Catarrhine Primates,” Cold Spring Harbor Symposium on Quantitative Biology, Vol. 15, p. 41, Fig. 1.)



Rear view of a sculpture of the PattersonGimlin film subject, (created by and courtesy of Igor Bourtsev) contrasted in approximate scale to a human female and male figure

Napier took exception to the chimerical combination of apelike and

humanlike characteristics in the film subject. He remarked upon this after viewing the film and reiterated in his book, “The upper half of the body bears some resemblance to an ape and the lower half is typically human. It is almost impossible to conceive that such structural hybrids could exist in nature. One half of the animal must be artificial.” This statement was made in 1972 and although early hominid fossils had been studied by that time, it wasn’t until 1974 and the discovery of an *Australopithecus afarensis* skeleton that came to be known as “Lucy” that the mosaic nature of hominid evolution began to be fully appreciated. Lucy exhibited an anatomy in its upper body that was remarkably apelike, while the lower half bore many of the hallmarks of rather humanlike bipedalism. Napier’s statement was premature, and in fact the anatomy of the film subject actually anticipated what has become accepted as congruent with the parallel evolution of hominid bipedalism.

Several scientists have made a point of the similarity of the film subject’s walk to the walk of a human male, even though the subject bears the pendant breasts of a female. The distinctions between genders in human walking are the result of the wider female pelvis, necessitated by the large size of the birth canal needed to accommodate the human neonatal brain. This adaptation obliges a greater distance between the hip joints in the human female pelvis, which exaggerates the side-to-side tilt of the hips during walking. A bipedal ape of relatively smaller cranial capacity would have no such obstetric constraints and both male and female pelves of that species would be of similar architecture. Therefore, there simply is no incongruence. A “masculine” walk, by human standards, is exactly what should be expected for a small-brained female bipedal ape.

Pendulous breasts, it has been suggested, are a strictly human characteristic and are not to be expected on a creature with such apelike characteristics. The evolution of the human female breast has been a topic of extensive discussion and speculation in the scientific literature. There is no consensus regarding the selection pressures for human breast development or for the timing of their appearance in hominid evolution. In fact, the breasts of *lactating* apes are considerably enlarged, some even falling within the lower range of human dimensional variation, which is notably considerable. However, ape breasts do not have permanent fat deposits as do typical human female breasts, and they are certainly not as prominent as those present on the film subject. Whether the film subject is lactating or not is obviously unknown, however given the apparent engorgement it is tempting to speculate that she may indeed be lactating. Furthermore, if the enlargement of human breasts is somehow linked to

bipedalism, as has been hypothesized in at least one scenario among many, then why should it be considered aberrant for another bipedal hominoid to have evolved them convergently?

Concern has been raised over the light color of the soles of the feet, which have been said to be lighter than the palms and much lighter than typically seen in dark-colored great apes. In the film, the soles of the feet are similar in shade to the sandbar, so much so that some have suggested that perhaps sand was adhering to the wet feet of the film subject if it had just crossed the creek. What is more likely is that the smooth surface of the sole of the foot, when angled appropriately to the sun and the camera, was overexposed on the film. When I had the opportunity to visit the film site I was impressed by the dark gray shade of the sandbar. It was much darker than I expected from my viewings of the film. I even scooped some up in a film canister for later reference. Therefore, in the film the sole of the foot appears the same shade as the sand, while in reality the sand is much darker than it appears in the film. Hence, the sole of the foot is actually darker than it appears in the film. The same overexposure also occurs with the palms to a lesser degree due to their different angle to the sun, and is less noticeable due to their limited visibility. They look relatively darker than the overexposed soles, except for occasional highlights. In those frames when the sun does reflect off the appropriately oriented edge of the palm, it appears every bit as light (overexposed) as the soles of the feet. A similar reflective shine can also be seen as highlights on the smooth parts of the face, especially beneath the eye, across the nose, and at the lips. However, due to the more irregular surface of the face, as compared to the relatively flat plane of the sole of the foot, the overall darkness of the face is more readily perceived. A simple comparison to the appearance of the feet of a chimp or gorilla when viewed from a comparable angle with similar lighting conditions reveals their remarkable similarity.

A sequence of stills from the PattersonGimlin film illustrating the appearance of the sole of the foot (Courtesy of Martin and Erik Dahinden). Below is a sequence of images of a chimpanzee foot seen from a comparable perspective.

Frank Beebe was adamant that the film was, as he put it, “a double-jointed phony.” He asserted that there was a dead giveaway of fakery in the casts and the photographs of the footprints. “There is plain evidence of a double tarsal joint—a phenomenon that appears nowhere in nature. It can be explained only by picturing a human foot inside some larger mechanical device to make the tracks.”

It isn’t clear whether Beebe was referring to the so-called split ball feature, which is only mildly expressed in the filmsubject casts, or whether attention had been drawn to the midtarsal pressure ridge. In either case Beebe was apparently unfamiliar with ape feet, which exhibit a much greater degree of flexibility of the midtarsus, called the midtarsal break (see chapter 13). He may also have been unfamiliar with infant human feet, which possess a flexion crease across the ball of the foot very similar to that evident in the casts of the film subject. In persons with hypermobile feet, this crease may persist for some time.



Casts of infant and juvenile human feet exhibiting a flexion crease at the haIlucial, metatarsophalangeal joint, the "ball" of the foot

I was curious what sort of evaluation the film would receive today from disinterested experts in human locomotion nearly four decades later. I posted a query on the Biomechanics discussion list on the World Wide Web. It seemed reasonable that with the advances in technology a definitive quantitative analysis of the film subject's pattern of movement should be possible. There were three takers of the challenge, but only one ultimately followed through and offered an opinion. Dr. Gordon Robertson of the University of Ottawa, an expert in biomechanics and gait analysis remarked, "My only comment would be that the movements of the subject do not appear to be that of an animal, for example a bear, because of the rather blase attitude towards the filmmaker. All wild animals would have reacted more cautiously. But as to the subject being a human or another species the film is not of sufficient quality to reach any conclusions. Thus, trying to determine if the gait parameters were similar to a human is impossible. Furthermore, any human can mimic other gait patterns so that discrimination between human and non-human gait is also impossible especially with such a short amount of data."

Robertson's generalization about wild animal behavior seems too simplistic, and the evidence does not seem to justify his characterization of the film subject's "attitude." However his cautionary note about the challenges of distinguishing the film subject's gait from a human's gait is well taken, although perhaps also overstated. It should be noted that this preliminary assessment was based on a dubbed VHS tape several generations removed from the original film.

Advances in graphic technology have made it possible to visualize and study the PattersonGimlin film in novel and revealing ways. What lies beneath the hairy covering of the famous California Bigfoot? Animator and computer-generated effects expert Reuben Steindorf, of Vision Realm, created a computer model of “Patty,” as the film subject has been nicknamed. Beginning with a reconstruction of the skeletal proportions of the subject’s foot that I inferred based on tracks from the film site, combined with casts of the tracks themselves, Steindorf reconstructed Patty’s skeletal anatomy from the ground up, using “reverse kinematics.” This is a laborious process that creates linkages between the modeled skeleton and the movie image, matching limb segments and joint centers identified on the film subject. Once the superimposed correlation is established, the model can be tracked through three-dimensional space. His digitally animated model comes to life as an animated skeleton tracing Patty’s movements across the monitor screen. The model skeleton can be rotated in 3-D space, permitting a view from any desired perspective.

By drawing attention to skeletal landmarks, the stooped posture of the head and shoulders is emphasized as Patty walks smoothly on flexed knees and hips. This is a compliant gait and is adaptive for a heavy biped. A backpacker with a heavy pack typically adopts this manner of walking, especially when walking downhill, in order to reduce shock to the ankles, knees, and hips. The compliance of the slightly flexed joints reduces stress on bones and ligaments, and stores kinetic energy in tendons crossing flexed joints.

Reuben Steindorf reconstructed the skeleton of the film subject using reverse kinematics. (Courtesy of Doug Hajicek / Whitewolf Entertainment, Inc.)

A consequence of the flexed knee of the support limb is reduced clearance for the swing limb, the limb in forward motion. In other words, the distance between the hip and the ground is less than the length of a fully extended support limb. This necessitates a higher step by the swing limb in order for the toes to clear the ground. Imagine walking with swim fins on one's feet as an extremely exaggerated example of this high-stepping walk. Also noteworthy is the sharp toeing out (abduction) of the foot during the swing phase. Together with the high step, this toeing out may aid in clearance of the swing foot.



Interlimb proportions of the film subject based on Steindorf's estimation and tracking of joint centers (Courtesy of John Green)

During the animation process Steindorf tracked the joint centers through 116 frames of the film, yielding a reliable estimate of the film subject's limb proportions. The problem of foreshortening is addressed by taking the maximal length of limb segments apparent when the limb lies parallel to the film plane. Steindorf confirmed, as had been previously noted by numerous observers, that the upper extremity was rather long relative to the lower. This ratio can be expressed as an intermembral index (IM). It is defined as the combined length of the humerus and radius, i.e., the distance between shoulder and wrist, divided by the combined length of the femur and tibia, hip to ankle, times 100. The intermembral index for the film subject was approximately 88. I had independently made a preliminary estimate of between 80 and 90, a range that brackets Steindorf s value. An average human IM is 71. Obviously, determining the intermembral index from the film frames is not an exact exercise. By this I simply mean it is not as accurate as putting disarticulated dry bones from a museum drawer on a measuring board. However, it is possible to make a reasonable estimate for the sake of comparison with a would-be human actor. The centers of rotation of the joints can be aproximated for the mov ing limb segments and proportionalities of the limbs can be determined even in the absence of an absolute scale. Remember an index, being a ratio, has no units. The fact that my own preliminary estimate of IM between 80 and 90 was

independently confirmed by Steindorf s more systematic analysis yielding an IM value of approximatel 88 should not be casually dismissed. This estimate is well outside the human range as reported in various sources of anthropometric data, so much so that the margin of measurement error in estimating the index for the film subject is trivial. The combination of these proportions with the exceptional breadth dimensions argue compellingly against the simplistic hypothesis of an average man, even one wearing shoulder pads, donning a typical gorilla costume, or using artificial arm extensions.

During the transfer of the film to high definition tape, a pair of unusual details caught Doug Hajicek's attention. There was a peculiar orientation of the swinging leg during the high-stepping walk. The knee appeared to walleye inward during the swing of the limb, while the foot was noticeably abducted or rotated outward. The Russian observers had made a passing note of the same thing. In his book *American Bigfoot: Fact or Fiction*, Dmitri Bayanov observed, ". . . Patty left footprints following a single invisible line. As revealed by some of the frames, with each step she made with her lifted foot a kind of rotation movement, as if dancing the Charleston, and put the foot down exactly in front of the one on the ground." Was this a strategy for clearing the foot when walking on a flexed, compliant limb? Or might it indicate an injury resulting in a compromised function of the limb? Obviously, generalizations based on a sample of one should be entertained cautiously.



A comparison of the effects of scaling the upper and lower extremity of Bob Heironimus to the limb proportions seen in the film subject (Courtesy of Martin and Erik Dahinden and Chris Murphy)

At a particular point in the film an unusual looking bulge on the right outer thigh caught Hajicek's attention. It protruded noticeably during extension of the knee in support. I discussed possible interpretations of the bulge with Dr. Andrew Nelson, of the Idaho State University health-professions faculty. The bulge appears consistent with a traumatic rupture of the lateral fascia over the thigh. Herniations of muscle through a defect in the overlying fascia of the thigh are rare in humans, but when present in the thigh usually occur over the quadriceps, specifically over the vastus lateralis muscle. The lateral fascia is a layer of fibrous connective tissue that surrounds the muscles of the thigh like a support hose. A rupture may occur directly, as a result of a traumatic blow, or alternately, it may be the indirect result of pathology such as trichinosis, typhoid fever, or other infections. When the muscle contracts in the early part of the step it protrudes prominently through the gap in the fascia. It reduces when the muscle relaxes. Accordingly, the bulge apparent on the thigh of the PattersonGimlin film subject is prominent precisely at the period of the step cycle when the vastus lateralis is contracting and abates when the muscle is relaxed. What are the odds of such details of anatomy and pathology being functionally incorporated into a costume from 1967?



Dr. Andrew Nelson, Idaho State University, comments on the unlikelihood of a hoaxer in 1967 having an understanding of gait biomechanics. (Courtesy of Doug Hajicek/Whitewolf Entertainment, Inc.)

Dr. Nelson concluded, "After analyzing the biomechanical issues of the Patterson footage, I find it very hard to believe that somebody in 1967 could have fabricated the intricacies of the soft-tissue anomaly as evidenced by the

irregularity of the thigh. The understanding of biomechanics at that time was primitive at best."

Kyle W. Council, a professional computer graphics animator, offered his perspective of the film. "As part of my craft I have an intuitive sense of natural human movement. I animate human characters for games. When I view the PattersonGimlin film, I see a mode of movement that is not human, but humanlike. The arm swing and movement of the shoulder girdles are clearly that of a truly massive frame. The musculature of the creature is very thick, but not restrictive to the range of motion in the shoulder joints. In the trapezius muscle group, the diamond-shaped set of muscles that anchor the shoulders, nape of the neck, and upper thoracic vertebrae, the contraction of these thick muscle sheets is clearly visible. In the cadence of the walk, the presence of great and compact body mass is evident. Also, the creature's knee, not reaching full extension, is certainly an adaptation to supporting great weight. A fully extended knee has poor resistance to twisting force.

"In conclusion, the reality of the film subject as an uncataloged animal is self-evident. It simply cannot be a costume; the boundaries of the human form do not even fit within the form of the creature. Furthermore the mass of the creature is so great and carried with such poise, a man could not even be trained to carry such great weight or walk bearing weight in such a fashion. The muscle masses, if they had been padding, would have been static and restrictive. The presence of visible muscle contraction, the freedom of movement, and the cadence of the walk, all fully support the claim that the footage documents a living hominid outside the genus of man."

I found Council's comment that ". . . the boundaries of the human form do not even fit within the form of the creature," a significant one. Recall the stark contrast evident between McClarin's profile and that of Patty, as well as the revelations of the *Anthropometric Source Book*. In this vein, the reaction of an avid bodybuilder provided some particularly insightful perspective on the physique of the PattersonGimlin film subject. First, he noticed the very large and well separated deltoid muscles. He noted that he had only seen one human being with deltoids that large. It was none other than Arnold Schwarzenegger at his peak. Next, the trapezius attached rather high on the back of the head. He compared them to Dorian Yates and Greg Kovacs, who are noted for their trapezius development; neither had traps remotely as large as seen on the film subject. The appearance of the latissimus dorsi was very unusual in that the large muscle appeared to attach higher up on the thorax than in humans. He observed that the gluteus maximus appeared nearly three times more massive than typical

in human athletes. The gastrocnemius, especially the lateral head, and the soleus, comprising the calf muscles, were exceptionally large and well developed. He compared them to those of Mike Matarazzo, known for the largest calf muscles in history—the film subject won hands down. He attested that no bodybuilder, not even Schwarzenegger, came close to the size of the erector spinae muscles, the two columns of muscle running parallel to the backbone. Finally, the complete naturalness of appearance and movement of the scapulae, or shoulder blades, impressed him.

An enlightening comparison can be made between the dimensions of Arnold Schwarzenegger at the peak of his bodybuilding career and estimated dimensions provided by Chris Murphy, based on a reconstructed height at the upper range of estimates for the PattersonGimlin film subject:

IN/LBS	SCHWARZENEGGER	P-G FILM SUBJECT
height	74	88
weight	235	700
arms	22	32
chest	57	68
waist	34	68
thighs	28.5	46
calves	20	30

There is certainly a diversity of perspectives and conclusions about the nature and implications of the PattersonGimlin film. Those that have given the film the most thorough consideration have, with few exceptions, concluded that it is probably authentic or that its authenticity cannot be readily eliminated given the limitations of image quality or want of definite scale. It should be remembered that the original film was viewed a number of times before it was duplicated, rendering it somewhat scratched and damaged. The images that most people see today are the product of several generations of copying from film to film and then to video or digital image. This has drastically reduced the clarity and detail of the image and potentially introduced artifacts that might distract the

casual observer from the straightforward impression of the image. On the other hand, those who are most adamant in their rejection of the film, characterizing it as an obvious “man in a monkey suit,” are often the least familiar with its details and its provenance, or they have little or no expertise with which to assess it meaningfully. After nearly four decades, the film remains a most intriguing piece of natural history footage.

Demo version limitation

Demo version limitation

Demo version limitation

BY THE NUMBERS: STATISTICAL ANALYSES

As a young newspaperman, John Green was aware of stories of the hairy giants of Canada's Pacific Coast. First popularized in 1929 by writer J.W. Burns, a teacher on the Chehalis Indian Reservation near Green's hometown of Harrison Hot Springs, sasquatch had become something of a regional icon and the focus of the town's celebration of Canada's Centennial. Never having taken the "Indian legend" seriously, Green was nonetheless intrigued by firsthand accounts of giant footprints by people he knew well and respected. Said Green, "Interviewing people and gathering facts are my regular occupation, and if I were being fooled very often, my readers would be bringing it to my attention. These stories rang true to me, but I took the additional step of having them legally sworn to . . . I took what I had gathered to the University of B.C., expecting that scientists would want to investigate the matter. I still had a great deal to learn." Undeterred by the offhand dismissal of the possibility of a giant ape, he went on during the succeeding decades to collect accounts, numbering into the thousands, of encounters with hairy giants and discoveries of huge footprints by people from every walk of life.

Young newspaperman John Green shows a 17-inch cast of California's Bigfoot to residents of Agassiz, British Columbia. (Photograph by Jack Long)

What is the utility of Green's collection of stories? Taken individually we are not only at the mercy of the veracity of the storyteller, but also limited by the witnesses' individual power of observation and accuracy of interpretation. Furthermore, the compiled data do not represent a systematic, regimented sampling taken under controlled conditions. These data represent the sum of scores of serendipitous encounters, which may or may not be credible, that happened to get reported and happened to make their way into the files of John Green. Many of these came by way of newspaper clipping services or radio news reports, personal correspondence, and published narratives. Personally investigating and assessing the credibility of each and every report would fully occupy the attention of a large fulltime investigative team with an unlimited budget, let alone a single journalist with a job to hold down and a family to support.

However, upon reflection it will be recognized that this sort of anecdotal data forms the basis for many valid statistical analyses. Green notes, "If it is any comfort, I once did a study of a wide variety of points, comparing percentages obtained while using only those stories which I thought should be reliable, and those obtained using every report in the file. The differences were insignificant in almost every case." Therefore, there appears to be an internal consistency to the signal emerging from the data, but whether this is a signal based on a common perception of a real animal or an imagined one is the question. Might there possibly be an unconscious filtering of accounts that fail to conform to some preconception of an American abominable snowman?

What is the hypothetical portrait of the sasquatch and its behavior that is

implied by these reports? In Green's own words, "The reports are numerous enough to establish a few things about the sasquatch lifestyle. They are omnivorous, with almost equal mention of meats and vegetable matter in observations of things eaten, or apparently taken presumably to be eaten. They are largely nocturnal. Although humans cannot see well in the dark and there are far more humans around in the daytime, almost half of the sightings take place at night. They are not active in cold weather. Less than 10 percent of reports mention snow, and tracks in snow are rare. They have an affinity for water. Unlike the known apes, they have been reported swimming, both on the surface and underwater.

"The reports are also informative in what they do *not* mention. In spite of a common assumption that sasquatch live in caves, indications of use of caves, or any form of shelter, are very rare. Tool use is not indicated at all, and while objects are sometimes thrown, it is in a looping underhand manner, not in an overhand straight line. There are also no reports of fangs, or claws, an unlikely omission if we are dealing with an imaginary monster. These are presumably not reported because they don't exist, but there are also very few reports of females, infants, or small juveniles, which must exist. This brings into question one of the most obvious assumptions, that sasquatch are solitary animals. Less than 10 percent of reports involve more than one creature, but if females and their young are very rarely seen it remains possible that family groups exist, while normally only lone males take a chance of encountering humans."

Sasquatch tracks in snow in the foothills of the Blue Mountains near Walla Walla, Washington. The compacted snow beneath the footprints has pedestalled as the wind has blown away surrounding snow. Their size and length of step is contrasted to the smaller and parallel human track. (Courtesy of Brian Smith)

Reported sizes of sasquatch encountered range from under 4 feet to nearly 14 feet, with an average height of 7.5 feet. Hair was straight and short to medium length. Half of the reported colors were black or dark, one quarter were brown, 15 percent were light in color and 8 percent were gray. Only 14 percent of the reports made any mention of a noticeable smell. Posture was usually erect or with a stoop.

Is it possible to distinguish natural patterns in such observational data concerning sasquatch, from the inherent randomness that one might expect of fabrications and hoaxes? Are there any patterns within the data that would be suggestive of a living population rather than a fictitious phenomenon? Dr. Henner Fahrenbach, retired microscopist, formerly with the Oregon Regional Primate Research Center, has published a statistical analysis of reported sasquatch dimensions based in large measure on Green's compiled data. He limited his analysis to those reports emanating from the western U.S. and Canada. Dr. Fahrenbach states, "A sufficiently large sample size, as we have for many measurements, has the advantage of supporting through such treatment either an origin from a living population of animals or, conversely, exposing a set of fictitiously generated values." With a large enough sample, it can be presumed that any biological patterns present may emerge from the extraneous outliers.



Dr. Henner Fahrenbach was among the first to publish a statistical analysis of metrics of sasquatch anatomy. (Courtesy of Doug Hajicek/Whitewolf Entertaiment, Inc.)

First off, Fahrenbach examined patterns in the frequencies of footprint dimensions. He noted that footprints are the standard stock in trade of sasquatch

research, and have the advantage of providing a degree of objectivity not always attainable with other categories of observational data. Even so, evaluating footprint dimensions is a different matter than say, taking standard measurements of bones in a museum cabinet. An individual footprint is the trace evidence of the interaction of the foot with the variable conditions of the substrate. Apparent dimensions can be influenced and distorted by the dynamics of walking, e.g., slide-ins, dragouts, curled toes, depth of impression, foot rotation, *etc.* The measured greatest length of individual footprints even in a single trackway may vary by as much as 10-15 percent. All of these factors introduce intra-individual variation that will affect derived correlations and indices.



The distribution of foot lengths derived from a sample of reports (Courtesy of Henner Fahrenbach)

A large proportion of continuous frequency distributions in nature approximate a normal distribution, a symmetrical bell-shaped curve. It would be expected that if reported footprint lengths were indeed sampling a living population, the summation of that data would also approximate a normal dustribution. Fahrenbach found that a sample of sasquatch track lengths distribute in a somewhat peaked (kurtosis = 1.89) bell-shaped curve. The range of variation in footprint lengths included from 4 to 27 inches, with a mean of 15.6 inches long and a standard deviation of 3 1 inches. The distribution does not suggest extreme sexual dimorphism, or marked difference in size between males and females, which would be reflected in a bimodal distribution. Fahrenbach acknowledges, “At most, if can be speculated that, at the median of footprint size, the sexual dimorphism does not exceed two inches in foot length or roughly one foot in body height” (since the measurement data were summarized in 2-

inch intervals). It should be recognized that the sample is not necessarily limited to fully adult individuals. A slight negative skewness of the distribution suggests the contribution by juveniles presumably included within the sample. Fahrenbach reasons, "The normal distribution overall argues compellingly against any alternative hypothesis to the existence of the sasquatch as a cryptic species, in that production of fictitious data over forty years by hundreds of people independently of each other would have generated a distribution with many peaks."

Examples of the smallest footprint casts in the author's research collection

Fahrenbach continues by adding related dimensions of the foot and gait that are correlated in a functionally cohesive fashion. For example, sasquatch footprints are not simply enlarged facsimiles of human footprints. They are consistently relatively wider than human footprints of such a size would be. The ratio of width to length is called the width index. Almost the entire set of sasquatch footprints for which length and width measures are available, has a greater width index than average human feet do. This relationship is consistent with the heavy body build reported for sasquatch. When the width index is scaled against foot length, a negative regression is revealed for combined male and female samples of both human and sasquatch feet. That is, the foot width increases at a slower rate than foot length, in both populations. In humans there is a more dramatic drop off in relative foot width, that is, people with very long feet typically have relatively narrow foot widths. In the sasquatch sample the

index remains closer to 0.5 throughout the range of foot lengths, that is, the foot maintains a width that is about half its length throughout the size range.



Bivariate plot of foot length to width for a sample of sasquatch footprints and human feet (Courtesy of Henner Fahrenbach)

Owen Caddy has independently confirmed this observation for a smaller but more recent set of data. A sample of forty widely varying human feet was measured, including foot length, width of ball, and width of heel. A subset was then impressed in a wide variety of soils to varying depths while in a variety of motions. Casts were made and similarly measured. Variances between measures of the foot compared with measures of the casts were less than 3 percent for foot length and less than 2 percent for measures of width. Next a sample of twelve putative sasquatch casts was measured. By expressing the shape of the foot as unitless indices and presenting the data as a bivariate plot, Caddy has demonstrated that there is virtually no overlap between the putative sasquatch footprints and the sample of human feet, even allowing for a margin of error of 3 percent.

It is clear that there is a slightly larger range of variation in the sasquatch sample. On this point Fahrenbach notes, “It is very probable that the sasquatch population, being composed of animals with a long life span, few offspring, and little culling by predators, will display wide physical variation.”



Bivariate plot of heel breadth ratios for a sample of sasquatch and human feet (Courtesy of Owen Caddy)

In exploring the correlation of height and foot length, Fahrenbach began with the PattersonGimlin film subject. Patterson himself estimated the subject to be 7′ 4″ (other estimates based on the scale established by the 14.5″ footprints have been lower). Jeff Glickman, a forensic analyst, arrived at a height of 7′ 3-5″ using a superimposition method with a graduated pole as a reference. The combination of a 14. foot length and 7′ 3.5″ height yields a foot length-to-height ratio of 16.5 percent, or a foot-to-height multiplier of 6.04. In addition Fahrenbach's data include eighty-nine reports with both measured foot length and estimated height. The resulting correlation (correlation coefficient = 0.558) yielded a slightly lower mean multiplier of 5.84. This relationship between foot length and height illustrates that the sasquatch foot grows disproportionately in excess of general bodily dimensions. Since body weight, a function of volume, increases to the cube of linear dimensions, and surface area of the sole of the foot increases to the square, it is to be expected that foot length (and breadth) scales positively with increasing height. In other words, the foot gets relatively longer at a greater rate than height increases. The allometric formula describing this disproportionate size relationship yields a height estimate of 7′ 7″ for a 14.5″ foot. This is slightly higher than the estimate for the PattersonGimlin film subject, but considering that substantial individual variation is anticipated, and that the sample presumably pools male and female (as well as juvenile) individuals, the correlation is impressive.

Frequently, footprints are impressed to remarkable depths, raising questions about the weight of the sasquatch. Fahrenbach notes the difficulty of visual estimates of weight and instead proposes an estimator that utilizes the allometric relationship between chest circumference and body weight for primates ranging

in size from tamarins to baboons, to which he added a sample of ten gorillas. The modified formula incorporating gorillas has a correlation coefficient of 0.956. Turning again to the PattersonGimlin film subject, Fahrenbach derives an estimate of chest circumference of 60″. When the scaling formula is solved using this estimate, a predicted weight of 542 lbs is the result. Considering the variation within the gorilla sample, the potential range of values for the PattersonGimlin film subject lies between 400-700 lbs. Extrapolating further, it could be predicted that a sasquatch with the mean foot length of 15.6″ would stand 7′ 10″ and weigh 658 lbs; an 18″ footprint equates to a 8′ 4″ sasquatch weighing 768 lbs. Bear in mind that there is considerable variation around these predicted values to be expected in a natural population.

The correlation of foot dimensions with predicted weights has significant implications for the accommodation of plantar pressures beneath the foot of a giant bipedal ape. Bone, cartilage, and fatty connective tissues of the foot can only tolerate limited imposed pressures. Allometric relationships, or disproportionate scaling of body dimensions, are adaptations to these stresses imposed on the feet by increased body weight. Fahrenbach examined several sasquatch footprint casts of various sizes, matched them to predicted body weight, and then calculated sole pressure values that varied from between 6 to 9 lb/in2. By comparison, the human foot yields values of about 10 lb/in2 for the contact area of the foot (the typical one-sided hourglass outline of an arched foot on a hard surface) and 5 lb/in2 for the entire area of the sole of the foot. A booted foot has a value of only 2.5 lb/in2. Thus, the estimated plantar pressure values for the sasquatch foot are not too different from those values for human feet (although 4-5 times that of a booted foot in the field). Excesses in plantar pressure are likely compensated for by behavioral adaptations and modifications to the soft tissues of the foot, for example, a more compliant gait, flat feet, and thicker sole pad. Recent studies of human locomotion have revealed that a compliant limb posture alone may reduce stresses by as much as 18 percent. A relatively broader, thicker heel pad has considerably increased fat volume to accommodate increased loads on the foot.

Could random independent hoaxes produce such a well-correlated pattern? Fahrenbach concluded, “I have come to the following conclusion. The histogram that resulted from, for example, the foot length, is indicative of originating from a living population by virtue of its bell shape. If it had been fictitious, you would never have gotten this sort of shape, which is distinctly peaked at 16 inches. Therefore, I must conclude that in all probability there is a living entity that has produced these data—a large primate walking about in the North American

forests . . . Study of this rather overwhelming mass of circumstantial evidence would suggest that scientists should take this matter more seriously and not reject it offhand."

The geographical pattern of distribution of reported encounters with sasquatch or the discovery of footprints holds potential for additional analysis. Recent computer technologies have permitted the development of GIS (geographic information systems), which is used to capture, display, and analyze spatial data information. GIS enables one to envision the geographic aspects of a body of data and receive the results in the form of some kind of map. These various datasets are referred to as coverages and may contain data on soil types, vegetation types, precipitation, wildlife ranges, *etc.*

There has been little attempt to apply this novel GIS approach to the analysis of sasquatch reports. An initial attempt was undertaken by Peter Aniello as a student at the University of Colorado at Denver. Aniello utilized data available through the Bigfoot Field Researchers Organization (BFRO) and established coordinates for 377 encounters within the Cascade Bioregion in Washington, Oregon, and northern California. An objective of his analysis was to determine if any trends in the spatial distribution of these encounters would reflect movement of the sasquatch "population" correlated with human population expansion, especially in the regions of Seattle, Washington, and Portland, Oregon. This assumes that all of the sasquatch in the Pacific Northwest constitute a single population and behave as such, which Aniello acknowledges may or may not be the case. The patchiness of their distribution may contradict this assumption. It should also be recognized that the encounter data are not the result of a systematic survey or transect. They are the accumulated record of intersections between spheres of human and presumed sasquatch activity. Nevertheless, Aniello's analysis produced intriguing results that revealed trends suggesting that as a whole, sasquatch encounters were occurring farther from population centers and at higher elevations.

Aniello concludes, "GIS technology is a valuable tool in wildlife management of known animals. As this study demonstrates, it can also be a valuable tool in tracking movements and characteristics of unknown animals, or cryptozoids, possibly giving clues to these animals' whereabouts and habits. The ability to uncover and analyze hidden spatial patterns in data using GIS is perhaps its greatest strength, and should be an integral part of future sasquatch studies, as the subject gains legitimacy."

STEPPING THROUGH TIME: THE EVIDENCE OF FOOTPRINTS

My research interests revolve around the functional anatomy and evolutionary history of the primate foot as it relates to the otherwise singular human adaptation of walking on two feet, i.e., bipedalism. The skeletal and muscular anatomy of the foot, from primitive mammals and monkeys to great apes and humans, has preoccupied a large part of my professional career. So it was the evidence of the sasquatch footprints that particularly captured my attention. Clearly, *something* is leaving enormous humanlike tracks on the backcountry roads and riverbanks of North America's mountain forests. With the potential for misidentification of bear or human footprints accounted for, the otherwise inexplicable footprints that remain must be either hoaxed or hominoid. In the absence of bones or body, the tracks constitute the most abundant and informative data that can be dealt with by scientific evaluation. These traces left in the ground are for me a sizable chapter in the story behind the sasquatch, and one that is often underappreciated.

For hunter or conservationist, tracks left by animals leave clues about their numbers and behaviors. Renowned wildlife tracker Dr. Jim Halfpenny observed that mammals are among the most elusive animals in the world. Much of what is learned about mammals in the wild comes from the stories that can be read from their tracks and other sign. I spent an afternoon with Halfpenny in his Gardiner, Montana, home just north of Yellowstone National Park, discussing the interpretation and nature of sasquatch tracks. We jointly examined a small selection of sasquatch casts that I had brought along to illustrate the traces of dynamic features I observed—toe movement, midfoot flexibility, pressure ridges, *etc.* These duplicates were subsequently left with Halfpenny to be added

to his remarkably extensive and informative collection of wildlife track casts. He was clearly impressed by the animation evident in the sasquatch track casts, and interested in my inferences about their dynamics, but in the end he seemed to feel that the story told by the tracks did not yet have a definitive conclusion. He was quite willing to give serious consideration to any new track evidence we might recover, and challenged me to put him onto a fresh track. Then he was confident he would get to the bottom of it one way or the other.

A clear example of the sasquatch footprints located by Deputy Sher iff Dennis Heryford in Grays Harbor County, Washington, in 1982 (Courtesy of Dennis Heryford)

Dr. John Bindernagel echoed many of Halfpenny's sentiments and further addressed the significance of sasquatch tracks: "There is so much more evidence for the existence of sasquatch than most people realize. In addition to eyewitness descriptions and drawings, we have hundreds of descriptions, photographs, and plaster casts of the tracks. For me as a wildlife biologist, it's the tracks that we

depend upon for the existence of an animal in a study area. We don't usually see the mammals, but we do see their tracks. In the case of the sasquatch, this is the most compelling evidence we have." Clearly those who have most closely examined the footprints attributed to sasquatch are the least inclined to simply dismiss them offhandedly as hoaxes.

The sometimes-enormous size of the sasquatch tracks gave rise to the common American appellation of "Bigfoot." These footprints average between 15 and 16 inches in length, with a reported range of 4-27 inches. Their superficially humanlike appearance is largely the consequence of the inner big toe being aligned with the remaining toes, whereas an ape's inner toe diverges much like a thumb. The resemblance to human footprints largely stops there, however. In fact, the sasquatch footprints lack the principal distinctive features that set the human foot apart from that of its hominoid cousins. Sasquatch footprints are typically flat with no consistent indication of the true hallmark of the human foot—a fixed longitudinal arch. Additionally, there is little indication of differential weight bearing under a specialized "ball" at the base of the big toe. The sasquatch foot is relatively broader and the sole pad apparently thicker, by comparison to human feet. The heel and toe segments are disproportionately longer.

One example from a series of casts made by Officer Dennis Heryford

The tracks do indicate a bipedal gait, one where sasquatch walks on two feet, long considered a strictly human trait, but now recognized to be widespread among prehuman hominids, and perhaps present even in a much earlier Eurasian great ape called *Oreopithecus*. This latter case has prompted recognition that the evolution of bipedalism is not a singularly human trait, but a manner of moving on the ground that has evolved independently in parallel, multiple times. Indeed, apes display a clear tendency to adopt an upright posture and to walk on two feet from time to time—referred to as *facultative* bipedalism. It appears that more than one species of ape became a full-time biped, or *habitual* biped. This further blunts the criticism of the hypothesis that *Gigantopithecus* was perhaps bipedal, evolving the habit convergently under similar ecological conditions.

The manner of walking on two legs inferred for sasquatch appears quite distinct from the typical mode of modern human walking, which may reflect an independent origin. The succession of sasquatch footprints frequently displays an exceptionally long stride, often with the footprints marshaled one directly in front of the other. Although human footfall patterns exhibit a considerable range of variation, most modern Euro-Americans leave lines of alternating right and

left footprints separated by some distance referred to as a straddle, or step width. Sasquatch footprints generally lack the indications of differential pressure beneath heel and ball as in an arched foot, but instead are rather uniform in depth. Occasionally, the dynamic signature of the foot indicates a more apelike midfoot flexibility. In all, the sasquatch footprint is not merely an enlarged facsimile of a human footprint, but appears to represent a uniquely adapted primate foot associated with a distinctive mode of bipedalism, one that may well have evolved independently although roughly in parallel to hominid bipedalism. What is this exceptional sasquatch foot suited for?

From the shape of the foot a reasonable inference of the skeletal proportions can be made as in this cast from Grays Harbor County, Washington.

As an anatomist and physical anthropologist at Idaho State University, I have examined fossilized hominid footprints from sites as diverse as Hawaii, Turkey, France, and East Africa. Turning my attention to the sasquatch footprints, I now have assembled nearly two hundred casts of sasquatch tracks in my lab, including the addition of the late Dr. Grover Krantz's cast collection. This assemblage has provided a significant opportunity to assess the degree of

consistency as well as the variability present among these footprints. It has also highlighted the occassional hoaxes and misidentifications.

Dr. John Bindernagel was an invited speaker on the subject of sasquatch at the campus of Idaho State University in 2002, and on that occasion he was able to inspect and study the assembled casts housed in my lab. In a subsequent letter to the dean of Arts and Sciences he shared the following sentiment: "The opportunity to spend three days in Jeff Meldrum's lab during this period gave me an opportunity to examine the quality and extent of the material he has assembled. With his permission, I will be directing other scientists to this collection. I can only commend Jeff Meldrum and ISU for addressing this subject in a timely and appropriate manner, showing scientific leadership, which has been sadly lacking up to now in this subject area. Based on the results of my own research I am confident that such leadership will eventually—and perhaps sooner rather than later—be amply repaid as other scientists finally accept our responsibility to address this subject. The ISU collection of track casts requires biologists to explain it, and must figure importantly in upcoming discussions."

As I embarked on a review of this sample of footprints, a number of questions came to mind. Can the repeated appearance of recognizable individuals be demonstrated by the presence of their footprints in a particular region? Are there documented series of footprints that exhibit animation through variation in toe position and/or foot rotation as the living foot supports body weight during a step? Do the footprints exhibit signs of the dynamic interaction of the foot with the soil, such as pressure ridges and tension cracks? Are the footprints simply enlarged human footprints, or are distinctions present in the inferred anatomy that make sense considering the sasquatch's large size and habitat preferences? What can be learned about any underlying consistency and variation from this truly unique sample of footprints?

Roger Patterson displaying two casts of sasquatch tracks (Courtesy of Vance Orchard)

Repeat appearance of a particular individual sasquatch as attested by this series of casts made at the Bluff Creek construction site by Jerry Crew, 1958; Hyampom, by Bob Titmus, 1962; Bluff Creek above Notice Creek, by Roger Patterson, 1964

My first consideration was the repeated appearance of particular individuals. It stands to reason that if these animals are as rare as they must certainly be to have remained so elusive, then when footprints *are* found in a given region over a period of time, chances are they were left by one of a very few local individuals and there should be repeated appearances of recognizable footprints. After all, the five-toed soft-soled footprint of sasquatch would reasonably exhibit

more distinguishing individual characteristics than a hoofed-deer track. This has certainly been borne out by assembling as many specimens of footprints as possible with information about the circumstances of their discovery. A case in point would be the original “Bigfoot” cast made by Jerry Crew at Bluff Creek, California, in 1958. Tracks of that individual with a l6-17-inch footprint were seen a number of times over the subsequent years, including a series of casts made by Bob Titmus and Syl McCoy near Hyampom in 1963, and a pair of tracks cast in the region by Roger Patterson in 1964 at Laird Meadow above Notice Creek, not far from the original Bluff Creek site.

A number of other examples soon became evident as well, including a notable similarity between the 15-inch track from the Blue Creek Mountain Road in 1967 and the casts from the Patterson-Gimlin film site. Investigators at the time felt that the casts Roger made were different from the 15-inch track that had been seen on a number of occasions. This impression may have resulted from the difference in nature of the substrate that the tracks had been observed in, ranging from firm moist sand to powdery dust on a hardpan logging road. A careful comparison reveals a high degree of congruence. Carefully outlining and superimposing scaled images of the prints and casts can readily visualize this resemblance. The implication is that the subject of the Patterson-Gimlin film also left tracks on the Blue Creek Mountain Road a month earlier. In fact this individual appears to have left footprints in the region on a number of occasions.

Another example includes several casts and photographs of footprints that appeared to be from the same individual that left the tracks I observed in 1996 in the foothills of the Blue Mountains in southeastern Washington. In Krantz’s collection was a copy of a cast made in northern Oregon, about twenty miles south of the location of my footprint site. Two local anglers happened upon a string of five 14.5-inch footprints along the stream bank in a densely timbered area seldom frequented. One footprint was impressed an inch deep in mud and was quite distinct. The others were in grass and retained less detail. A matted down area in the ferns indicated a large animal had lain there and a nearby 3-5-inch yew was snapped off four feet above the ground. They mentioned their find to the proprietor of a local store. Although incredulous, she and her husband went out to have a look for themselves. Their dog, a dingo-shepherd cross, acted terrified by something in the area. They photographed the print, covered it, and returned later to make a cast. The original is on display in their establishment and I have had the opportunity to examine it carefully and later add a duplicate to my collection. It corresponds very closely in size and proportions to the casts I made near Walla Walla, down to the unusual feature of the long second and third

toes. It also displays midfoot flexibility about a transverse axis.

On the left is a footprint from the Blue Creek Mountain Road trackway in 1967; in the center is a cast made by Roger Patterson at the film site just over a month later; on the right are the superimposed scaled outlines of the footprint and cast, suggesting they were made by the same individual.

15-inch casts by Bob Titmus from Bluff Creek in 1958 (left) and the Patterson-Gimlin film site in 1967 (right)

As an interesting aside, the Forest Service was contacted by phone and informed of the tracks. They simply laughed and asked what the witnesses had

been drinking. They declined to investigate. However, a few minutes later one of the personnel from the office called the witnesses back and quietly asked if he might be shown the tracks and be permitted to photograph them. It turned out that some interested individuals in the office maintained an unofficial file of reports of tracks and sightings that occurred rather regularly in the region.

Footprint and cast made near Tollgate, Oregon, 1986 (Courtesy of Lorretta Nietch)

Ultimately, one could argue that repeated appearances might more simply be explained as repeated hoaxes by a persistent prankster, who periodically trots out a single pair of fake feet and lays down some bogus tracks, even if this involves widely separated and out of the way locations. This simplistic suggestion has some merit since there certainly have been instances where hoaxes have been exposed. These relatively rare instances are usually transparent, which brings us to the next factor—animation. A line of footprints made with artificial feet appears quite unnaturally monotonous to the experienced eye. There is minimal variation from one footprint to the next. Toe position is unvaried, mud cannot squeeze between joined carved toes. The intrinsic alignment of foot segments is constant, devoid of the signs of flexibile linkage present in a living foot, allowing it to dynamically interact with the ground under varying conditions of the soil and speed of walking.



14-inch footprint cast by the author at Five Points, outside of Walla Walla, Washington

The primate foot skeleton is composed of twenty-six individual bones, with nearly as many joints. These joints, especially those of the tarsus, the bones at the ankle end of the foot, have multiple axes of rotation defining their interrelated movements. This complexity permits the foot to conform to the inclined and uneven surface of the ground as the animal transmits weight through a step and moves over its environment. However, the skeleton is a linked system, and the shape of joints and the presence of ligaments functionally limit the potential movements of the elements of the foot relative to one another. In other words, there is a limited range of coordinated configurations that can be adopted by the living foot skeleton. For example, the axis of the foot may exhibit different extents of rotation, i.e., pronation or supination, which raises or lowers the inner edge of the foot as it twists about its long axis. Other signs of animation include variation in toe position, with differential degrees of flexion/extension and splaying. Such features of animation provide important clues about the form and function of the foot.

It is crucial to realize that the footprint is not simply a static mold of the foot, but rather a record of the transient dynamic interaction of the foot with the

ground. In addition to the impressed shape of the individual parts of the foot, the forceful transmission of weight throughout the course of the step may produce characteristic distortions of the surrounding soil, such as tension cracks or pressure ridges that are quite distinct from the impact features of a weighted prosthetic or artificial foot. Likewise, distortions of elements of the foot can result from slide-ins or drag-outs, varying depth of impression, or by the expansion of the soft-tissue sole pad under weight.



A halftrack imprint and cast by the author at Five Points, outside of Walla Walla, Washington, and interpretation of the foot action that produced it

Returning to the clear footprints I observed in a muddy road in the Blue Mountains of southeastern Washington, in addition to the evident animation, one of the most significant aspects was the indication of pronounced flexibility in the midfoot. In several instances, the heel had left no impression in the ground, presumably elevated in the air as when a sprinter runs on the ball of the foot. However, lacking a fixed arch, the sasquatch foot would flex much as an ape's foot flexes at the midfoot, specifically, at the midtarsal joint. Thus, only the forefoot, distal to the midtarsal joint would leave an imprint.

A 14inch footprint cast by the author alongside a halftrack

I commenced looking for additional examples of this expression of midfoot flexibility, and a number of further instances of similar “halftracks” have been subsequently indentified. One of these was documented by a set of photographs taken by Don Abbott, an archaeologist from the British Columbia Royal Museum, in 1967. These 15-inch footprints were part of an extensive trackway comprising over a thousand footprints along the Blue Creek Mountain Road in northern California and were examined thoroughly by John Green and Rene Dahinden, sasquatch investigators also from Canada. There were several photos of clear complete footprints, but one photo showed an abbreviated footprint, missing a heel imprint. The photos included a tape measure for scale and each was taken from approximately the same distance and angle. It was a simple matter to project, trace, and superimpose the outlines of the footprints to demonstrate that the relative position of the proximal edge of the abbreviated footprint appeared very similar to the halftracks I had examined in the Blue Mountains of southeastern Washington.



Series of 15-inch footprints examined on the Blue Creek Mountain Road, northern California. The upper pair are complete footprints, while the lower is a halftrack. Notice the point of midfoot flexion revealed by superimposing the outlines of the prints. (Courtesy of John Green)

Another striking example came from the west coast of Washington, in the eastern part of Grays Harbor County. Deputy Sheriff Dennis Heryford was one of several officers investigating footprints discovered near a spot called “Abbot Hill” in 1982. Two clear full-length tracks had been found on a muddy logging spur at the end of a trail through the salmonberries created by something very large. More tracks were found about a quarter mile along the spur. These had a nine-foot step and showed only the imprint of the forefoot. The tracks were exceptionally distinct in the mud. What appear to be pathologies of the head and base of the fifth metatarsal are evident along the outer edge of the cast of the complete foot. The cast of the halftrack is truncated at a point that likewise approximates the inferred position of the midtarsal joint, the transverse line of flexion in the midfoot.



Casts made by Deputy Sheriff Dennis Heryford in Grays Harbor County, Washington. The cast on the right is another example of a halftrack. Superimposition of the two outlines reveals the point of midfoot flexibility.

Even more examples have been identified. Perhaps the most intriguing case in point is present in the Patterson-Gimlin film. The film subject potentially affords a remarkable view of the plantar surface of the sasquatch foot, as well as an unobstructed perspective on several step cycles. In addition to a prominent elongated heel, a midtarsal flexibility is evident during the stance phase of gait, and considerable flexibility can be observed in the midfoot during the swing phase. A long line of deeply impressed footprints was left in the loamy sandbar at the film site. Patterson cast single examples of right and left feet. He selected the clearest, flattest, least distorted examples to be found. The casts are actually excellent representations of the anatomy of the static foot, but display little by way of dynamic features, nor does the single pair convey an obvious sense of animation that might be evident in a sequence of footprints. As a result, they made relatively little impact on the experts of the time, who regarded them as likely made by flat, carved fake feet.

Fortunately, Gimlin had covered a number of the footprints with slabs of

bark pulled from the dead snags piled on the sandbar, shielding them from the rains that came during the following morning. Patterson and Gimlin didn't return to the site again, but two days later, on the following Monday, a Forest Service timber cruiser, Lyle Laverty, and his crew of seasonal employees visited the site. They had been camped near the junction of Notice Creek and Bluff Creek since early summer, preparing timber sales in the region. On the weekend following the filming, they were in town in Orleans and heard about the incident. On Monday they drove up to the site to have a look for themselves. They observed the footprints, and Laverty took some pictures of the most distinct prints. The dimpling effects of the rainfall can be seen in the photographs. Laverty followed the tracks along the sandbar for several hundred feet. Things seemed to be as Patterson and Gimlin have since described them. In contrast to Patterson's casts, Laverty's pictures depict examples of very dynamic footprints with features such as distinctive pressure ridges and discs in the midtarsal region. One photographed footprint in particular clearly exhibits a pronounced pressure ridge across the midfoot. These pictures proved to be extremely informative.



Photographs of footprints at the Patterson-Gimlin film site illustrating dynamic features. Note especially the pressure ridge particularly evident in the upper left footprint, subsequently among those cast by Bob Titmus. (Courtesy of Lyle Laverty)

Sequence of stills from the Patterson-Gimlin film exhibiting midtarsal flexion in the foot at push-off (Courtesy of Martin and Eric Dahinden)



Contrast between the inferred midtarsal break in the sasquatch foot and the longitudinal arch of the human foot. Note the position of the resuiting pressure ridge. Also notice the elongation of the sasquatch heel.

Nine days after the filming, Bob Titmus, the taxidermist mentioned earlier in connection with the Bluff Creek incidents in 1958, then in 1967 a Canadian resident, arrived at the site. He came prepared to cast the footprints, which were still clearly impressed in the sandbar, relatively protected by the bark, although the effects of the rain had left its mark before Gimlin was able to get them covered. In all, ten successive footprints were cast, providing a distinctly unique record of the potential variation present in a single sasquatch trackway. I have examined the original casts myself, and they are now accessioned at the Willow Creek-China Flat Museum collection. High quality silastic rubber molds of eight of the ten original casts, prepared by Grover Krantz, are now curated in the special collections of the Smithsonian. Animation of the foot is quite evident in

this series of footprints. Three of the ten casts are of the very footprints photographed earlier by Laverty, providing exceptional corroborative documentation of these significant data.

A human footprint in moist sand often leaves a pressure discjust behind the ball of the foot.



The left foot skeleton of a human foot (left) and a chimpanzee (right) indicating the position of the tarsal or transversetarsal joints (arrows). Cu = cuboid, Ca = calcaneus, Na = navicular, Ta = talus

What accounts for the distinctive halftracks and pronounced pressure ridge that so distinguishes these tracks from human footprints? It is the flexible midfoot characteristic of the hominoid, or ape, foot. An ape's foot lacks a fixed longitudinal arch, and the joints at and below the ankle permit a greater range of motion than present in the human foot. The reconstructed sasquatch foot also lacks a fixed arch, as indicated by the clearest examples cast by Patterson

himself, which are quite flat but certainly not featureless. In fact, the outline of the navicular can be readily identified on the inner side of the foot, just as it is evident in an ape footprint, or a very flat human footprint. In the typical human foot this bone is elevated in the apex of the arch, unless the foot is significantly pronated, or rolled inward. In contrast, the sasquatch foot retains the primitive apelike characteristic of a flat flexible midfoot. The range of motion permitted by the calcaneocuboid and talonavicular joints allows the heel to function in leverage and propulsion somewhat independently of the relatively prehensile function of the forefoot. In primates this coordinated flexion between the two segments of the foot is referred to as the "midtarsal break."

To appreciate the significance of this feature we must turn to the generalized ape foot. In the grasping foot of the ape, the great toe, or hallux, functions in opposition to the relatively long lateral digits in a pincer-like grip. This foot posture is especially evident when the ape is climbing on vertical or inclined tree trunks or branches—an ape specialization. The forefoot functions as a prehensile or grasping organ, maintaining a secure grip with its divergent big toe, while the hind foot provides leverage. The plantarflexors of the ankle elevate the heel as the power arm of a lever with its fulcrum at the midtarsal, or transverse tarsal joint.

14-inch footprints in the foothills of the Blue Mountains of southeastern Washington. Note the pressure ridge. (Courtesy of Vance Orchard)

The midtarsal break is also evident in the chimpanzee foot when it is walking on the ground. In studies of the pressures beneath the chimp foot, lifting the heel shifts the center of weight ahead of the midtarsal joint, especially beneath the cuboid bone. Generally the entire midfoot bears the weight rather than concentrating it under a specialized ball of the foot. A similar pattern of weight distribution is implied by the dynamics of some examples of sasquatch footprints. The deepest part of the imprint lies just anterior to the midtarsal joint. If the ground is plastic enough, it may be pushed up behind the midfoot following the midtarsal break, creating a pressure ridge. I have identified repeated and geographically widespread instances of these pressure ridges in sasquatch footprints.

This midfoot flexibility also explains the relatively elongated heel attributed to the sasquatch foot. Critics of the Patterson-Gimlin film took exception to a protruding heel that suggested to them oversized fake feet worn by a “man in a fur suit.” One skeptic went so far as to assert that the Achilles tendon appeared to attach far forward on the heel in an unnatural fashion, negating any mechanical advantage afforded by the elongated heel. These explanations are simply based on erroneous interpretations of the appearance of the subject or blatant ignorance of foot mechanics, and they can hardly account for the dynamic actions and appearance of the feet evident in the film and the associated tracks.



Two 14-inch footprints examined by the author in the foothills of the Blue Mountains of southeastern Washington in February 1996 displaying midtarsal pressure ridges

Another interpretation based on sound principles of biomechanics would be that a means of increasing foot leverage needed by a bipedal animal with the large body weight of a sasquatch would be to increase the relative length of the heel. This trend is well documented in other apes of increasing body weight, from gibbons to gorillas. Indeed, if a series from chimp to lowland gorilla to the more terrestrial mountain gorilla, then on to sasquatch is considered, it can be seen that the sasquatch foot is a natural extension of the trends accompanying increased size and terrestriality, i.e., elongated and broadened heel, greater alignment of the great toe, and shortening of the remaining digits. Early hominids appear to have applied these principles prior to a stabilization and refinement of the longitudinal arch and associated adapatations to modern human walking and running. Once the transition to a fixed arch was made,

humans modified the strategy significantly. Rather than lengthening the heel further, leverage was increased by shifting the pivot point, or fulcrum, from the midtarsus to the ball of the foot, and incorporating the midfoot segment into the power arm of the lever. Then the trend for heel elongation reversed itself in parallel with mechanical adaptations evident in other cursorial or running mammals.



A series of feet—(left to right) chimpanzee, lowland gorilla, mountain gorilla, sasquatch—illustrating a trend for relatively shortened toes, aligned great toe, and elongated and broadened heel

The heel of modern humans became shorter to increase the speed ratio of the foot lever system, as endurance running became a primary human locomotor adaptation.

In the proposed sasquatch foot with an elongated heel, the gap between the Achilles tendon and the tibia, or shinbone, is wider. When the tendon is comparatively relaxed during the swing phase of gait, the heel appears to protrude in a nonhuman fashion. It was from a single poorly redrawn film frame depicting this situation that the misplaced attachment of the calcaneal tendon was inferred by the critic of the Patterson-Gimlin film subject. When the calf muscles are contracting and the tendon is taut during the stance phase, it obviously inserts on the proximal end of the calcaneus, and the heel no longer seems to protrude and the ankle appears unhumanly thick. In this regard the appearance of the Patterson-Gimlin film subject's heel is consistent not only with the dynamic signature of the accompanying footprints, but also with the biomechanical expectations for a foot supporting a giant bipedal ape, not to mention the observable action of appropriate muscles at key points in the step cycle.

An example of a sasquatch footprint exhibiting an apparent deformity may serve to highlight these distinctions of skeletal anatomy. These tracks were

discovered near Bossburg, Washington, in 1969. The shenanigans that ensued from the incident have cast a pall of suspicion over the tracks. Kenneth Wylie, author and naturalist, alleged that it was confessed resident faker Ray Pickens who was responsible for the Bossburg tracks. Pickens appeared on television displaying his wares, an oversized pair of carved wooden fake feet attached to work boots. The devices were on par with the crude creations whittled by Rant Mullens. Furthermore, by his own public admission, Pickens's initial escapade with his concocted feet came long after the cripple foot tracks were originally discovered at Bossburg in December of 1969. He told reporters he first made his carved feet in February 1971.

Still from a television news report in which Ray pickens displayed a false foot he used to hoax footprints.

In spite of the high jinks, the Bossburg tracks remain a remarkable set of footprints deserving of consideration on their own merits. Two interested scientists, John Napier and Grover Krantz (not to mention a number of orthopedists and podiatrists that I have conferred with) took the footprints quite seriously. The malformed right foot caused Napier to reflect, "It is very difficult to conceive of a hoaxer so subtle, so knowledgable—and so sick—who would deliberately fake a footprint of this nature. I suppose it is possible, but it is so unlikely that I am prepared to discount it." Napier examined only a very limited sample of footprint casts and photos, including the Bossburg casts. On this basis he inferred two distinct types of footprints, which he referred to as the "hourglass" and the "human" types. The hourglass type was distinguished by the waisted appearance of the shank of the foot. They also displayed toes that were more equal in size, separated from the sole by a ridge of soil. Napier made a

further point about an observation that the heel impresses more deeply on the outer edge of the heel, the gait is pigeon-toed and the oblique alignment of the toes indicates a push off from the outer side of the foot. Although impressed by both types, he found it implausible that there were two varieties of Bigfoot and eventually cast doubt upon, then rejected the hourglass type. It appears that the principal example of the human type was the footprints from Bossburg. Since this assessment has been cited in support of the contention that the Bossburg tracks are merely enlarged facsimilies of a malformed human foot copied from an orthopedics textbook, it is worthwhile to examine Napier's criteria more closely.



Paired casts of the "crippled" sasquatch at Bossburg, Washington. The author has inferred the skeletal proportions (differing somewhat from the reconstruction of Krantz).

First of all, Napier placed a great deal of significance on the relative size of the great toe. He provided a table of values for the big toe width index [(big toe width × 100)/combined width of all toes] for a sample that comprised a mere seven sasquatch casts and six humans (all measurements derived from photographs of footprints). The Bossburg big toe index was reported as 35.7, compared to average values of 23.3 (range of 18.2-28.7) for the five remaining hourglass types, and 32.8 (range of 31.1-36.5) for the human type. In an attempt to replicate Napier's measurements for the Bossburg footprint casts I arrived at an index value of 25, well within the hourglass type's range and outside that for human footprints. The confusion may have ensued from the degree of splaying of the toes, or from the ambiguity in the boundary between the first and second toe in the particular Bossburg cast Napier was examining. If one allows for the appropriate width of the second toe, assuming it is minimally as wide as the third

toe, then the big toe is smaller than inferred by Napier. This is borne out by reference to the malformed foot. The lateral toes are misshapen and apparently enlarged, but the great toe seems unaffected. It seems unlikely that it would become smaller in width, while the lateral toes were hypertrophied. In fact its width is a good match for the inferred width of the big toe on the opposite foot. Hence the principal criterion for the classification of the Bossburg tracts as *human type* cannot be supported.

The remaining distinctions have more to do with the nature of the substrate in which the footprint was left, than with the feet themselves. In a thin veneer of dust on a hardpacked logging road, a gap is more evident between the toe pads and the sole than when the same foot leaves a deeper imprint in soft soil. The same gap is suggested by a wet human footprint on an unyielding cement surface. This is exaggerated by the relatively longer toes apparent in the sasquatch footprints. When they are curled in flexion the ridge is more pronounced. The toes of the Bossburg tracks are flexed to a considerably lesser degree than the examples cited as hourglass types. They are also aligned obliquely, similar to the hourglass type, and indeed the shank of the foot is waisted, flaring to a broad heel (which Napier inaccurately rendered in outline in his figure). There is no contradiction between the sasquatch footprints, no distinction into two types. The Bossburg tracks do not conform to a human pattern, but are as distinct from human footprints as any of Napier's hourglass types.

Krantz examined the "cripple foot" tracks in the ground firsthand and they embodied for him the first convincing evidence for the reality of sasquatch. The deformity exhibits an anatomy consistent with the general condition referred to as *pes cavus*, specifically a type of skewfoot. Its unilateral manifestation is suggestive that it resulted from a spinal cord lesion, rather than a congenital deformity. Regardless of the epidemiology, from the pathology Krantz inferred the position of the joints disposed on the outside edge of the foot. He considered the protrusions presumably caused by hypertrophied connective tissue to be associated with the deranged joints proximal and distal to the cuboid bone. These prominent bunionettes on the outside margin of the foot, resulting from the inward twisting of the forefoot, are positioned more distally than would be the case in a human foot suffering from a similar condition, but are in accord with the proportions of an elongated heel segment and the position of the midtarsal joint as inferred from the pressure ridges and halftracks already examined. The resulting skeletal proportions and joint positions are remarkably consistent with the model of sasquatch foot morphology suggested here based on

independent examples of footprints.

Skeptics have argued that Krantz's reconstruction does not hold up because the ankle joint, the tibiotalar joint, does not contact the ground and therefore cannot be inferred from a footprint. They argue further that no skeletal feature can be inferred from the impression of soft tissue and that the protrusions on the lateral side of the cripple foot could be interpreted in any number of ways. Such comments expose a lack of understanding of the correlated nature of foot anatomy and no appreciation for the features discernable in footprints. Krantz's placement of the tibiotalar joint was based not only on the cripple foot casts, but derives from his observations of the Patterson-Gimlin film subject as well. The film subject displayed ankles that were quite thick from front to back. The placement of the tibia, or shinbone, is just beneath the skin at the front border of the leg. Therefore reasonable placement of its long axis is evident, even allowing for body hair. Furthermore, the relationship of the talus to the anterior calcaneus is quite consistent, excepting highly specialized leapers such as tarsiers. The notable variation comes in the relative length of the calcaneal tuberosity, i.e., the proximal length of the heel. This elongated heel, to which is attached the Achilles tendon, is what lends the ankle its apparent thickness in the film subject. The fact that the relative length of the calcaneus, attested to by its appearance in the film subject, corresponds so closely with the relative placement of the proximal bunionette in the cripple foot, seems too fine a point to be sheer coincidence, especially when it correlates with the multiple independent examples of midfoot flexibility, midfoot pressure ridges, and halftracks.

The allegation that no skeletal feature can be inferred from the impression of soft tissue can be readily refuted. I sampled a set of weight-bearing footprints from a large and diverse class of university students (a sample of more than fifty students). Their soles were dusted with fingerprint powder, after which they stepped onto a strip of lifting tape, which was then applied to card stock. In the majority of these, the prominence of the tuberosity of the fifth metatarsal was evident as a convexity on the lateral edge of the foot. Proximal to it lies the cuboid, from which the position of the calcaneocuboid joint can be approximated. In those fewer individuals with flat pronated feet, the tuberosity of the navicular was evident as a convexity on the medial side of the foot. The talonavicular joint is just proximal to it. With this information it is a simple matter to approximate the position of the transverse tarsal joint from the footprint. The positions of the heads of the first and fifth metatarsals are indicated by the widest breadth across the forefoot immediately proximal to the

toes. Flexion creases on the toes correspond in typical fashion with the interphalangeal joints. The development of the apical pads of the digits can also imply aspects of toe proportion. In reality, a great deal about the foot skeleton *can* be deduced from the features of a footprint.

Two casts from southeastern Washington exhibiting obviously long toes. On the left, a cast made by Wes Sumerlin near Indian Springs in 1988; on the right, a cast made by Paul Freeman south of the Mill Creek Watershed in 1987. The casts represent the same individual.

Deformities and misalignments of the toes also permit inferences to be drawn about the positions of joints and thereby the relative toe lengths. Together with other examples of pronounced toe mobility as evidenced in the variability of toe position from footprint to footprint, they indicate that the sasquatch toes are relatively longer and more mobile than human toes, even those of individuals with feet not usually confined in shoes. In some instances the footprint indicates long toes that are sharply curled in a flexed posture, leaving an undisturbed ridge of soil behind the toe pads. Gripping in this fashion the toes are also adducted, or pressed in against each other, side-to-side. This packed position may contribute to the squarish appearance of the toes. With only the toe tips in contact with the ground they look much like “peas in a pod,” as noted by Napier. In other instances the toes are fully extended and give a truer impression of their absolute lengths and proportions. In this position, they are sometimes abducted, or splayed apart from each other, occasionally with mud extruded through the gaps between the toes. Examining one’s own fingers can provide a dramatic illustration of these contrasting situations. When extended, the fingers are rather disparate in length and apparent size, but curl them toward the palm and suddenly they appear nearly equal in length with rather uniform tips lined up like

peas in a pod.

Profile of the fifth toe of the halftrack cast by the author outside of Walla Walla, Washington, in 1996



Comparison of the relative mean toe length (third digit) in a sample of hominoids. The combined length of the tarsus and the third metatarsal is standardized to a single unit, and the values to the right express the length of the toe as a percentage of the unit length. Note that the sasquatch are approximately intermediate to those of modern humans and an early bipedal hominid (modified from Tim White and Gen Suwa).

Among the casts that I made in 1996 in southeastern Washington was one in which the toes had deeply impressed in the soft mud and the first and fifth digits splayed against the sidewall of the track. The result was a side profile of these flexed marginal toes, the first instance of such that I am aware of. The least toe on these nearly 14-inch tracks is over 3 inches long. In other words, the toes of this sasquatch foot would conceivably have as much prehensile, or grasping ability as a human hand (excluding the opposition of the thumb). Given the greater muscle mass of the lower leg of the sasquatch, the grip strength of the

toes would be many times that of a man's fingers. Expressed as a percentage of the combined lengths of the hindfoot and midfoot, the sasquatch toes are intermediate in relative length between those of a human and an early bipedal hominid, *Australopithecus afarensis*. Allowing for the relative elongation of the hind foot segment of the much larger sasquatch, the toe percentage is actually much closer to the early hominid value.

The issue of toe length is related to another occasional feature that has drawn comment, and was noted by Napier as a feature of his "hourglass" type. This is the apparent "split ball" that was particularly evident in a couple of examples of footprints in northern California and was grossly exaggerated in the fake feet carved by Ray Wallace. Rather than being a hallmark of the sasquatch foot, as mistakenly asserted by some, only a limited number of individuals exhibited this feature to a pronounced degree—the 15-inch and 13-inch tracks found on the Blue Creek Mountain Road in 1967, and to a much lesser degree the original 17-inch individual. Dr. Grover Krantz had concluded that assuming the sasquatch midfoot skeleton was comparable to a human's, the tremendous weight of the sasquatch would dictate toes and metatarsals relatively shorter than a human's. In a flat foot, both the proximal as well as the distal ends of the hallucial metatarsal would be pressed to the ground, creating a second ball around the proximal joint of that bone, hence a split or "double ball." However, examination of numerous casts produced only rare additional examples of the double ball feature, but presented many examples of long splayed toes. The resolution to this apparent contradiction came one evening while I was indulging my wife with a foot massage as we watched a late movie together. My wife has very flexible toes, which she can actually curl beneath her foot, resting upon the back of the toe "knuckles" when she is sitting, a trait she has passed along to most of our boys. She also has a relatively thick sole pad, which extends nearly to the first interphalangeal joint, giving her toes a quite stubby appearance when viewed from below, i.e., from the perspective of a footprint. As I massaged her foot, I rubbed my palm over the tops of her toes, pressing them into flexion. As I did, a distinct crease appeared across the ball of her foot that extended nearly its full width. This flexion crease corresponded to the position of the metatarsalphalangeal joint around which the ball of the foot is situated. The same relationship can be more handily observed by flexing one's fingers as when waving "bye-bye." The action emphasizes a crease running across the palm that corresponds to the position of the proximal knuckle joints. The same action applied to my foot produced no obvious crease, as my sole pad is much thinner and does not extend as far beyond the bases of my toes as my wife's, nor

do my toes exhibit a comparable range of flexion.

Even the tracks from the Patterson-Gimlin film site, which are often described as showing stubby toes, actually indicate relatively long toes, obscured by an extension of the sole pad as indicated in this inferred reconstruction.

In fact, all humans are born with a flexion crease across the ball of their foot, as can be readily confirmed by referring to the inked footprint on one's birth certificate. As development of the foot continues and the ball of the foot fills out and forms more fully, the crease is generally lost. It may persist to varying degrees in persons with hypermobile flat feet, however. The presence of a split ball to varying degrees in selected sasquatch tracks indicates a thick extensive sole pad in those particular individuals, which bunches up when the long toes are sharply flexed. In reconstructing the skeletal proportions of the footprint from the Patterson-Gimlin film site, I placed the metatarsalphalangeal joints as indicated by the faint flexion crease. This produced toes of a length generally consistent with other sasquatch tracks in which the toes only appeared to be much longer. Recent enhancements of the Patterson-Gimlin film, using digital color-channel separation technologies, have provided never-before-seen clarity of detail of the film subject's anatomy. I was especially intrigued by a stabilized sequence of frames that provided a view of the dorsiflexion of the toes near the end of the swing phase of a step. The toes briefly angle upward just before the foot makes contact with the ground. They are noticably long and exhibit an excellent proportional match to the reconstructed lengths inferred from the

plantar flexion crease. I have likewise redrawn the skeletal proportions of the Bossburg cripple foot to reflect the longer toe proportions, which produces better agreement with the soft tissue anatomy evident in those footprint casts. Details of the longer toes were confirmed, corroborating my revised reconstruction, when I was afforded the opportunity to examine and photograph the *original* casts, courtesy of Chris Murphy. Therefore, the "split ball" feature appears to have been a rather restricted regional idiosyncrasy that is not characteristic of sasquatch tracks generally, yet is a consistent expression of the expected variation within the hominid-based model of the sasquatch foot.

The overall dynamic signature of the sasquatch footprints concurs with numerous eyewitness accounts noting the smoothness of gait exhibited by the sasquatch. For example, one witness observed, "It seemed to glide or float as it moved." Absent is the head-bobbing or vertical oscillation characteristic of the stiff-legged human gait. The compliant gait on flexed knees and hips not only reduces the peak impact forces under the feet, but also avoids the focused concentration of pressure under the heel and ball of the foot. Recall that these pressures would be disproportionate in a sasquatchsized biped. Instead, the broad foot is placed flat on the ground, distributing weight more evenly across a large surface area and throughout a thick sole pad. The compliant gait also increases the period of double support, when weight is borne over both feet, simultaneously reducing the duration that an individual foot must bear the brunt of total body weight.

By contrast, human walking is characterized by an extended stiff-legged striding gait with distinct heel-strike and toe-off phases. Upward bending of the toes, placing elevated bending stresses on them, marks the end of the stance phase. Double support is minimized in order to maximize step length, resulting in the push-off coming more from the toes rather than from the forefoot. These bending stresses exerted on the toes are reduced by selection for relatively shorter straighter toes that participate in traction and propulsion at the sacrifice of prehensile capacities. Efficiency and economy of muscle action during endurance walking and running are maximized by reduced mobility in the ankle and hindfoot joints, limiting movements toward simple flexion and extension, a fixed longitudinal arch, which provides a stable platform of support and increased leverage, and elongation of the Achilles tendon for speed of flexion and elastic storage of kinetic energy.

These distinctive qualities of modern human walking may have been relatively recent evolutionary innovations. After the initial transition to habitual bipedalism, perhaps as early as 7 million years ago, the hominoid grasp-climb

adaptation of the foot was compromised by moderate shortening of the lateral toes and reduction in the range of abduction, or divergence, of the medial toe, the hallux. The first direct evidence of early hominid bipedalism came with the discovery of fossilized footprints in petrified volcanic ash beds 3.7 million years ago at the site of Laetoli, in East Africa. The Laetoli footprints exhibit these modifications to the prehensile portion of the foot to an intermediate degree. The big toe is considerably aligned with the remaining toes, but all are comparatively long.

Cast of a 3.7-million-year-old Laetoli footprint of an early bipedal hominid; exhibiting a pressure ridge (arrow), a product of midfoot flexibility

There has been continuing debate over the extent to which the Laetoli hominids display modern human foot morphology. Some have argued that the footprints imply a foot essentially modern in all aspects, while others have pointed out features that indicate retention of more apelike characteristics of the foot. I first drew attention to what might be a midtarsal pressure ridge evident in

a number of the fossil footprints, which suggested the retention of midfoot flexibility. This is remarkably reminiscent of the comparable feature in the sasquatch tracks. In a depiction of a reconstruction of the *A. afarensis* foot skeleton superimposed upon a Laetoli footprint, this feature can be seen to lie immediately proximal to the position of the reconstructed midtarsal joint. Some have suggested this feature is possibly the result of termite burrowing or an excavation artifact; however, the repeated and consistent position of the feature, combined with other ridge indications within the footprints of a transverse axis of foot flexion, indicate its interpretation as a pressure ridge is justified.

An exceptional example of a midtarsal pressure release is evident in a particularly well-preserved Laetoli footprint (Gl-26), indicated by plastic flow of the wet ash pushed up behind the midtarsus. Careful examination of this feature excludes the possibility of it resulting from exfoliation of successive layers of ash or other excavation artifact. The leading edge of the flow is continuously rounded and unbroken, and has the same appearance as the ash extrusion between the first and second toes of another very clear print (Gl-36).

Fossilized footprint of an 400,000-year-old hominid found in the south of France at the site of Terra Amata (Courtesy of Charles DeLumley)

Recent analyses of fossil hominid foot skeletons also indicate midfoot flexibility in australopithecine, and perhaps early *Homo* feet. At some point thereafter, in the evolution of modern human foot morphology, changes occurred

to stabilize the foot platform, increase mechanical advantage of ankle flexors, and improve efficiency and economy in long distance, endurance walking and running. Determining the timing and pattern of the evolution of these characteristics has remained a challenge due to the paucity of fossilized footprints or foot skeletons from the period spanning 2.0-0.5 mya. Two potentially critical specimens have remained largely unpublished. The first of these is the footprint at the Terra Amata site, in southern France. The site dates to approximately 400,000 years ago. The single published photo of this footprint suggests a midtarsal pressure ridge and a lack of a well-developed longitudinal arch, as well as the lack of a differentiated ball. This seems to agree with the observation that a single metatarsal of the big toe attributed to *Homo erectus* is remarkable in its lack of robustness. The gracile proportions of the bone combined with its distal joint morphology suggest it was part of a foot that lacked a well-developed ball. The footprint also appears relatively long for its breadth. This and relative position of the apparent pressure ridge suggests a degree of heel elongation. This would increase the leverage of the ankle flexors in response to dramatically increased body mass in *Homo erectus* over previous hominids. Although not as significant as the proposed gigantism in sasquatch, the parallel in biomechanical response is very suggestive.

The second specimen of interest is the nearly complete foot skeleton of the Jinniushan hominid from a site in China dating to just less than 200,000 years ago. A photograph of the skeleton has appeared in a popular Chinese magazine, but detailed descriptions or analyses of the foot skeleton have yet to be published. Features of the foot skeleton visible in the magazine photo suggest that stabilization of the transverse tarsal joint had occurred by that time. Specifically, the shapes of the joints of the midtarsus reveal that they could lock in a stable position to support a longitudinal arch. Also the bones of the big toe are large and thick, indicating the importance of toeing-off in this species. Interestingly, it appears that the heel remains relatively elongated.

Therefore, based on this admittedly limited assessment, it emerges that the transition to the modern foot form, characterized foremost by the longitudinal arch and well-developed ball and big toe, may have occurred only as recently as less than 200,000 years ago. In that case, it should now be recognized that the majority of the history of hominid bipedalism reveals a sustained and apparently successful strategy of locomoting bipedally on flat flexible feet. Modern human foot morphology was perhaps a surprisingly recent evolutionary innovation. The stabilization of the midfoot and associated modifications, especially to the distal foot, i.e., shortening of the toes, enlargement of the big toe, development of the

ball, as well as shortening of the heel, were relatively recent innovations that marked a shift in hominid locomotor adaptation to a lighter skeleton combined with endurance walking and running.

The sasquatch appear to have adapted to bipedal locomotion by employing a compliant gait on flat flexible feet. A significant degree of prehension has been preserved in the toes by retaining the uncoupling of the propulsive function of the hind foot from the forefoot by means of the midtarsal break. The toes are spared the peak bending forces experienced by human toes at toe-off by means of the compliant gait with its extended period of double support (the interval of a gait during which both limbs are in contact with ground and support body weight) and push-off from the front half of the foot. All in all, this would be an efficient strategy for a giant terrestrial bipedal ape. In fact, it is an extension, most likely in parallel, to the very strategy that marked the mode of bipedalism used by early hominids. The sasquatch foot and footprints exhibit intriguing parallels to the morphology of the hominid foot, maintaining aspects of the longstanding bipedal hominid strategy, while modifying it, e.g., increased breadth and further lengthening of heel, to accommodate its gigantic body proportions.

The inferred architecture of the sasquatch foot is not only well documented, but seems well suited to the physical aspects of the terrain of its purported range. The retention of somewhat prehensile toes, combined with increased leverage of the heel, give it an advantage negotiating the steep and uneven mountainous forest landscapes of North America. The locomotor adaptation of an organism is a major element in defining its niche. The conformity of the inferred sasquatch locomotion to an overall hominoid/early hominid framework, and the anatomical distinctions correlated to its environmental specializations are plausible and compelling arguments for a real animal. Could such coherence of form and function emerge from an unrelated series of spurious counterfeits?

Demo version limitation

SPLITTING HAIRS AND MOLECULES: DNA AND PHYSICAL EVIDENCE

Footprints, with all they imply, constitute no more than trace evidence, and no matter how compelling they may be, no matter how anatomically appropriate and internally consistent they appear, they are merely suggestive of the presence of the sasquatch. Where is the *hard* evidence? The vexing absence of bones and teeth has already been discussed in light of the nature of soil chemistry in Northwestern forests. Hair provides another *physical* remnant of the creature itself. Precise hair identification—trichinology—is, however, a challenging process requiring an extensive reference collection with which to compare the unknown sample. There can be considerable individual variation in hair length, color, texture, and stage of growth within a species, as well as variation between different regions on the body of a single individual animal. Arriving at a conclusive identification can be a labor-intensive process requiring exhaustive comparisons with known standards.

In the past there have been several independent analyses of hair attributed to sasquatch, more often than not conducted at the request of an amateur investigator. Usually, the hairs were readily identified as belonging to a commonly known animal such as bear, coyote, or human. However, some hair samples were of indeterminate identity. While an indeterminate indentification of an alleged "sasquatch hair" is interpreted by some as indication of an unknown animal, it is more conservatively regarded by others as the lack of a comprehensive collection of hair samples from known species of animals with which to compare the strand in question. Indeed this would be the only reasonable outcome for hair that might in fact have come from a sasquatch. All that could be concluded is what species the hair did not appear to belong to.

Conclusive identification depends on a match to a known sample of hair, i.e., an established standard. Without a confirmed sample of sasquatch hair, any hair truly originating from a sasquatch would necessarily languish in the indeterminate category. Such a standard is unlikely to be acknowledged until hair is pulled directly from a sasquatch body by a qualified analyst.

Hairs obtained from the Bluff Creek area by Ivan Sanderson were submitted for analysis to Dr. F. Martin Duncan, who was in charge of the extensive hair collection at the London Zoo. Duncan stated that they could not be matched to any known North American mammal, but that they could be from an unknown large primate, based on common features shared with species of that order.

Nearly a decade later, suspect hairs collected in central Idaho, in 1968, were sent to Ray Pinker, an instructor of police science at California State College in Los Angeles. He likewise determined that the specimens did not match any sample of known animal that he had in his collection, but showed some characteristics common to humans and nonhuman primates. The hairs were light, showing variation in color and thickness along their length unlike human hair, but exhibited a humanlike scale pattern and lacked a continuous medullary core. The sample contained both coarse guard hairs and fine underhairs, uncharacteristic of primates. As suggestive as these observations might appear, Pinker reiterated that he could not identify the hairs as sasquatch until he had a sample of authentic sasquatch hair to match it to.

Dr. Sterling Bunnell, M.D., a member of the California Academy of Sciences, conducted another hair analysis in 1993. Of a sample collected in northern California, he said, “I have examined the hair specimen you provided from Damnation Creek and compared it by light microscopy under direct and transmitted illumination with human, chimpanzee, gorilla, orangutan, and *Pygathrix* monkey hair. It is clearly related to the human-chimpanzee-gorilla group, but is distinguishable from each of these. On the basis of surface and internal structure it seems more like gorilla hair than human or chimp, while by the same criteria human and chimp appear closely related. The specimen hairs are remarkable in the extremely fine and diffuse pigmentation (the other species show dark melanin clumps and medullary streaks) and the absence of observable medullary structure.”

Such results have remained unimpressive, or simply unknown, to the scientific community at large. But as I discussed this challenging situation of the lack of a sasquatch standard with Dr. Henner Fahrenbach, it occurred to us that if the indeterminate hair samples did in fact come from an unknown species of ape, there should be a suite of distinctive and distinguishing diagnostic features

consistently characteristic of the suspect hairs. By backtracking to some of the labs and collecting their reports, it did appear that the indeterminate hairs displayed notably uniform characteristics, and likely represented an uncataloged single species of animal as their source. What are these characteristics of hair that form the basis of identification?

In nonprimate mammals, the hair is differentiated into three types: 1) longer, coarser guard hairs, which provide mechanical protection, 2) a finer undercoat of fur hairs, which provide insulation, and 3) stiff vibrissae or whiskers, which serve as tactile organs. Of these types, the guard hairs are of greatest diagnostic value. Primate hair is generally undifferentiated and has been described as possessing a modified combination of the characteristics of guard hairs and undercoat hairs. All hair varies, even single hairs from the same individual. In this way, hairs are rather like snowflakes. Therefore, a composite of characteristics occurring in all *or most* of the hairs in the reference sample is considered diagnostic. The outer layer of the hair shaft is called the cuticle. It consists of overlapping scales and may be thick or thin, clear or pigmented. The intermediate layer is the cortex, the main constituent of the shaft that gives the hair its texture. It contains keratinized cells and one of two types of pigment granules: melanin (brown) and phaeomelanin (blond and red). Also present are cortical fusi (tiny air bubbles) and ovoid bodies (dark ovals) the functions of which are unknown. An innermost central channel, found only in large thick hairs, is the medulla. It varies in diameter and may be dark when empty and filled with air, or it may be clear, although actually filled with cells.

Other characteristics include the diameter, cross-sectional shape, and length of the hair shaft. The hairs of individual species tend to wear differently. Some hair ends fray and split; others wear to a blunted end. Human head hair is ever-growing, lengthening about 10 cm per year, and typically has a cut end that is easily recognized under magnification. The follicle structure is less well studied, but may also display distinctive features. These are complicated by the changes that accompany the hair's growth cycle. Growing hair is said to be in the anagen phase, and the root appears as a stretched out tangle. During the resting phase, or telogen phase, the root ends in a neat bulb.

Fahrenbach has assembled over a dozen samples of hair that could not be attributed to any of the commonly known animals of North America, but which share a common suite of distinguishing features of the sort just discussed. Two of these samples are described in greater detail here:

Unknown sample A averaged 8′ (20 cm) in length (ranging from 3′ to 15′), was dark reddish brown to black; wavy to slightly curly in parts; mean diameter

of 65 μm (range 58-73 μm); cross-section round to slightly flattened entire length. Medulla absent, minimal fragmentary medulla in one region; cuticle pigmentation showed an irregularly waved mosaic pattern; scale margins were smooth to mildly crenulated (wrinkled); distance between scales intermediate; 9-12 scales per 100 μm linear distance. Most hairs were in the telogen stage of hair growth cycle, that is, they were ready to fall out on their own. A few strands had follicles attached. Some of the hairs had split ends, i.e., a brushlike tip, whereas most had smoothly rounded worn tips. None were cut.

Unknown sample B averaged 3-4′ (8.5 cm) in length (ranging from 2′ to 5′), was reddish brown to blond. It was identical in anatomy to sample A, except for the complete absence of a medulla. All hairs had attached follicles. Neither sample shows any indication of being cut.

”These samples were taken from adjacent fresh twist-offs,” Fahrenbach noted. “They came clearly from the same species, but from two different individuals, one light reddish brown with an average length of four inches (worn ends), the other with dark reddish brown (black to the naked eye), average length eight inches. Two sasquatches matching these colors were observed within twenty minutes in the immediate vicinity of the twist-offs by several eyewitnesses. None of the witnesses had the prerequisite hair color or morphology.”

The anatomy of the hair samples ruled out the common mammals of the region. There was no feature that absolutely ruled out identification as human hair, although the lack of cut ends on relatively short hairs seemed to make a human source quite unlikely. “The glitch in the absolute determination of the hair,” conceded Fahrenbach, “is the fact that *some* human hair can have a similar appearance.” And yet the circumstantial evidence of the discovery combined with the anatomy seemed to leave the sasquatch option open.

As novel molecular techniques became available, they held the potential of a surer identification of the hair than sole reliance on anatomy. In 1988, Bob Titmus sent some hair samples collected in northern California to Dr. Jerold Lowenstein, M.D., at the University of California, San Francisco. Dr. Lowenstein had pioneered techniques of radioimmunoassay. This technique employs the body’s ability to generate antibodies to foreign antigens. Antibodies were made to the unknown hair sample and then were cross-reacted with human, gorilla, and chimpanzee samples. Lowenstein concluded, “I used all of your material to make antibodies in a rabbit and then tested that antibody to see which animal’s serum gave the best reaction. It reacted more or less equally with human, chimpanzee, and gorilla, which suggested that it was probably human.

Those three are so close that I can't distinguish them (yet) [sic] on the basis of hair, though I can distinguish them if I have skin or blood." Lowenstein's conservative conclusion may not have taken into account the fact that the hairs in question were grown to length, with uncut ends, making it very unlikely that they were human.

The recent advent of polymerase chain reaction (PCR), a process that permits the exponential amplification of a targeted strand of DNA, and the ensuing revolution in DNA research has opened a new possibility for the study of sasquatch hair. DNA can be extracted from the cells within the hair and selected portions of the molecule can be sequenced. The sequence of the nucleotides, or DNA subunits, can in turn be compared to homologous sequences for known species and the sample may be identified. If it does not match the sequence of any known animal, then at least the phylogenetic position of the sample is determined. In other words it can be determined what its closest relatives are in its respective family tree. As with the hair itself, without a known sample of sasquatch DNA, the DNA sequence cannot be conclusively attributed to sasquatch.

Fahrenbach's samples A and B, described above, were examined by Dr. Paul Fuerst, at Ohio State University. Repeated attempts using both shafts and follicles, failed to successfully amplify mitochondrial DNA from the samples. Several reasons were hypothesized to explain the obstacle: the small diameter of the hair combined with the lack of a cellular medulla, the duration and conditions of storage of the hair before analysis, or some species-specific property of the DNA.

Todd Disotell of New York University has candidly said, "It's definitely true that different species' hair shows differential amplification probabilities. For instance, chimps' work well, gorillas' are a challenge. The closer to the bulb or the bulb itself is clearly the best. Shafts don't always have DNA in them. Unfortunately, I know of no study that has studied it intensively or in a controlled manner that could pinpoint what works best. Basically, you just try and cross your fingers."

Curiously, one quest for yeti DNA had a similar outcome. An expedition to Bhutan retrieved hair samples of interest, collected from an alleged yeti nest. These were conveyed to the Oxford molecular biologist, Bryan Sykes, for analysis. Sykes began with the assumption that he was dealing with bear hair, and so his findings came rather as a surprise. Attempts to sequence the DNA were altogether unsuccessful. In an interview with *Smithsonian Magazine* he remarked, "We normally wouldn't have any difficulty at all. It had all the

hallmarks of good material. It's not a human; it's not a bear, nor anything else that we have so far been able to identify. We've never encountered any DNA that we couldn't sequence before. But then, we weren't looking for the yeti . . . I didn't think this would end in a mystery."

Not all yeti samples have proved so mysterious. Peter Matthiessen submitted a hair sample from Tibet for analysis. Despite the insistance of his sherpa guides that the hair was from a yeti, the analysis concluded that the coarse hair was from a horse. However this does little to rationalize the indeterminate nature of the Bhutan hair studied by Sykes, or the unsequenced samples of alleged sasquatch hair. It should not be taken as affirmative evidence of either reputed creature, but it certainly signifies and should be acknowledged that an unanswered question remains that demands scientific attention.

When the Skookum cast was recovered, Noll, Randies, and Fish left the encrusting soil in place until I was able to arrive and direct the cleaning process. Using optivisors and magnifying glasses, we meticulously cleaned away the dirt using dental picks, needle probes, and soft brushes. Every fiber that was encountered was carefully placed in paper specimen envelopes. Dr. Fish and I subsequently sorted these. It was obvious that the hair of a variety of animals was present at the site, as was to be expected given the presence of various tracks. However, some hair appeared distinct during our preliminary assessment, and samples of those hairs of particular interest were sent to Dr. Fahrenbach for independent examination. He concurred that some of the hairs were consistent with the profile for sasquatch hair that he had established. Subsequently Dr. Fish conducted his own microscopic evaluation and identified additional specimens that coincided with the sasquatch characteristics.

The recovery of suspect hairs from the Skookum cast provided a new opportunity to reattempt DNA analysis. For this endeavor, Dr. Craig Newton, a molecular biologist with British Columbia Research, was enlisted. Newton indicated that, "If we get a DNA sample, we will generate a DNA sequence that will identify the source of the hair somewhere on the tree of life, either between humans and primates, or between other organisms of the forest. It's all in the DNA."

Molecular biologist Craig Newton attempted to sequence DNA from sasquatch hair samples. (Courtesy of Doug Hajicek / Whitewolf Entertainment, Inc.)

Newton's intention was to get as much data as possible in order to attract the attention of experts in *primate* DNA and human forensics to examine the question more thoroughly. He successfully extracted DNA from the hair samples, although it was fragmentary. In this case he attempted to utilize nuclear DNA primers, the short bits of DNA used to initiate the amplification of the target DNA. Preferable would have been primers for mitochondrial DNA (mtDNA). The mitochondria are numerous organelles within the cell that produce chemical energy and have their own strand of DNA. The mtDNA has characteristics making it sometimes more useful for amplification, identification, and analysis. Based on the sequences yielded by the fragmentary nuclear DNA, he was unable to rule out human contamination, or even a possible human source.

The study of hair samples has been troubled by the occurrence of synthetic fibers mistakenly associated with sasquatch activity, or perhaps intentionally passed off as sasquatch hair for whatever reason. Paul Freeman displayed examples of sapling trees twisted over, presumably by sasquatch. Entangled in the splintered wood were what appeared to be hair strands. These turned out to be extruded monofilament Dynel fibers, commonly used as synthetic fur and wigs, as well as stuffing in furniture. On the surface, this appears to be a clear-cut case of hoaxing. However, others, including a retired game warden, have also discovered suspicious "hair" that likewise turned out to be similar synthetic fibers. It has been suggested that these resilient fibers have become something of

a pervasive environmental contaminant, although the extent of this has not been determined. It should be noted that Freeman has collected several samples of true hair that number among Fahrenbach's collection of possible sasquatch hair, including samples from which degraded DNA was extracted by researchers at Ohio State University. It seems unjustified to throw out all the evidence as the result of a case of misidentification.

Scat, the excrement or feces of an animal, constitutes another important form of physical evidence. It is a significant form of sign that conveys revealing information about the identity of the animal, the location of its activities, and its size and diet. In the past the study of scat (scatology) has been largely descriptive. Identification of scat is based on characteristics such as texture, shape, size and quantity, color, odor, and location. There is a great deal of inherent variability in the appearance of scat. For example, tracker Jim Halfpenny observes, "Experience has shown that visual identification of scat without additional clues may be correct only 50-66 percent of the time. Experienced naturalists in laboratory tests of unmarked scat correctly identified only 88 percent of lion scat and 64 percent of bobcat scat. The wrong identifications stress the need for other supporting clues, including tracks, wherever possible."

Since bears are large omnivores, it stands to reason that their scat, based on the effects of a similar diet, would most likely be erroneously attributed to sasquatch. Therefore, a detailed description of the characteristic and seasonal features of the feces of the bear family follows, as provided by Jim Halfpenny in *A Field Guide to Mammal Tracking in North America* Qohnson Books, Boulder, CO). "Bear scats are thick cords with blunt ends. The quantity of scat is often great, and you may see large piles. The omnivorous bears have brown, black, and blue-colored scat from eating pine nuts, animal protein, and berries respectively. Bear scat often contains insects, especially ants, termites, and bees. You may have to look hard at the scat to identify the undigested heads of these insects. Plant remains are also common, with grasses, dandelions, horsetails, and thistles being favored. Some scat containing plant material will be black. The fibrous nature of the scat and sweeter plant smell will separate these scat from those containing animal protein. In the Fall, a diet of acorns produces above-average-size brown scat. From April to October, grizzlies will raid the caches of squirrels for white-bark pine nuts and the husks will be evident in the scat. A Fall diet of berries will produce soft to semi-liquid scat. Scats greater than 2 inches (5 cm) in diameter have been considered grizzly scat. However, Herrero reported that of 140 grizzly scats measured in Banff National Park, 60 (58

percent) were less than 2 inches. Larger grizzlies produce larger scat. If you use the 2-inch rule, you will tend to misidentify the females, who may be with their young, and young males, a very serious error."



Sample of scat tentatively attributed to sasquatch (Courtesy of John Green)

Innovations in the study of endoparasites, chemistry, and DNA can potentially provide added information. Ivan Sanderson reported the results of a rare analysis of endoparasites conducted by an unnamed Oregon medical lab on a scat sample suspected to have originated from a sasquatch. It contained the eggs of a parasitic nematode worm of the genus *Trichuris*. The size and proportion of the eggs are distinct for individual species, which in turn are very host-specific. That is, certain parasite species are found only in the guts of particular host species of mammals. The sasquatch sample contained three types of eggs, although the examiner demurred from identifying them due to their state of deterioration. It was concluded that the largest eggs were outside the range of human parasite ova, but that such large eggs had been reported from various other primates. Sanderson also reported on a sample that was packaged in a container with dry ice and sent to him in New York for transfer to Dr. W.C. Osman Hill, then senior scientist at the London Zoological Society. In Sanderson's words, "This specimen shook up the scientists . . . this fecal mass did not in any way resemble that of a known North American animal. On the other hand it did look humanoid, but it had some peculiar features, as if the lower bowel had a spiral twist. But, above all, it was composed exclusively of vegetable matter, and this, as far as could be identified, of local (Californian) fresh-water plants. The real clincher was that it contained the eggs and desiccated remains of certain larvae otherwise only known in (a) some North

American Indian tribal groups in the Northwest, (b) pigs imported from south China, (c) human beings in country districts in southwest China, and (d) pigs from that same area." Another potential Asian connection?

Dr. Vaughn Bryant, an anthropologist at Texas A&M University, examined two scat samples from the Pacific Northwest, which consisted largely of plant matter. Based on the microscopic examination of the reconstituted cells of the constituents of the feces, he was able to rule out man, moose, elk, deer, and bear as the source in these cases, but could not identify the source further. His findings were published in the edited collection of papers, *Manlike Monsters on Trial*. Bryant reflected on the course of events: "I lived in the Pacific Northwest during the late 1960s and 1970s when I taught anthropology at Washington State University. I was good friends with Grover Krantz, and he and I would discuss much of the ongoing search and information about sasquatch. I was a skeptic, but open-minded. We went out to look at sighting locations once in a while. When I moved to Texas, I continued my interest in the subject and let it be known that I was willing to examine feces and hair if any were found (these are my specialty areas). Soon, I was receiving all sorts of packages of feces—some still fairly fresh. The problem was that I was soon overwhelmed with samples and could not examine all of the samples due to time and expense. Remember, I was also teaching a full load, working with my own graduate students, trying to publish research, establish a scientific reputation, and do what my university and colleagues called 'scholarly work.' Bigfoot did not fit into that category and, in fact, I was told several times that my continued interest in the subject put my career in jeopardy. Nevertheless, I continued working on some of the materials. The bottom line is that I could never find anything that would eliminate the fecal samples from belonging to some other animal that was also omnivorous. Perhaps someday someone can do DNA of a sample. However, the process is costly and time consuming."

Clearly the question of sasquatch's existence is unlikely to be resolved conclusively without physical evidence. The conventions of zoological taxonomy require a type specimen, traditionally in the form of a body or a sufficiently diagnostic physical body part, to decisively establish the existence of a new species. Whether DNA alone will ultimately satisfy that standard remains to be seen. I am doubtful. I am not aware of a precedent for determining a new species on the basis of DNA evidence, in the absence of a physical specimen. Subpopulations of recognized species have been differentiated based on DNA sequence differences and been given species status, but those subpopulations were previously known and sampled. However, a substantial DNA sequence

would be a major development in the search. Short of a body, or a significant part of one, it would seem that the elusive DNA evidence is the next objective to be focused upon by those who can no longer dismiss the matter out of hand.

WHERE WE STAND: THE EVIDENCE WEIGHED AND MEASURED

The most stifling situation that can ensue from this subject is for the treatment of the question of the existence and nature of sasquatch to be reduced to an argument between "believers" and "skeptics." I am frequently asked, "Do you believe in sasquatch?" I invariably and firmly reply that a question of *belief is* simply not at issue. Belief generally connotes the acceptance of something as true in the absence of objective evidence or conclusive proof. It is usually equated with a position of faith. Science is about subjecting hypotheses to evaluation by marshaling evidence that may either refute, or lend support to a premise. Therefore, from a scientific standpoint I can say that a respectable portion of the evidence I have examined suggests, in an independent yet highly correlated manner, the existence of an unrecognized ape, known as sasquatch. This conclusion of necessity remains tentative and provisional since the interpretation of the evidence, however persuasive it may be at this point, remains ultimately inconclusive. It should be well noted that a pending conclusion has rarely provoked a scientist to abandon research that is backed by empirical evidence. Unfortunately, those scientists who *have* made the effort to systematically review and evaluate the data, and as a result are motivated, if not obliged, to pursue their intellectual curiosity further, are frequently labeled as "believers" and are judged incapable of further objectivity.

From the sidelines, ideological skeptics would wrap themselves in the banner of science and profess that they approach a controversial phenomenon from a rational and critical position. However, the extreme conservatism typically embraced by such individuals is not without its own pitfalls. Michael Shermer, founder of the Skeptics Society and publisher of the *Skeptics Magazine*, offers

this caution in his manifesto: “The key to skepticism is to continuously and vigorously apply the methods of science to navigate the treacherous straits between ‘know nothing’ skepticism and ‘anything goes’ credulity.” This is a worthy aim, and Shermer’s caution about the treacherous nature of the passage is warranted, the correct bearing to that middle course is sometimes as elusive as sasquatch itself. It would seem that many skeptics run aground as they unwittingly list or deliberately steer toward the extreme of incredulity. This can result from a lack of motivation to become informed about the essential evidence, the simple impracticality of thoroughly evaluating every assertion that comes along, or even more fundamentally, the sheer lack of the requisite expertise to evaluate the evidence for such a broad range of purported phenomena. Whichever cause it may be, many professing skeptics do not allow their own ignorance of the primary data to prevent them from pronouncing baseless and often cynical condemnation of the subject and those most familiar with it.

In his regular *Scientific American* column, Shermer was apparently prompted by the rash of publicity surrounding the Wallace story to address the issue of Bigfoot. In opening the column he professed open-mindedness, saying that Bigfoot, “. . . while occasionally eliciting an acerbic snicker, enjoys greater plausibility [than the Jackalope] for a simple evolutionary reason: large hirsute apes currently roam the forests of Africa, and at least one species of a giant ape —*Gigantopithecus*—flourished some hundreds of thousands of years ago alongside our ancestors.” Then Shermer runs aground upon a shoal on the coast of “know nothing” skepticism. He asserts that although the question of Bigfoot may have warranted our exploratory resources at one time, it no longer does. Why? Because he believes that “If such creatures survived in the hinterlands of North America and Asia, surely by now one would have turned up.” After rehearsing this tired cliche, he next fully exposes his lack of familiarity with the details and depth of the evidence by summing up the entire matter as simply a collection of stories. According to science historian Frank J. Sulloway, of the University of California at Berkeley, stories do not constitute science, and it makes no difference whether one confronts one, ten, or a hundred anecdotes. Shermer raises this caveat to a maxim when dealing with “Bigfoot hunters.” He admonished, “Their tales make for gripping narratives, but they do not make sound science. A century has been spent searching for these chimerical creatures. Until a body is produced, skepticism is the appropriate response.”

Indeed, in so far as skepticism embodies the *continuous and vigorous application of the methods of science*, then Shermer’s conclusion is quite

justified. However, his characterization of the question does little to convey a sense of its history or of the mounting evidence—trace, photographic, and physical—such as discussed in this volume, which takes the matter far beyond a mere collection of anecdotes. Shermer was recently invited to present a public lecture on the Idaho State University campus. He didn't on this occasion broach the subject of sasquatch, but he was engaged during his visit by a group of students who happene d to be producing a documentary called, "Rocky Mountain Bigfoot," for their mass communications class project, mentored by Dr. Michael Trinklein. During a brief recorded interview, Shermer acknowledged the possibility of the existence of sasquatch, but deemed it very unlikely. "Okay, fine, I'm glad you're looking. I hope you find something—call me when you do. After a hundred years I'd get a little discouraged by now. I'd go try to find something else—like aliens," he said. The students quickly realized that Shermer's skepticism was not based on a familiarity with, let alone expert evaluation of the evidence, and in the face of their probing questions he simply fell back to the position that "It's just mythology. . . . For this to be a science you've got to have a body. That's the way it works."

I should reiterate my acknowledgment that the conventions of zoological taxonomy require a type specimen to establish the existence of a new species. On this point Shermer is in principle quite correct. That having been said, the position that the evaluation of the evidence presented in this book falls outside the purview of good science is frankly indefensible. I don't think any reasonable investigator is out to convince the skeptics in the absence of physical proof, but I suggest that to offhandedly ignore or simply dismiss the current "body" of evidence that bears on this question, is to have failed to navigate the treacherous strait between "know nothing" skepticism and "anything goes" credulity. The nature and extent of the evidence fully justifies, in truth demands, the serious attentions of scientists.

Perhaps even more disingenuous is to acknowledge the evidence, but then to distort and make light of it. Benjamin Radford, managing editor of *Skeptical Inquirer* magazine, published a skeptical summary entitled, "Bigfoot at 50: Evaluating a Half Century of Bigfoot Evidence." Assuming that the Bigfoot phenomenon abruptly sprang into existence in 1959, Radford acknowledges that after nearly fifty years, the question of Bigfoot's existence remains open. He notes that the issue comes down to evidence. "There is indeed no shortage of evidence. The important criterion, however, is not the *quantity* of the evidence, but the *quality* of it." To support his contention that the evidence for Bigfoot is generally poor, he cites contradictory conclusions drawn by "Bigfoot

researchers," but makes no distinction between the conclusions drawn by credentialed scientists and those of amateur investigators. Instead, he pits their interpretations of the data against one another as if they were on equal footing. As each category of evidence is necessarily summarized briefly, but incredibly superficially, he repeatedly misleads, misrepresents, and selectively quotes the opinions of unqualified individuals as if they were authorities. Eyewitness accounts are summarily dismissed, even those by trained observers, such as wildlife biologists, since, as he puts it, "Anyone, degreed or not, can be mistaken." All spurious footprints are lumped together and then he wonders at the lack of consistency that one might expect from a single unknown species. Turning to the Skookum imprint, instead of evaluating the features of the cast itself, he remains incredulous because the animal "made such an odd approach to the food." Not so odd if he had a familiarity with great ape feeding behavior.

Radford's discussion of the Patterson-Gimlin film is most egregious—rife with inaccuracies that are implied as indicative of a probable hoax. He states the assumption that Patterson was on the scene with the express purpose of capturing a sasquatch on film. In point of fact, Patterson was there in response to the recent discovery of clear footprints with the intent of filming fresh tracks for inclusion in a documentary he intended to produce. Next, Radford says that a known hoaxer (Ray Wallace) claimed to have told Roger exactly where to go to see the Bigfoot on that particular day. Indeed, Wallace *claimed* to have told Roger where to go, but it was clear from later interviews that he possessed little knowledge of the specific area, and his family, although claiming he had hoaxed other films and photos, publicly denied any involvement by Wallace in the Patterson incident (although in the face of waning media interest in their story, some members of the family have made public statements to suggest or even assert that Wallace was responsible for the Patterson-Gimlin film as well). Finally, Radford alleges that Patterson turned quite a profit and garnered publicity for his book. But, in fact, what modest profits may have been realized were expended in further efforts to pursue the creature. Even when Patterson was about to suffer a premature death from Hodgkin's disease and could have reaped significant profits by revealing a fake, he maintained his original account of the events, as has his disenfranchised partner in the filming, Bob Gimlin, to this day.

At last, Radford equates *inconclusive* results of the analysis of hair, scat, and blood samples that defy identification with negative evidence (i.e., the lack of information) and glibly suggests that when a *conclusive* result is found, the source is commonly elk, bear, or cow hair. This approach ignores the fact that a

wide sample of independently collected hair defies identification or standard DNA sequencing protocols. That conclusion is quite different from negative evidence.

Both of these skeptics are biased by a different but related misconception. Shermer asserts that a century has been spent searching for Bigfoot with no conclusive result to show for it. *Who* has been doing the searching? What institutionally sponsored and equipped scientific expeditions have committed sustained effort and resources to document or alternately refute the existence of a North American ape? Virtually none. On the other hand, Radford implies that the evidence for sasquatch has been weighed and measured and has been found wanting. Radford and the majority of those critics cited in his article have limited expertise to evaluate the diverse evidence—e.g., footprints, dermatoglyphics, hair, scat, vocalizations, etc.—with a degree of competence or authority. Indeed, precious few qualified scientific researchers have made any serious attempt to systematically review and evaluate the data, although the number continues to increase. Several such scientists have been featured in this volume, and their approach to the subject and the conclusions they arrived at contrast markedly with those of the professional skeptics—and of some of the "believers" for that matter.

A welcome sign of a thawing of attitude among the "orthodoxy" came as a sidebar in a *Scientific American* article. The article in the August 2003 issue was by paleoprimatologist Dr. David Begun, of the University of Toronto. The sidebar was entitled, "Bigfoot Ballyhoo." The text was reasonably and refreshingly objective in addressing the question, but the editorial choice of title betrays a persistent underlying "tongue-in-cheek" attitude and an underappreciation of the accumulating evidence suggesting the potential existence of a North American ape. *Ballyhoo* is defined as an "exaggerated clamorous attempt to advance a cause." Implicit is the suggestion that the "believers" are stumping for sasquatch by exaggerating the weight of the evidence. The more disturbing exaggeration I have witnessed is the excessive trivialization of the data, often by the media, but also by self-assured skeptics and by inadequately informed scientists.

What are the implications of indeterminate hair samples that display consistently distinct characteristics; many hundreds of eyewitness encounters by reputable professionals, including wildlife biologists, foresters, national park rangers, field geologists, and law enforcement officers; functional analyses of an extensive collection of footprints, some that I have personally documented in remote areas of northern California and Washington; dermatoglyphics; recorded

vocalizations; and films that have withstood the critical scrutiny of locomotion experts? The more notable clamor seems to arise from those who emphatically refuse to examine these data or to discuss them in an objective and scientific manner.

Rather than consider the sasquatch some uniquely extraordinary apparition, it is much more productive to identify those features it appears to bear in common with other organisms. In what ways is it consistent with our knowledge of the evolution, natural history, and biogeography of primates on the one hand and with known wildlife in North America on the other? In this book the mounting evidence for the existence of an unknown North American primate has been considered by a world-class lineup of specialists from a broad spectrum of disciplines. They have ventured to weigh and measure the evidence concerning the presence of such a giant North American ape on its own merits without preconception or prejudice. What conclusions have they drawn from their investigations? Have their previous opinions been modified by the experience?

In several instances the evidence is intriguing if not outright persuasive and compels to further investigation. The footprints and Skookum cast were pivotal in turning the heads of noted primate anatomists and dermatoglyphists. Expert viewers could not casually dismiss a number of films and videos as simply an obvious case of a "man in a fur suit." Morphologically, the hair evidence indicates some unknown animal, although the definitive DNA evidence remains elusive and must become a focus of future endeavor. The pervasive sightings and notable correlations of consistent anatomy, behavior, and vocalization also point to a real animal—one that displays remarkable parallels to known great apes, while exhibiting unique characteristics appropriate to its particular ecology. The deeply rooted cultural and historical knowledge of a hairy wildman possessed by indigenous populations attests to a zoological entity.

Where does the investigation go from here and what data are required to reach a definitive resolution? A body? DNA? The final answers to these questions will require a challenge to some preconceptions held by the scientific community, in which extreme skepticism is sometimes deemed a requirement for reputable membership. For me, it now seems more incredible to suggest this matter could all be dismissed as mere stories, misidentifications, and spurious hoaxes than it is to at least rationally entertain the well-founded suggestion that the legend of sasquatch possibly has its basis in a real animal and may eventually prove to be among the most astounding zoological discoveries ever.

What might be the implications of such a discovery? The thing that clearly unites us *physically* as a global human family is our common origin. Our

understanding of that common physical origin has been increased as we have come to better understand and appreciate our closest kin in the animal kingdom —the great apes. The pioneering researches of early field primatologists have virtually pulled back a curtain, revealing the narrowness of the "gulf" that separates us from them. How much *more* impacting would be the discovery and recognition of a hominoid possibly more humanlike than any other inhabiting this planet? As the shrinking tropical habitats of the known apes have brought to public consciousness the stewardship we bear for the distant tropical environment and its imperiled coinhabitants, so might the recognition of sasquatch sharpen our sense of responsibility for our own temperate habitats and bring into finer resolution our connection to wild places.

Selected Bibliography

Alley, J.R. *Raincoast Sasquatch*. Blaine, Wash.: Hancock Publishers, 2003.

Arcadi, C, D. Robert, and C. Boesch. (1998) Buttress drumming by wild chimpanzees: Temporal patterning, phrase integration into loud calls, and preliminary evidence for individual distinctiveness. *Primates*. 39(4):505-518.

Bayanov, D. *America's Bigfoot: Fact, Not Fiction*. Moscow, Russia: Crypto-Logos Publishers, 1997.

Bayanov, D., I. Bourtsev, and R. Dahinden. (1984) Analysis of the Patterson-Gimlin film: why we find it authentic. In: V. Markotic and G. Krantz (eds.) *The Sasquatch and Other Unknown Hominoids*. Calgary: Western Publishers, pp. 219-234.

Begun, D. Planet of the Apes. *Scientific American*, August 2003, pp. 74-83.

Bindernagel, J.A. *North America's Great Ape: The Sasquatch*. Courtenay, B.C.: Beachcomber Books.

Bourne, G.H., and M. Cohen. *The Gentle Giants: The Gorilla Story*. New York: G.P. Putnam's Sons, 1975.

Brown, P., T. Sutikna, M.J. Morwood, R. P. Soejono, E. Jatmiko, Wayhu Saptomo, and Rokus Awe Due. A new small-bodied hominin from the Late Pleistocene of Flores, Indonesia. *Nature* 431:1055-1061.

Bryant, Jr., V.M., and B. Trevor-Deutsch. Analysis of feces and hair suspected to be of sasquatch origin. In: Halpin, M. and Ames, M. M. (eds.) *Manlike Monsters on Trial: Early Records and Modern Evidence*. Vancouver: University of British Columbia Press, 1980, pp. 291-300.

Burns, J.W. Introducing B.C.'s hairy giants. *MacLean'sMagazine*, April 1, 1929, p.9f.

Chorvinsky, M. (1994) New Bigfoot photo investigation. *Strange Magazine*, No. 13, Spring 1994, pp. 10f.

Chorvinsky, M. (1993) Our strange world: Bigfoot and the Ray Wallace connection. *Fate*, November, pp. 22-29.

Churchill, E., McConville J.T., Laubach, L. L., Churchill, T, Erskine, P. and Downing, K. (1978) *Anthropometric Source Book, Volume II: A Handbook of Anthropometric Data*. NASA Reference Publication 1024 (NTIS No. N79-13711/3/3/XPS). National Aeronautics and Space Administration, Scientific and Technical Information Office.

Ciochon, R.,J. Olsen, and J. James. *Other Origins: The Search for the Giant Ape in Human Prehistory*. New York: Bantam Books, 1990.

Coleman, L. *Bigfoot! The True Story of Apes in America*. New York: Paraview Pocket Books, 2003.

Cronin, Jr., E.W. *The Arun: A Natural History of the World's Deepest Valley*. Boston: Houghton Mifflin, 1979.

Daegling, D.J. *Bigfoot Exposed: An Anthropologist Examines America's Enduring Legend*. Walnut Creek, Calif.: AltaMira Press, 2004.

Daegling, D.J. (2002) Cripplefoot hobbled. *Skeptical Inquirer* 26(2):35-38.

Daegling, D.J., and D.O. Schmitt. (1999) Bigfoot's screen test. *Skeptical Inquirer* 23(3):20-25.

Daegling, D.J., and Grine, F. E. (1994) Bamboo feeding, dental microwear, and diet of the Pleistocene ape *Gigantopithecus blacki. South Africa Journal of Science* 90:527—532.

Dennett, M. 1989. Evidence for Bigfoot? An investigation of the Mill Creek 'Sasquatch Prints.' *Skeptical Inquirer* 13(3), Spring: 264-272.

Ducros, A., and J. Ducros. From satyr to ape: A scandalous sculpture in Paris. In: R. Corbey and B. Theunissen (eds.) *Ape, Man, Apeman: Changing Views Since 1600*. Leiden: Department of Prehistory, Leiden University, 1995, pp. 337-339.

Enders, R. K. The "Abominable Snowman." *Science* 126:858 (25 October 1957).

Fahrenbach, W. H. (1997-1998) Sasquatch: size, scaling, and statistics. *Cryptozoology* 13: 47-75.

Galdikas, B.M.F. *Reflections of Eden: My Years with the Orangutans of Borneo*. Boston: Little, Brown and Co., 1995.

Gee, H. *H.flores*, God and Cryptozoology. *www.nature.com/news/2004/041025/full/0410252html*

Gill, G.W. Population clines of the North American Sasquatch as evidenced by track lengths and estimated stature. In: Haplin, M. and Ames, M. M. (eds.) *Manlike Monsters on Trial: Early Records and Modern Evidence*. Vancouver, University of British Columbia Press, 1980, pp. 265-273.

Glickman, J. (1998) Toward a resolution of the Bigfoot phenomenon. Hood River, Oreg.: North American Science Institute (unpublished report).

Goodall, J. *The Chimpanzees of Gombe: Patterns of Behavior*. Cambridge, Mass.: Belknap Press, 1986.

Green, J. *Sasquatch: The Apes Among Us*. Seattle: Hancock House Publishers, 1978.

Green, J. *Year of the Sasquatch*. Agassiz, B.C.: Cheam Publishing, 1970.

Green, J. *On the Track of the Sasquatch*. Agassiz, B.C.: Cheam Publishing, 1968.

Greenwell, J. R. Cryptozoology: On the trial of unverified animals. *Wild Tracks* (Newsletter of the International Wildlife Museum) Winter, 2001:4-5.

Greenwell, J.R., D.J. Meldrum, M. T. Slack, and D.A. Greenwell. (1999) A Sasquatch field project in northern California: Report of the 1997 Six Rivers National Forest Expedition. *Cryptozoology* 13:76-87.

Halfpenny, J. *A Field Guide to Mammal Tracking in North America*. Boulder: Johnson Books, 1986.

Hillary, E. *Nothing Venture, Nothing Win*. New York: Coward, McCann & Geoghegan, Inc., 1975.

Heuvelmans, B. *On the Track of Unknown Animals*. Cambridge, Mass.: MIT Press, 1965.

Husbands, C. When Did 'Hobbit' Humans Die Out? Not So Long Ago, Say Indonesian Villagers. *Berkeley Daily Planet*, November 2, 2004.

Kerbis Peterhans, J., Wrangham, R. W., Carter, M.L., and Hauser, M. D. (1994) A contribution to tropical rain forest taphonomy: Retrieval and documentation of chimpanzee remains from Kibale Forest, Uganda. *Journal of Human Evolution* 25:485-514.

Kirkpatrick, D. (1968) The search for Bigfoot. *National Wildlife* 6(3):43-47.

Kirlin, R. L. and L. Hertel. Estimates of Pitch and Vocal Tract length from Recorded Vocalizations of Purported Bigfoot. In: Haplin, M. and Ames, M. M. (eds.) *Manlike Monsters on Trial: Early Records and Modern Evidence*. Vancouver: University of British Columbia Press, 1980, pp. 274-290.

Kleiner, K. (2000) Bigfoot's buttocks. *New Scientist* 168(2270):8.

Krantz, G.S. *Bigfoot Sasquatch Evidence*. Blaine, Wash.: Hancock House Publishers, 1999.

Krantz, G. S. (1987) A reconstruction of the skull of *Gigantopithecus blacki* and its comparison with a living form. *Cryptozoology* 6:24-39.

Krantz, G. S. (1983) Anatomy and dermatoglyphics of three sasquatch footprints. *Cryptozoology* 2:53-81.

Krantz, G.S. (1972) Anatomy of the Sasquatch foot. *Northwest Anthropological Research Notes* 6(1):91-104.

Krantz, G. S. (1972) Additional notes on Sasquatch foot anatomy. *Northwest Anthropological Research Notes* 6(2):230-24l.

Krantz, G.S. (1971) Sasquatch handprints. *Northwest Anthropological Research Notes* 5(2): 145-151.

Leonard, N. L. *The First Americans*. New York: Time-Life Books, 1973.

Long, G. *The Making of Bigfoot: The Inside Story*. Amherst, N.Y.: Prometheus Books, 2004.

Mack, C. *Grizzlies and White Guys: The Stories of Clayton Mack*. Madeira, B.C.: Harbour Publishing, 1996.

Marsh, O.C. (1877) Ancient life in America. *Scientific American Supplement* 4(90): 1436-37 and 4(91): 1449-51.

Matthiessen, P. and T. Laird. *East of Lo Monthang: In the Land of the Mustang*. Boston: Shambhala Publications, 1995.

McKinnon, J. *In Search of the Red Ape*. New York: Ballantine Books, 1974.

Meldrum, D.J. (2005) Review of *Bigfoot Exposed: An Anthropologist Examines America's Enduring Legend*, by David J. Daegling. *Journal of Scientific Exploration* 19:304-316.

Meldrum, D.J. (2004) Midfoot flexibility, fossil footprints, and Sasquatch steps: New perspectives on the evolution of bipedalism. *Journal of Scientific Exploration* 18:67-79.

Meldrum, D.J. (2004) Fossilized Hawaiian footprints compared to Laetoli hominid footprints. In: D.J. Meldrum and C. E. Hilton (eds.) *From Biped to Strider: The Emergence of Modern Human Walking, Running, and Resource Transport*. New York: Kluwer Academic and Plenum Publishing, pp. 63-84.

Meldrum, D.J. (2002) Midfoot flexibility, footprints and the evolution of hominid bipedalism. *American Journal of Physical Anthropologists Supplement* 34:111-112 (abstract).

Meldrum, D.J. (1999) Evaluation of alleged Sasquatch footprints and inferred functional morphology. *American Journal of Physical Anthropologists Supplement* 28:200 (abstract).

Meldrum, D.J. (1997) Review of *Bigfoot of the Blues*, by Vance Orchard. *Cryptozoology* 13:109-111.

Meldrum, D.J., and D. R. Swindler. (2004) The Skookum imprint: trace evidence of Sasquatch? *Program with Abstracts of the 87th Annual Meeting of the Pacific Division, American Association for the Advancement of Science*, p. 65 (abstract).

Meldrum, D.J., and J.H. Chilcutt (2001) Dermatoglyphics in casts of alleged North American Ape footprints. *Program of the Northwest Anthropological Conference*, p. 35 (abstract).

Meldrum, D.J., and J. R. Greenwell. (1998) Bigfoot: Take two. *BBC Wildlife Magazine* 16:68-71.

Mitani J. C, and J. Stuht. (1998) The evolution of nonhuman primate loud calls: Acoustic adaptation for long-distance transmission. *Primates* 39:171-182.

Montagna, W. (1976) From the director's desk. *Primate News* l4(8):7-9.

Murphy, C.L. *Meet the Sasquatch*. Blaine, Wash.: Hancock House, 2004.

Napier, J. *Bigfoot: The Yeti and Sasquatch in Myth and Reality*. New York: E.P. Dutton & Co., 1973.

Orchard, V. *The Walla Walla Bigfoot*. Prescott, Wash.: Ox-Yoke Press, 2001.

Patterson, R. *Do Abominable Snowmen of America Really Exist?* 'Yakima, Wash.: Northwest Research Association, 1966.

Patterson, R., and C. Murphy. *The Bigfoot Film Controversy*. Blaine, Wash.: Hancock House Publishers, 2005.

Perez, D. E. Bigfoot at Bluff Creek. BigfooTimes, October 20, 2002 (Released as booklet May 1994).

Pert, C. *Molecules of Emotion: The Science Behind Mind-Body Medicine*. New York: Simon and Schuster, 1999.

Radford, B. (2002) Bigfoot at 50: Evaluating a half century of Bigfoot evidence. *Skeptical Inquirer* 26(2):29-34.

Rennie, J. Unexpected thrills. *Scientific American*, May 1996, p. 4.

Ruby, R. H., and J.A. Brown. *The Spokane Indians: Children of the Sun*. Norman: University of Oklahoma Press, 1970.

Sanderson, I.T. *Abominable Snowmen: Legend Come to Life*. Philadelphia: Chilton Book Co., 1961.

Sanderson, I.T. (1968) First photos of "Bigfoot," California's legendary "Abominable Snowman." *Argosy*, February.

Sanderson, J., and M. Trolle. (2005) Monitoring elusive mammals. *American Scientist* 93: 148-155.

Savage-Rumbaugh, E.S., S.L. Williams, T. Furuichi, and T. Kano. Language perceived: *Paniscus* branches out. In: W. McGrew, L. F. Marchant, and T. Nishida (eds.) *Great Ape Societies*, New York: Cambridge University Press, 1996, pp. 173-184.

Schaller, G. B. *The Mountain Gorilla: Ecology and Behavior*. Chicago: University of Chicago Press, 1976.

Shermer, M. (2003) Show me the body. *Scientific American*, April 14.

Shermer, M. *Why People Believe Weird Things: Pseudoscience, Superstition, and Other Confusions of Our Time*. San Francisco: W.H. Freeman, 1997.

Shipton, E: *The Mount Everest Reconnaissance Expedition*. New York: E.P. Dutton, 1952.

Shuman, J. B. (1968) "This Is Bigfoot." *West, L.A. Times Magazine*, December 15, pp. 24-26, 29.

Simpson, G. G. (1984) Mammals and cryptozoology. *Proceedings of the American Philosophical Society* 128(1):1-19.

Sprague, R., Editorial, *Northwest Anthropological Research Notes* 4(2):127-128.

Sprague, R. Carved stone heads of the Columbia River and Sasquatch. In: Haplin, M. and Ames, M. M. (eds.) *Manlike Monsters on Trial: Early Records and Modern Evidence*. Vancouver: University of British Columbia Press, 1980, pp. 229-234.

Sprague, R. and Krantz, G.S. (eds.) *The Scientist Looks at the Sasquatch II*, Moscow, Idaho: University of Idaho Press, 1979.

Straus, Jr., W. L. Abominable Snowman. *Science* 123:1024-1025 (8 June 1956).

Swan, L. W. "Abominable Snowman." *Science* 126:858 (25 October 1957).

Swan, L. W. *Tales of the Himalaya: Adventures of a Naturalist*. La Crescenta, Calif.: Mountain N' Air Books, 1999.

Swindler, D.R. and C.D. Wood. *An Atlas of Primate Gross Anatomy: Baboon, Chimpanzee, and Man. Malabar, Fla.: Robert E. Krieger Publishing Company, 1982*.

Vlcek, E. (1959) Old literary evidence for the existence of the "Snowman" in Tibet and Mongolia. *Man* 59:133-134.

Wallace, D.R. *The Klamath Knot: Explorations of Myth and Evolution*. San Francisco: Sierra Club Books, 1983.

Ward, M. (1997) Everest 1951: The footprints attributed to the Yeti—myth and reality. *Wilderness Environmental Medicine* 8(l):29-32.

Weidenreich, F. *Apes, Giants and Man*. Chicago: University of Chicago Press, 1946.

White, T. D., and G. Suwa. (1987) Hominid footprints at Laetoli: Facts and interpretations. *American Journal of Physical Anthropology* 72:485-514.

Wylie, K. *Bigfoot: A Personal Inquiry into a Phenomenon*. New York: The Viking Press, 1980.

Yutaka Kunimatsu, Y., B. Ratanasthien, H. Nakaya, H. Saegusa, S. Nagaoka (2004) Earliest Miocene hominoid from Southeast Asia. *American Journal of Physical Anthropology* 124:99-108.

Yerkes, R. M., and A. W. Yerkes. *The Great Apes: A Study of Anthropoid Life*. New Haven: Yale University Press, 1929.

Index

A

Abbott, Don, 60, 149, *150*, 230
Abbott's duiker, 127
abdominal anatomy, 167–68
abduction of women, 77–79
abominable snowman, *see* yeti (abominable snowman)
Abominable Snowmen: Legend Come to Life (Sanderson), 51
Academia Sinica, 90
Achilles tendon, 117, *118*, 120, 121–22, 235
Agar, Tom, 97
Akin, James P., 257
Alaskan brown bear *(Ursus middendorffi)*, 93, 96, 102, 210
Alford, Glenn, 119–21
Algonkian Indians, 84–85
Allen, Betty, 73
Alley, Robert, 74, *77*, 81
almasti of Mongolia, 44
American Association for the Advancement of Science, 50
American Association of Physical Anthropologists, 70
American Bigfoot: Fact or Fiction (Bayanov), 175
American black bear *(Ursus americanus)*, 93, *103*, *127*, 203, 208, 210
American Board of Commissioners for Foreign Missions, 85

American Indian Movement, 82
American Museum of Natural History, 150–51
Andean mountain cat, 127
Anderson, Carl, *132*
Andrews, Peter, 104
anecdotal evidence, statistical analyses of, 211–19
Aniello, Peter, 218–19
Anthropometric Source Book, 163, 164, 177
Anthropomorpha ("man-shaped" animals), 36, *36*
Antioch (California) *Ledger*, 50
apes, *see* great apes
arboreal apes, 99, 100
Argosy magazine, 151, l6l
Athapaskan Indians, 83
Auman, John, 56
Australopithecus afarensis ("Lucy"), 169, 242, 245
axillary organs, 187

B

baboons, 36
bagpipes, 200–201, *201*
Bambenek, Greg, 197, 198, *198*
Barnum and Bailey, 193
Bayanov, Dmitri, 11, *147*, 175
bear, 203–19
  body size, 93
  distinguishing characteristics of, 205
  hibernation, 189

mistaken sasquatch sightings and, 203, 204, 205, *205*, 207–10
paws and tracks, 17, 203–204, 206–10, *206–209*
scat, 267–68
standing upright, 203, *203*, 204, *205*
vocalizations, 196
see also specific types of bear
Beebe, Frank, 167, 171
Begun, David, 91, 275
behavioral parallels of great apes and sasquatch, 179–93
Benson, Robert, *196*, 196–97, 198
Beowulf, epic of, 36
Bergman's rule, 93–94, *94*
Bering land bridge, 95–97
Berry, John, 252
Bhutan's Forestry Department, 41, *42*
Bigfoot
origins of name, 51, 223
see also specific aspects of sasquatch
"Bigfoot at 50: Evaluating a Half Century of Bigfoot Evidence," 273-74
Bigfoot Exposed (Daegling), 163
Bigfoot Field Researchers Organization (BFRO), 18, 19–20, 197, 218
Skookum Meadows expedition, 112–23
Bigfoot of the Blues (Orchard), 23
Big Footprints (Krantz), 23
Bigfoot Sasquatch Evidence (Krantz), 162
Bigfoot: The Yeti and the Sasquatch in Myth and Reality (Napier), *91*, 160–61, 169
Bili (or Bondo) ape, *43*, 43–44
Bindernagel, John, 11, 19, 116, 120, *147*, 181–82, 184, 191, 198–99, 205–206,

222–23, 224
bipedalism, 22, 52, 99–100, 117, 179, 207, 221, 245
Achilles tendon and, 122
buttocks and gluteal muscles and, 122
convergent evolution of, 90, 99, 181, 223, 224
facultative, 223
Gigantopithecus and, 99–100, 223
habitual, 223
Bittner, David, 129–30, *130*, 134–35
Blue Creek Mountain Road, footprints on, 60, *66*, 67, *68*, 226, *226*, 230, *230*, *235*, *236*
Bluff Creek
allegedly hoaxed footprints at, *55*, 55–71, *57*, *59*, *61*, *62*, *63*, *65*, 242
Patterson-Gimlin film site, *see* Patterson-Gimlin film
Boesch, Chris, 185
bonobos, or pygmy chimps, 43, 98, 99
Boorstin, Daniel, 37
Bossburg, Washington footprints, *237*, 237–39, *238*
Bourne, Geoffrey, 87, 95, 165
Bourtsev, Igor, 159, 167
breasts, 152–53, 170
Brother Bear (film), 204
Brown, John, 85–86
Brown, Ron, 116, 120, *131*
Bryan, Alan, 151
Bryant, Vaughn, 269
buk'wus motif, *73*, 75, 182, 183
Bunnell, Sterling, 262
Burns, J. W., 50, 211
buttocks

buttocks
bipedalism and pronounced, 122
imprints, 111–12, *112*
Byrne, Peter, 162–63

C

Caddy, Owen, 126, 192, 216
California Academy of Sciences, 98
camera traps, 127
Carl, G. C., 150
Catches, Pete, 83
cave dwellers, 212
Chilcutt, Jimmy, 117, 120, *254*, 254–55, *255*, 256, 257, 258
chimpanzees, 36, 98, *181*
air sacs extending out from the larynx, 200
diet, 188
drumming by, 185
facial expressions, 183, *183*
foot, *234*, 235, *236*
fossil record, *104*, 104–105, *105*
intimidation behavior, 184
Rabongo Forest, 192–93
trail markers, 114
Chinese snub-nosed langurs *(Pygathrix roxellana)*, 97–98
Chorvinsky, Mark, 69
Ciochon, Russell, 89, 92, 99
clam beaches, sasquatch sightings at, 191
Closner, Bill, 22

Coleman, Loren, 57, 63–64
Colville Indians, 86–87
convergent evolution, 90, 99, 181, 223, 224
Coon, Carleton, 91
Council, Kyle W., 176–77
Coyote, 76–77
Crew, Gerald (Jerry), 51, 55, *55*, 59–60, 61, *61*, 64, *225*, 226
Cronin, Edward, 11, 39, *40*
Crowley, Matt, 257
cryptozoology, 45–53
Cuvier (French naturalist), 41, 44

D

Daegling, David, 163–64
Dahinden, Rene, 62, 138, 145, 158, 165, 230
DeAtley, Al, 138, 144, 145, 150–51
deltoid muscles, 177
Dennett, Michael, 57
Derek, Bo, 78–79
dermatoglyphics (skin ridge detail), 22, 117, 249–59, 275
  in sasquatch tracks, *251*, *251–59*, *253–58*
diet, 98, 167, 168, 187–91, 212
  of *Gigantopithecus*, 92, 101, 167, 168
digitigrade fashion of walking, 206
Discovery Channel, 18
Disney Studios, 157, 204
Disotell, Todd, 265
Divine, Doug, 131

DNA, 265, 266–67, 270, 274, 276
Donskoy, Dmitri, 158, 160
dsonoqua, 75, *75*, 182, 183, *183*, 201
Duncan, F, 262
Durham, Michael, 126

E

Edmonds, Chuck, 108
Egan, Timothy, 68–69
elephants, 198
Emmons, G. T., *49*
Enders, Robert K., 38
evolutionary biology, 22
eyes, evolution of, 180

F

facial expressions, 182–83
Fahrenbach, Henner, 19, 69, 120–21, 122, 213–18, *214*, 262, 263, 265, 266
fat-tailed lemur, 189
feeding, *see* diet
feet, 231
  bear, paws and tracks, *see* bear
  dermatoglyphics, *see* dermatoglyphics (skin ridge detail)
  elongated heel, 231, 235, 236, *236*, 237, 246
  fixed longitudinal arch of human, 223, 229, *233*, 246
  flexion crease, 171, *171*, 243, 253
  the heel, 208, 231, 235, 236–37, 240, 246

heel pad, 207
lateral fascia, 175–76
metatarsalphalangeal joint, 243, 244, 253
midtarsal break, 171, 234–35
midtarsal flexibility, 229, 231, 233, *233*, *234*, 234–35, 245
plantar pressure, 217–18
pressure ridge, 234, 235, 246, 253
the soles, 170–71, *171*, 218, 223, 243–44
talonavicular joint, 240
toe alignment, 236, *236*
see also dermatoglyphics (skin ridge detail); footprints, sasquatch
female sasquatch, 133, *133*, 142–43, 166–67, 213
Field & Stream, 121
Field Guide to Mammal Tracking in North America, A (Halfpenny), 267
fingerprints, 249
Fingerprint Whorld, 252
First Americans, The, 75
Fish, LeRoy, 115, 116, 120, 121, 122, 197, 266
footprints, sasquatch, 22, 23–27, 51, *51*, *128*, *221–48*, *222–38*, *275*, *276*
animation factor, 228–29, *229*, 231, 234
Blue Creek Mountain Road, footprints on
Bossburg, Washington, *237*, 237–39, *238*
correlation of height and foot length, 216–17
deformity, exhibiting a, 237–40, *238*
dermatoglyphics, *see* dermatoglyphics (skin ridge detail)
flatness of, 223, 224
hoaxes, *see* hoaxes and analysis for hoaxes
length of, 223
mammals as elusive animals, 221

midfoot flexibility, 26, 27, 221, 224, 229–30, 231
Native American carved stone, *78*, 79
Oregon coast, south of Tillamook, *190*, 191
Patterson-Gimlin film, *see* Patterson-Gimlin film
from Patterson-Gimlin film site, 22, *143*, *144*, 226
pressure ridges, 221, *232*, 233
repeated appearances of particular individuals, 225–28, *226*, 254
significance of, 222–23
Six Rivers expedition, 28, 29, 32, *32*
"split ball" feature, 242–44
statistical analysis of dimensions of, 214–16, *216*
toe length, *128*, 128–29, *129*, 238–39, *241*, 241–42, *242*, *243*, 244
toe movement, 221
Walla Walla, Washington, 23–27, *24*, *213*, 227, *228*, *241*
see also feet
footprints, yeti, 36–42, *40*, *41*, *42*
forensic measurements, photographics and, 125–35
Fossey, Dian, 52, 187
fossil record
absence of, meaning of, 91, 102–104
conditions limiting, 102–106
for extinct primates, 102–103
Gigantopithecus and, 90, 101–102, 103, 105–106
Freeman, Paul, 23–26, *107*, 110, *110*, *111*, 111–12, 241, *256*, 267
video of a sasquatch, *128*, 128–31
Fremiet, Emmanuel, *77*, 78
Fuerst, Paul, 265
Fusch, Ed, 86–87

G

gait, 218, 223–24, 244–47
of bear, 204–205
human, 207, 223–24, 244–45
Patterson-Gimlin film analysis, 161, 163, 164–65, 169–70, 172–76, 174–75, *175*
Galdikas, Biruté, 52, 78, 185, 196
gastrocnemius, 177
Gavin, Michael, 76
Gee, Henry, 47–49
genitalia, male, 187
geographic information systems (GIS), 218–19
gibbons, *168*
Gigantopithecus, 49, *89*, 89–106, *90*, *91*, *92*, 167, 179–80, 180, 272
diet of, 92, 101, 167, 168
fossil record and, 90, 101–102, 103, 105–106
habitat of, 90–91, 101
link between sasquatch and, 95–97
locomotion by, 99–100, 223
Gigantopithecus blacki, *92*, 93, 101
Gigantopithecus giganteus, 93
Gilgamesh, epic of, 36
Gill, George, 94
Gimlin, Bob, 69, 70, 133–34, 137–47, *147*, 231, 274
GIS (geographic information systems), 218–19
Glickman, Jeff, 162–63
gluteal muscles, bipedalism and well-developed, 122
gluteus maximus, 177

Gombe chimps, 183
Goodall, Jane, 52, 87–88, 99, 183–84
Gorilla Carrying Off a Woman, 77, 78
gorillas, *100*, 115
  anatomy and diet, 168, 188
  foot of, *236*
  fossil record, 104–105
  intimidation behavior, 185
  palm print, *255*
  sweat glands, 187
  torso skeleton, *168*
  weight, 90
Gray Wolf, Ralph, 83
great apes, 92, 205–206, 276
  air sacs extending out from the larynx, 200, *200*
  arboreal, 99, 100
  behavioral parallels of sasquatch and, 179–93, 276
  bipedalism, *see* bipedalism
  breasts, 170
  dietary preferences, 188
  earlier ideas about, 193
  fat accumulation, 189
  foot of, *234*, 235, *236*
  fossil record, *see* fossil record
  Gigantopithecus, see Gigantopithecus
  infants, *132*
  inner toe of, 223
  intimidation behavior, 184–85
  knowledge gained in recent decades about, *192*, 192–93

Miocene, 92–93
odors, pungent, 186–87
sleeping nests, 186
temperate Pacific Northwest forests, ability to live in, 187–92
unrecognized, 43–44
see also chimpanzees; gorillas; orangutans
Green, John, 11, 60, 62–63, 67–68, 71, 75, 79, 95, 120, 137, 145, *147*, 149, 153, 155–57, *156*, 187, 211–12, 213, 230
Greenwell, Darwin, *28*
Greenwell, Richard, 28, *28*, 45
Grieve, Don, 158, 159, *159*, 160, 165
grizzly bear *(Ursus arctos)*, 93, 188–89, 203, 208, *208*
scat, 268
Groves, Colin, 167
grylloblattid (primitive form of cricket), 96

H

habitat, 97–98, 187–92
Bergman's rule (increased body size in northerly habitats), 93–94, *94*
of *Gigantopithecus*, 90–91, 101
hair, 213
color, 213
female breasts, 152–53
lack of sasquatch standard, 262
as physical evidence, 261–67, 274, 275, 276
-raising reaction, 183–84
Skookum Meadows cast and, 122
Hajicek, Doug, 17–19, *19*, 32, 131, 174–75

Halbritter, Allene, 155
Halbritter, Harry, 155
Halfpenny, Jim, 221–22, 267–68
handprints, 107–11, *108–11*
  dermatoglyphics, *see* dermatoglyphics (skin ridge detail)
Haylock, Stephen, 252
Heaton, Timothy, 104
height of sasquatch, 213
  correlation of foot length and, 216–17
  Patterson-Gimlin film and, 157, 160, 162, 163, 165–66, 177
Henry, Richard, 157
Herrero, Stephen, 268
Heryford, Dennis, *222*, *223*, 230–31, *231*
Heuvelmans, Bernard, 90–91
hibernation, 189–91
Highpine, Gayle, 82–85
Hill, W. C. Osman, *91*, 269
Hillary, Sir Edmund, 37, 39
hoaxes and analysis for hoaxes, 227–28, 237, *237*
  Bluff Creek, allegedly hoaxed footprints at, *55*, 55–71, *57*, *59*, *61*, *62*, *63*, *65*
  Freeman video, 129–30, *130*
  Patterson-Gimlin film, *see* Patterson-Gimlin film, analysis and scientific reaction to
  Skookum Meadows imprint, 118–19
Hodgson, Al, *65*, *66*, 67, 134, 137, 138, 145
Hodgson, Michael, 162
hominids, characteristics of, 90
hominoid evolution, revised ideas about, 45–48
Homo erectus, 89, 96, 246

dating of fossils, 45–46
Homo floresiensis, 46–49
Hoopa Indians, 73
Hopi, 84
Houck, W. J., 150
Hsu, Michael, 32–33
Humboldt Times, 51, 55, 73
Hunter, Stuart, 70
Husbands, Caty, 48
Hyde, Steve, 257

I

Idaho State University, 119–21, 224, 273
infants, 131, 133, *133*, 213
infrasounds, 198–201, 202
intermembral index (IM), 174, 180
International Society of Cryptozoology, 28, 45
International Wildlife Museum, 45
In the Spirit of Crazy Horse (Matthiessen), 82–83
intimidation behavior, 184–85
Iroquois (Six Nations Federation), 84
"Is There an American Abominable Snowman?", 151

J

Jablonski, Nina, 104
Jane Goodall Institute, 44
Japanese macaques *(Macaca fuscata)*, 97

Jinniushan hominid, 247
Joe Flying By, 83
Johnson, Kirk, 37
Johnson, Dr. Matthew, 69

K

King Kong, 193
Kirkpatrick Dick, 151
Kirlin, Lynn, 201–202
Klamath Knot: Explorations of Myth and Evolution, The (Wallace), 74
Kling, Benny, 252
knuckle prints, 107, *107*
knuckle-walking, 99, 107–108
Kootenai Indians, 82
Kovacs, Greg, 177
Krantz, Grover, *21*, 21–23, 27, *91*, 99–100, 108–109, 116, 119–20, 158, 160, 162, 163, 164, 188, 224, 226–27, 234, 237, 239–40, 242–43, 251, *251*, 252, 255, 269
Kwakiutl tribe, 75–76

L

Laetoli footprints, 245, *245*, 246
Lakota, or western Sioux, 82
land bridge between Asia and North America, 95–97
language centers of the brain, 180
latissimus dorsi, 177
Laughery, Bill, 23, 130, *131*

Laverty, Lyle, 231–33
LB1, 46–47
Leland, Roy, *208*, 208
Levine and Edgerton, 202
Life magazine, 150, 151
Lines, Tom, 131, *132*, 133
Linnaeus, Carl, 35, *36*, 43, 181
London *Daily Mail*, 37
London Zoo, 262
Lowenstein, Jerold, 264
"Lucy" *(Australopithecus afarensis)*, 169
Lufengpithecus chiangmuanensis, 103

M

macaques, *100, 168*
McBrearty, Sally, 104
McClarin, Jim, 155–57, *156*
McCoy, Syl, 145
Mack, Clayton, 74–75, 87, 185
McKinley, Todd, 58
McKinnon, John, 48
McLeod, Dr. James, 253
McNeely, Jeff, 11, 39, *40*
McTaggert-Cowan, Ian, 149
Manlike Monsters on Trial (Halpin and Ames), 269
Marcot, Bruce, 208–209
Markotic, Vladimir, 151
Marsh, Owen C, 49–50, *73*

Martin, Bob, 102
Martyr, Debbie, 48
Matarazzo, Mike, 177
Matheus, Paul, 102
Matthes, Steve, 63, 64
Matthiessen, Peter, 82–83, 84, 265
meat-eating, 188
media, pseudoscience and, 44–45
melatonin, 189
Meldrum, Jeff (author), 12, 119, 120, 224, *255*
  Six Rivers National Forest Expedition, *28*, 28–32
Meldrum, Mike, 23, 26
metabolic rate, 94
metatarsalphalangeal joint, 243, 244, 253
Migeod, F W. H., 76
Miocene apes, 92
Mionczynski, John, 184, 186, 191, 199
missing links, 36, 179
Mitani, John, 199
mitochondrial DNA (mtDNA), 266–67
Montagna, William, 152–53
Morehead, Ron, 202
Morton's foot, 128, *128*
Moskowitz, Kathy, 79–80
mountain gorillas, 41, 98, 100–101, *101*, 122–23
  foot of, *236*
Mt. St. Helens, 58
Mullens, Rant, 57, 58, 59, *59*
Murphy, Chris, 177, 244

N

name sasquatch, coining of, 50
Napier, John, 11, 52, 151, *160*, 160–61, 165, 169, 237–38, 242
National Wildlife magazine, 151
Native Americans, bear and, 204
Native Americans, sasquatch and, 49–50, 73–88, 193
Nature, 47
Nelson, Andrew, 175–76, *176*
neuropeptides, 199
New Scientist, 121
Newton, Craig, *266*, 266–67
New York Times, 68–69, 70
nocturnal activity pattern, 191–93, 212
Noll, Richard, 115, 119, 120, 197, 266
North American Science Institute (NASI), 162
North America's Great Ape: The Sasquatch (Bindernagel), 181–82, *182*
Northwest Anthropological Research Notes (NARN), 21, 109
NPR's Talk of the Nation/Science Friday, 87

O

odors, pungent, 186–87, 213
Ojibway, Turtle Mountain, 83–84
opiate receptor in the brain, 199
orang pendek of Indonesia, 44, 48–49, 127
orangutans, 36
  as arboreal apes, 99
  fossil record, 105

intimidation behavior, 185
vocalizations, 195–96
Orchard, Vance, 23
Oreopithecus, 179, 223
Ostman, Albert, 187
Other Origins: The Search for the Giant Ape in Human Prehistory (Ciochon), 99
overtone-singers, 202
Owen, Ray, 83

P

Pacific Northwest forests
ability of great apes to live in temperate, 98, 187–92
fossilization conditions, 103
Painted Rock, 79–80
Palma, Edward, 252
Pate, Lori and Owen, 131–33, *132*
Patrick, Ed, 56
Patterson, Roger, 20, 60, 70, 133–34, 137–47, 150–51, 167, *225*, 226, *226*, 234, 274
Patterson-Gimlin film, 12, 20–21, 95, 133–35, *134*, *140*, *142*, *162*, 180, 188, 226, *226*, *227*, 231, *232*, *233*, 237, 240, 244
analysis and scientific reaction to, 21—22, 135, 149–78, 216, 217, 235–36, 274
circumstances of, 133–35, 137–44
film frame speed, 146, 158–60, 165
summary of analyses, 178
technological advances and contemporary evaluation of, 172–78
Wallace family and, 69–70
Peabody Museum, 49–50, *73*

Peasant foot, 128
Perez, Daniel, *147*, 157, 165
Perkins, Marlin, 39
Pert, Candace, 199
Peterhans, Julian Kerbis, *104*, 105
Peterson, Ken, 157
photographics and forensic measurements, 125–35
see also Patterson-Gimlin film
Pickens, Ray, 237, *237*
piloerection, 183–84, *184*
Pinker, Ray, 262
polar bear *(Ursus maritimus)*, 93
polymerase chain reaction (PCR), 264—65
posture of sasquatch, 213
Primate News, 152
Prior, Derek, 131–33
Prohaska, Janos, 157–58
Province (Vancouver, B.C.), 70
pseudoscience, 44–45
Pyle, Robert, 69

Q

quadrupedalism, 99, 100

R

Rabongo Forest, 192
Radford, Benjamin, 273–74, 275

radioimmunassay, 264
Raincoast Sasquatch (Alley), 74
Randies, Derek, 115, 116, 120, 197, 266
Rasmussen, Wayne, 253
Reader's Digest, 151
red bear of the Himalayas *(Ursus arctos isabellinus)*, 38
red panda *(Ailurus fulgens)*, 41, 96
Red Wing (Minnesota) *Republican Eagle*, 83
Reinhold, Judge, 70–71
Rijksen, Herman, 78
Roberts, Julia, 79
Robertson, Gordon, 172
"Rocky Mountain Bigfoot," 273
Roe, William, 182
Rogers, Lynn, 17, *204*, 204–205, 210
Rubert, Dave, 60
Ruby, Robert, 85
Rugaru, 83–84

S

sagittal crest, *166*, 166–67
Sanderson, Ivan, 51, 95, 133, 137, 167, 262, 268, 269
Sanderson, Jim, 127
San Francisco Chronicle, 70
Sarmiento, Dr. Esteban, 121, 122, *122*, 133
sasquatch, *see specific aspects of sasquatch, e.g.* footprints, sasquatch
Sasquatch: Legend Meets Science, 12, 18–19, *19*, 32
Savage-Rumbaugh, Sue, 114, 115

scat (excrement or feces of an animal), 267–69, *268*
Schaller, George B., 11–13, *41*, 52, 122–23, 187
Schillinger, Ed, 56
Schmitt, Daniel, 163–64
Schulz, Adolph, *91*
Schwarzenegger, Arnold, 177
Science, 37
Scientific American, 45, 272, 275
Scientist Looks at the Sasquatch, The (Sprague and Krantz), 21
scientists and sasquatch evidence, 258–59
  current status of, 271–76
  footprints, *see* footprints, sasquatch
  ignorance of great ape biology and, 205–206, 235–36
  Patterson-Gimlin film, 149–78
  physical evidence, 261–70
  preconceptions, difficulty in abandoning, 149, 150–51, 272
  Skookum body cast, 121–23
  vocalizations, *see* vocalizations
  see also names of individuals
screams, intense, 195, 197, 198
s'cwene'y'ti, 86–87
seasonal affective disorder (SAD), 189
Seattle Times, 55, 58, 68
Shapiro, Harry, 150
Shermer, Michael, 271–73, 274
Shipton, Eric, 11, 36–37
Shuman, James B., 151
Siamese crocodile, 127
Simpson, George Gaylord, 44

Six Rivers National Forest Expedition of 1997, *28*, 28–32, *30*, *31*, 184
size of sasquatch, *see* weight and size of sasquatch
Skeptical Inquirer, 57, 163, 273
skepticism, 271–73
Skookum Meadows, 112–23
  cast of imprint from, *116*, 116–23, *117*, *118*, 266, 274, 275
  possibility of a hoax, 118–19
  recorded vocalizations, 113, 197
Slack, Mark, 29, 30, *32*, 184
sleeping nests, 185–86, *186*
Slick, Tom, 37, 58
Smithsonian Institution, 22, 151, l6l, 234
Smithsonian Magazine, 265
species, number of known, 43
spectacled bear *(Tremarctos ornatus)*, 93
Spokane Indians, 85–86
Sprague, Roderick, 21, 50
statistical analyses, 211–19
Steindorf, Reuben, 172–74, *173*, *174*
stone-throwing, 31, 184
stone tools, 47, 180
Straus, William L., Jr., 37–38, 39, 101
Stringer, Chris, 91
Sulloway, Frank J., 272
Sumerlin, "Pee Wee," *131*
Sumerlin, Wes, 23, *131*, 241
Swan, Lawrence, 38–39
sweat glands, 187, 249–50, 252
swimming, 212

Swindler, Daris, *121*, 121–22, 123, 187
Sykes, Bryan, 265, 266
Systema Natura (Linneaus), 43

T

Taft, Bill, 131
taxonomy, 35
Telegraph, 70
Terra Amata fossilized footpint, 246, *246*
Terry, Allen, 197
Thorington, Richard, Jr., 151–52
Throat Singer of Tuva, Siberia, 202
throat-singers, 202
tigers, 198
Titmus, Bob, 55, 56, 60, 62, 109, 153–55, *155* 185, *225*, 226, *227*, *232*, 233, 253, 264
TLP productions, 70
tooth clacking, 195–96
torpor, 189–91
tracks, sasquatch, *see* footprints, sasquatch
Traditional Attitudes Toward Bigfoot in Many North American Cultures (Highpine), 82–85
tree lichens, 191
trial markers, 114
trichinology, 261
Trinklein, Michael, 273
Tripp, Maurice, 64
Troglodyte, 36

Tsimshian ceremonial mask, *49*, 49–50, 73, 182
Tsimshian people, 73

U

Uganda Wildlife Authority, 192
University of British Columbia, 149

V

Vancouver Museum, *78*, 79
Van Gelder, Richard, 150
Van Herwaarden (sighting of Sumatra apeman), 48
van Roosmalen, Marc, 43
vocalizations, 185, 195–202, 275, 276
  analysis of sasquatch recordings, 197
  format structure, 196–97
  infrasounds, 198–201, 202
  intense screams, 195, 197, 198
  Skookum Meadows, recorded at, 113, 197
  tooth clacking, 195–96
  whistles, 201–202
von Koenigswald, Ralph, 89–90

W

Walker, Rev. Elkanah, 85–86
walking, *see* gait
Wallace, David Rains, 74

Wallace, Elna, 69, 70
Wallace, Michael, 68, 69, 70
Wallace, Ray, 55–71, 242, 272, 274
Wallace, Wilbur "Shorty," 55-57, 62, 68
Walla Walla, Washington footprints, 23–27, *24*, *213*, 227, *228*, *241*
Walla Walla Bigfoot, The (Orchard), 23
Ward, Michael, 36–37
warning of disaster, Native American views of Bigfoot as, 83–84
weight and size of sasquatch, 163–64, 217
  film frame speed and, 146
  Patterson-Gimlin film and, 141–42, 157, 217
Wenatchee Daily World, 85
West magazine, 151
whale communications, 198
whistles, 201–202
Wildlife Conservation Society, 11
Williams, Shelly, 44
Willow Creek Bigfoot Symposium of 2003, 146–47, *147*
Willow Creek Museum, 67
Windigo, 83, 84–85
Witherow, John, 253
wolverine, 125—26
World Book Encyclopedia, 37
Wraight, Joseph, 95, 151
Wylie, Kenneth, 167, 237

Y

Yakima Indian Reservation, 137

Yates, Dorian, 177
Year of the Sasquatch (Green), 75
Yellowstone National Park, 189
yeren of China, 44
yeti (abominable snowman), 36–42, 90–91, 265
Yokuts people, 79–81
Young, Bob, 55, 59, 60
Yunnan snub-nosed monkey *(Pygathrix bieti)*, 97–98
Yurok Indians, 73

Z

zerlog khoon in Mongolian literary sources, 36, *37*

About the Author

Jeff Meldrum, Ph.D., is an associate professor of anatomy and anthropology at Idaho State University and affiliate curator of the Idaho Museum of Natural History. He received a B.S. and M.S. in zoology from Brigham Young University, specializing in vertebrate locomotion, and a Ph.D. in anatomical sciences, with an emphasis on physical anthropology, from the State University of New York at Stony Brook in 1989. His dissertation research was on terrestrial adaptations in the feet of African monkeys and implications for the evolution of hominid bipedalism. He conducted postdoctoral work at Duke University, where for a time he turned his attention to the evolutionary history of Neotropical primates, participating in paleontological fieldwork in Argentina and Colombia. His first appointment was at Northwestern University Medical School in the Evolutionary Morphology Group. He returned to his home state of Idaho in 1993. At ISU he teaches human anatomy to health-professions graduate students, evolution, and primate studies. His research turns on vertebrate evolutionary morphology, with recurring emphasis on human bipedalism. He has published numerous scientific papers and popular articles. He has coedited two volumes on the paleontology of Idaho, coauthored a volume on evolution and religion, and he was senior editor of *From Biped to Strider: The Emergence of Modern Human Walking, Running, and Resource Transport*. His involvement in the sasquatch question began after examining fresh tracks in southeastern Washington's Blue Mountains in 1996. He has assembled and analyzed the most significant collection of sasquatch footprint casts and photographs and has conducted collaborative fieldwork throughout the Pacific Northwest and Intermountain West under the moniker the North American Ape Project. His studies of this subject have been presented at numerous professional conferences and other public appearances. He is married to Terri Meldrum, and together they have six sons.

You Have The Book Now Own The DVD

- For the first time, scientists from many disciplines put the most compelling Sasquatch evidence under the microscope and apply forensic science to the on-going mystery.
- The DVD version of this landmark documentary contains several extras
- The full length of the Patterson footage in digital format, allowing you to zoom in on individual frames with unprecedented clarity
- More of the Freeman footage
- More of the Memorial Day footage
- An FAQ on the Sasquatch mystery
- A gallery of images related to Sasquatch evidence and research

SASQUATCH

LEGEND MEETS SCIENCE

Sasquatch: Legend meets Science Companion DVD

Directed By Doug Hajicek
Narrated By Stacy Keach
Produced By Whitewolf Ent. Inc.
Filmed in 35 mm. Widescreen
Running Time Aprox. 55 minutes
NTSC Region One
Special Features Menus
Available In VHS Also
Chapter Features
One Disc

To order the DVD go to www.legendmeetsscience.com

Sasquatch: Legend Meets Science and Legend Meets Science Are Trademarks of Whitewolf Entertainment Inc.